EXHIBIT F

THE VERANDAH

ADMINISTRATIVE AMENDMENT REQUESTS

1. Deviation from Z-05-081 Condition #9 – "Perimeter Buffer Key Table" requirement of a 6' high vinyl coated chain link fence described within "Buffer #1", to allow: approximately 744 linear feet along the western boundary of Parcel 1-B (Winding River) and a 1,324 linear feet portion along the southern perimeter to provide the required planting width of 15' and the required planting material of 5 trees and 18 shrubs per 100 linear feet and to eliminate the requirement of a 6' high vinyl coated chain link fence.

Justification:

The applicant is requesting relief from the "Buffer #1" requirement to install a 6' high vinyl coated chain link fence indicated in the Buffer Key Table. The existing vegetation will meet the required planting material and buffer width (15' wide, 5 trees per 100 linear and 18 shrubs per 100 linear feet). There is no need for the fence to be installed in this area, the subject property abuts a heavily wooded area, which provides screening for the residents. This will help lessen the costs for the developer and will not cause any harm to the safety and welfare of the residents.

2. ADD2008-00028 decreased the number of single-family homes permitted within the proposed Winding River development from 28 to 21. As part of this administrative amendment the applicant is requesting to increase the number of single-family homes for Winding River from 21 to 26.

Justification:

The addition of five lots will not change the footprint of the existing development area configuration. The perimeter berm for this parcel was previously constructed and will not be altered or affected by the proposed project. The currently proposed single family lots will be reduced in width from the previously proposed lots, therefore allowing five additional lots to be constructed.

Even with the addition of these five lots to this subdivision, the overall number of allowed units within The Verandah will not be exceeded. The attached Site Plan contains a Unit Count Table that depicts this information. The granting of this request will not adversely affect the public's health, safety or welfare.

3. Request to revise the Property Development Regulation Table approved under Z-05-081 to allow (single-family, zero lot line, two-family attached, townhouse and duplex) lots abutting lakes a 5' principal structure rear yard setback and a 0' accessory structure rear yard setback.

ADD2018-00062 Lee County ePlan

Justification: The applicant is requesting this deviation to maintain consistent setbacks for future homes abutting lakes as the existing abutting lakes homes have been set back in the remainder of the development. The current Lee County LDC Sec. 10-328(a) requires a 20' lake maintenance easement adjacent to a lake with no portion of the LME located on a single-family lot. Since this relatively newly enforced requirement relocates the rear property line of lots abutting lakes within Verandah, this deviation will provide the required relief needed to maintain the current land plan for Verandah. See attached revised property development regulations table.

4. Deviation from Lee County LDC Section 10-256(b)(2)c.1 which requires that a pedestrian way must be constructed in private subdivisions internal to a development along one side of all streets internal to the residential development, to allow: no sidewalk to be constructed along the streets internal to the development.

Justification:

The applicant is requesting this deviation to provide continuity and consistency between the remaining residential parcels to be developed within The Verandah and the existing residential developments. There are currently no sidewalks provided within the individual residential parcels, however there is an existing sidewalk constructed along Verandah Boulevard for the use of the residents.

Also, the internal subdivision streets dead end and therefore have a low traffic volume and are 4' wider than the LDC required minimum of 20' providing additional room for pedestrians to navigate to the main Forum Blvd sidewalk if they choose to. The granting of this deviation will not be injurious to the public's, health, safety or welfare.

Finally, it can be reasonably determined that there is an absence of need in conjunction with the internal subdivision sidewalk requirement as follows: the facility is not likely to connect to an existing or planned facility, scheduled for construction in a five-year transportation work program, (2) is not identified on the Lee Plan transportation map 3A (Financially Feasible Highway Plan), 3C (Financially Feasible Transit Network) or 3D (Unincorporated Bikeways/Walkways Facilities Plan), and (3) the roadway frontage is more than 60 percent developed, without facilities and the remainder of the undeveloped land will not provide a continuous facility at the time of build out.

5. Deviation from Lee County LDC Section 10-329 (d)(4) which requires the banks of excavations to be sloped at a ratio not greater than six foot horizontal to one foot vertical from the top of bank to a water depth of two feet below the dry season water table, to allow all lakes remaining to be constructed within the overall Verandah development using a 4:1 slope.

Per Lee County LDC Section 10-418(2)d2, littoral plants shall be planted two foot on center which is found by dividing a littoral area by four. The following are calculations for the littoral plants:

ADD2018-00062 Lee County ePlan

Lake B:
Normally Required Littoral Plants = (1,307 LF x 0.25) x 20' / 4 = 1,634 littoral plants
Total Provided Littoral Plants (Existing + Proposed) = 4,880 littoral plants
This total provides approximately 3 times the normally required number of littoral plants. This total includes 2,908 existing littoral plants.

Lake B1:
Normally Required Littoral Plants = (2,104 LF x 0.25) x 20' / 4 = 2,630 littoral plants
Total Provided Littoral Plants (Proposed) = 4,046 littoral plants
This total provides approximately 1.5 times the normally required number of littoral plants. All 4,046 provided littoral plants will be new plants.

Justification:

SFWMD permit (36-04314-P) approved on October 10, 2002 for the overall Verandah development (1,455 acres+/-), included a condition stating that lake side slopes could be no steeper than 4:1 to a depth of two feet below control elevation. Existing lakes B and B1 were constructed with these permitted 4:1 slopes over 10 years ago but the certification was not completed. Lakes B and B1 will be slightly modified and certified with 4:1 slopes but will also be constructed with littoral plantings along the entire lake edge where the proposed modifications are occurring. These littoral plantings will be above and beyond the normally required littoral plantings. These will be planted at the quantity normally required for a littoral shelf. The portion of Lakes B and B1 that are to remain in place are already stable and contain existing plantings/vegetation that should not be disturbed. In addition, these lakes will be owned and maintained by the Verandah West Community CDD. This CDD owns and successfully maintains many other lakes within Verandah. The granting of this deviation will allow these existing lakes (namely B and B1) to be slightly modified and certified consistent with the portions of the lake bank to remain and with the other existing lakes within the community and will not cause any detriment to the public's health, safety or welfare.

ADD2018-00062 Lee County ePlan

November 2018

REQUEST SUMMARY
ADD2018-00062 -MODIFICATIONS

1) The request below was part of the application for ADD2018-00062, however the language within the approved resolution dated September 14, 2018 is stated incorrectly. The request was for future homes abutting lakes within the remainder of the development, as highlighted below. Condition Number 3 of ADD2018-00062 specifically lists "Parcel 1-B" in conjunction with the amended property development regulations, this needs to apply to "all future homes abutting lakes", not just Parcel 1-B. The Property Development Regulation Table depicted under Condition 3 of ADD2018-00062 shows a Note "(1)"for the 5' lake setback. This "(1)" needs to be removed, measurement from control elevation will not apply to the remaining lakes abutting a lake.

Correct Language:
Request to revise the Property Development Regulation Table (Condition 2.C) approved under Z-05-081 to allow (single-family, zero lot line, two-family attached, townhouse and duplex) lots abutting lakes a 5' principal structure rear yard setback and a 0' accessory structure rear yard setback.

Justification: The applicant is requesting this deviation to maintain consistent setbacks for future homes abutting lakes as the existing abutting lakes homes have been set back in the remainder of the development. The current Lee County LDC Sec. 10-328(a) requires a 20' lake maintenance easement adjacent to a lake with no portion of the LME located on a single-family lot. Since this relatively newly enforced requirement relocates the rear property line of lots abutting lakes within Verandah, this deviation will provide the required relief needed to maintain the current land plan for Verandah. See attached revised property development regulations table.


2) Applicant is requesting to modify Deviation 5 approved under ADD2018-00062 by removing "Lake B1" from this approved Deviation. This lake is strictly used for conveyance, not for surface water quality or quantity. The littoral enhancements are not required since the 4:1 lake bank slope was previously approved by ADD2008-00028.

South Florida Water Management District Permit 36-04314-P/Application 070511-25 is silent regarding Lake B1. The plans show no littoral shelves and all lake banks are 4:1. Lake B1 is shown with a Control Elevation of 4.0, but nothing is controlling the lake.

Stormwater runoff associated with the 6.34 acre controlled basin Area of subbasin A is discharging into Lake A7 and stormwater runoff associated with the 7.32 acre controlled basin area of subbasin B is discharging into Lake B. Both lakes are part of the Verandah master surface water management system, which provides the water quality and attenuation requirements

ADD2018-00062 Lee County ePlan

during the 25 year 3 day storm event. The project is in substantial compliance with the original permit.




App 030124-5 removed lake B1, and the residential lots and roadway north of the Lake within Basin B by relocating the perimeter berm. "… Lake B1 was located outside the surface water management system and provided additional conveyance for the Orange River to insure no change in the staging of the river between the pre-development and post-development conditions. The plans now identify this area as future development with only exotic removal and limited clearing of the understory.

Revised modeling of the Orange River system shows that the removal of the proposed residential improvements off-set the removal of Lake B1 from the conveyance of the Orange River. Therefore, with the limited vegetation removal in this area, sufficient conveyance is provided in the Orange River so that the change in the staging between the pre-development and post-development condition is less than 0.1 ft increase. This is consistent with the originally approved design.

ADD2018-00062 Lee County ePlan

ADD2018-00062 Lee County ePlan



Design Summary Table								
Basin Name	Control Elev.	5-Year	Min. Road	25-Year	Min. Berm	FEMA Elev.	100-Year	Min. Fin. Floor
	NGVD	NGVD	NGVD	NGVD	NGVD	NGVD	NGVD	NGVD
A (CM)	4.9	6.3	6.9	7.9	7.7	8.0	8.3	8.3
B	4.0	5.6	6.0	6.4	6.3	8.0	6.9	8.0

NOTES:
1. ALL ELEVATIONS ARE REFERENCED TO 1929 NGVD DATUM.
2. THE RESIDENTIAL LOTS SHALL BE FILLED TO MIN. ELEVATION OF 9.50 (NGVD) ⚠
3. THE MIN ROAD ELEVATION = 7.00 (NGVD); ⚠ SEE SECTIONS FOR DETAILS.

N:\Bowcom\FINAL PLAN SET-R2000\DO - PAR 102\ERP\PAR-102-GRADING-DRAINAGE.dwg (Right Hand Border) cmg Jun 19, 2008 - 2:41pm

JOHNSON ENGINEERING
2122 JOHNSON STREET
P.O. BOX 1550
FORT MYERS, FLORIDA 33902-1550
PHONE (239) 334-0046
FAX (239) 334-3661
E.B. #642 & L.B. #642
DAVID V. WILLIAMS, P.E.
Fl. License No. 57624

Verandah™

Bonita Bay Group®

REVISIONS

NO.	DESCRIPTION	DATE
3	REVISED PER 1ST LEE COUNTY COMMENTS - NEW SITE PLAN	05/08
4	REVISED PER ITEMA REQUIREMENTS AND SFWMD COMMENTS	09/08

DATE: SEPTEMBER, 2007
PROJECT NO. 20076786
FILE NO. 36-43-25
SCALE: 1" = 60'

GRADING AND DRAINAGE PLAN

SHEET NUMBER
C-08