



LEE COUNTY BOARD OF COUNTY COMMISSIONERS

ZONING
and
COMPREHENSIVE PLAN AMENDMENT HEARING
AGENDA

Wednesday, June 21, 2023

9:30AM

DCI2022-00055
Z-23-019

Pratt's Preserve

DCI2021-00050
Z-22-037A

Greenwell SR31

CPA2022-00016

Barrett Park - Adoption

CPA2023-00004

Building Height and Resiliency - Transmittal

**NOTICE OF PROPOSED AMENDMENT TO THE
LEE COUNTY COMPREHENSIVE LAND USE PLAN
(ADOPTION HEARING)**

The Lee County Board of County Commissioners will hold a public hearing to consider the adoption of proposed amendments to the Lee County Comprehensive Land Use Plan (Lee Plan) on Wednesday, June 21, 2023. The hearing will commence at 9:30 a.m., or as soon thereafter as can be heard, in the Board Chambers, 2120 Main Street in Downtown Fort Myers.

The Board proposes to adopt an ordinance amending the Lee Plan as follows:

CPA2022-00016 Barrett Park Amend Lee Plan Map 1-A to redesignate the ±20.14 acre property from the Sub-Outlying Suburban future land use category to the Urban Community future land use category.

Copies of this Notice and the proposed ordinance are available for inspection or copying during regular business hours at the Minutes Office of the Clerk of Courts of Lee County. The Minutes Office is located in the Courthouse Administration Building, 2115 Second Street, Fort Myers, Florida. This meeting is open to the public. Interested parties may appear at the meeting and be heard with respect to the proposed plan amendment. A verbatim record of the proceeding will be necessary to appeal a decision made at this hearing.

It is the intent of the Board of County Commissioners that the provisions of this Ordinance may be modified as a result of consideration that may arise during Public Hearing(s). Such modifications shall be incorporated into the final version.

Lee County will not discriminate against individuals on the basis of race, color, national origin, sex, age, disability, religion, income or family status. To request language interpretation, document translation or an ADA-qualified reasonable modification at no charge to the requestor, contact Joan LaGuardia, (239) 839-6038, Florida Relay Service 711, at least five business days in advance. El Condado de Lee brindará servicios de traducción sin cargo a personas con el idioma limitado del inglés.

CPA2022-00016

Barrett Park

**SUMMARY SHEET
CPA2022-00016 – BARRETT PARK
ADOPTION HEARING**

REQUEST:

- Amend the Future Land Use Map designation on ±20.14 acres from Sub-Outlying Suburban to Urban Community.
- Amend Table 1(b) 2045 population allocation to accommodate residential development on the subject property.

The requested map amendment is a small scale comprehensive plan amendment per Florida Statute 163.3187(1). The amendment will allow for infill redevelopment of a 200 unit multi-family affordable housing development. The site is currently developed with 50 single-family affordable housing units.

LPA PUBLIC HEARING:

The LPA discussed the proposed amendments and various merits of the case, including the community meeting requirements, improvements to Barrett Road, the relocation of existing residents, and the funding of Lee County Housing Authority.

LPA PUBLIC INPUT:

There was one public comment concerning the proposed amendment addressing advertisement of the community meeting and appropriateness of the surrounding area for the proposed amendment at the LPA Hearing.

LPA MOTION:

A motion was made to recommend that the Board of County Commissioners (BoCC) **adopt** CPA2022-00016. The motion passed 4 to 0.

RAYMOND BLACKSMITH	AYE
KEITH DEAN	AYE
DUSTIN GARDNER	ABSENT
DAWN RUSSELL	ABSENT
DON SCHROTENBOER	AYE
STAN STOUDE	AYE
HENRY ZUBA	ABSENT

STAFF RECOMMENDATION:

Staff recommends that the BoCC ***adopt*** the proposed amendment as provided in Attachment 1.

LEE COUNTY ORDINANCE NO. ____

AN ORDINANCE AMENDING THE LEE COUNTY COMPREHENSIVE PLAN TO ADOPT A SMALL SCALE AMENDMENT (CPA2022-00016) PERTAINING TO BARRETT PARK; PROVIDING FOR PURPOSE, INTENT AND SHORT TITLE; ADOPTION OF SMALL SCALE AMENDMENT TO LEE PLAN MAP 1-A, THE FUTURE LAND USE MAP AND TABLE 1(B); LEGAL EFFECT OF THE “LEE PLAN”; PERTAINING TO MODIFICATIONS THAT MAY ARISE FROM CONSIDERATION AT PUBLIC HEARING; GEOGRAPHICAL APPLICABILITY; SEVERABILITY; INCLUSION IN CODE, CODIFICATION AND SCRIVENER’S ERRORS, AND AN EFFECTIVE DATE.

WHEREAS, the Lee County Comprehensive Plan (“*Lee Plan*”) and Chapter XIII, provides for adoption of amendments to the Plan in compliance with State statutes and in accordance with administrative procedures adopted by the Board of County Commissioners (“*Board*”); and

WHEREAS, the Board, in accordance with Section 163.3181, Florida Statutes, and Lee County Administrative Code AC-13-6, provide an opportunity for private individuals to request amendment to the Future Land Use Map through a small scale amendment public hearing process; and

WHEREAS, the Local Planning Agency (“*LPA*”) held a public hearing on the adoption of the proposed amendment on May 22, 2023. At that hearing the LPA found the proposed amendment to be consistent with the Lee Plan and recommended that the Board adopt the amendment; and

WHEREAS, the Board held a public hearing for the adoption of the proposed amendment on June 21, 2023. At that hearing, the Board approved a motion to adopt proposed amendment CPA2022-00016 pertaining to Barrett Park, amending Map 1-A of the Lee Plan, the Future Land Use Map and Table 1(b). The subject parcel is located between Pondella Road and Pine Island Road.

NOW, THEREFORE, BE IT ORDAINED BY THE BOARD OF COUNTY COMMISSIONERS OF LEE COUNTY, FLORIDA, THAT:

SECTION ONE: PURPOSE, INTENT AND SHORT TITLE

The Board of County Commissioners of Lee County, Florida, in compliance with Chapter 163, Part II, Florida Statutes, and with Lee County Administrative Code AC-13-6, conducted a public hearing to review a proposed small scale amendment to the Future

Land Use Map Series of the Lee Plan. The purpose of this ordinance is to adopt the amendment to the Lee Plan discussed at that meeting and later approved by a majority of the Board of County Commissioners. The short title and proper reference for the Lee County Comprehensive Land Use Plan, as hereby amended, will continue to be the "Lee Plan." This amending ordinance may be referred to as the "Barrett Park (CPA2022-00016)".

SECTION TWO: ADOPTION OF SMALL SCALE AMENDMENT TO LEE PLAN FUTURE LAND USE MAP SERIES, MAP 1A AND TABLE 1(B)

The Lee County Board of County Commissioners hereby amends the existing Lee Plan, adopted by Ordinance Number 89-02, as amended, by adopting an amendment to the Future Land Use Map Series, Map 1A, the Future Land Use Map to designate ±20.14 acres from Sub-Outlying Suburban to Urban Community, and amend Table 1(b) 2045 Population Allocation to accommodate residential development on the subject property. The subject parcel is located between Pondella Road and Pine Island Road. The corresponding staff report and analysis, along with all attachments for this amendment, are adopted as "support documentation" for the Lee Plan.

SECTION THREE: LEGAL EFFECT OF THE "LEE PLAN"

No public or private development will be permitted except in conformity with the Lee Plan. All land development regulations and land development orders must be consistent with the Lee Plan as amended.

SECTION FOUR: MODIFICATION

It is the intent of the Board of County Commissioners that the provisions of this Ordinance may be modified as a result of consideration that may arise during Public Hearing(s). Such modifications shall be incorporated into the final version.

SECTION FIVE: GEOGRAPHIC APPLICABILITY

The Lee Plan is applicable throughout the unincorporated area of Lee County, Florida, except in those unincorporated areas included in joint or interlocal agreements with other local governments that specifically provide otherwise.

SECTION SIX: SEVERABILITY

The provisions of this ordinance are severable and it is the intention of the Board of County Commissioners of Lee County, Florida, to confer the whole or any part of the powers herein provided. If any of the provisions of this ordinance are held unconstitutional by a court of competent jurisdiction, the decision of that court will not affect or impair the remaining provisions of this ordinance. It is hereby declared to be the legislative intent of the Board of County Commissioners that this ordinance would have been adopted had the unconstitutional provisions not been included therein.

SECTION SEVEN: INCLUSION IN CODE, CODIFICATION AND SCRIVENERS' ERROR

It is the intention of the Board of County Commissioners that the provisions of this ordinance will become and be made a part of the Lee County Code. Sections of this ordinance may be re-numbered or re-lettered and the word "ordinance" may be changed to "section," "article" or other appropriate word or phrase in order to accomplish this intention; and regardless of whether inclusion in the code is accomplished, sections of this ordinance may be renumbered or relettered. The correction of typographical errors that do not affect the intent may be authorized by the County Manager, or his designee, without need of a public hearing, by filing a corrected or re-codified copy with the Clerk of the Circuit Court.

SECTION EIGHT: EFFECTIVE DATE

The small scale Lee Plan amendment adopted by this ordinance will be effective 31 days after adoption unless challenged within 30 days after adoption. If challenged within 30 days after adoption, the small scale amendment to the Lee Plan will not be effective until the Florida Department of Economic Opportunity or the Administrative Commission issues a final order determining the small scale amendment is in compliance with Florida Statutes, Section 163.3184. No development orders, development permits or land uses dependent on this amendment may be issued or commence before the amendment has become effective.

Commissioner _____ made a motion to adopt the foregoing ordinance, seconded by Commissioner _____. The vote was as follows:

Kevin Ruane	_____
Cecil L Pendergrass	_____
Raymond Sandelli	_____
Brian Hamman	_____
Mike Greenwell	_____

DONE AND ADOPTED this 21st day of June 2023.

ATTEST:
KEVIN KARNES, CLERK

LEE COUNTY BOARD OF
COUNTY COMMISSIONERS

BY: _____
Deputy Clerk

BY: _____
Brian Hamman, Chair

DATE: _____

APPROVED AS TO FORM FOR THE
RELIANCE OF LEE COUNTY ONLY

Lee County Attorney's Office

Exhibit A (Adopted by BOCC June 21, 2023):
Adopted existing Future Land Use Map 1-A
Adopted revisions to Future Land Use Map 1-A
Adopted revisions to Table 1(b)

CAO Draft May 25, 2023

STAFF REPORT FOR BARRETT PARK: CPA2022-00016

Small-Scale Map Amendment to the Lee Plan



Recommendation:

Adopt

Applicant:

Lee County Housing
Authority

Representative:

Daniel DeLisi, AICP

Property Location:

9251-9500 Westcreek Cir,
North Fort Myers, FL

Property Size:

± 20.14

Planning District:

North Fort Myers

Commissioner District:

District #4

Hearing Dates:

LPA: 05/22/23

BoCC #1: 06/21/23

Attachments:

1: Proposed Amendments

REQUEST


- Amend the Future Land Use Map designation on ±20.14 acres from Sub-Outlying Suburban to Urban Community.
- Amend Table 1(b): 2045 Population Allocation to accommodate residential development on the subject property.

SUMMARY

The requested amendments will allow for the redevelopment of an existing affordable housing neighborhood, increasing the number of dwelling units from 50 to 200.

PROJECT LOCATION

The subject property is located on Barrett Road between Pondella Road and Pine Island Road.



RECOMMENDATION

Staff recommends that the Board of County Commissioners **adopt** the requested amendments based on the analysis and findings provided in this staff report.

PART 1 STAFF DISCUSSION AND ANALYSIS

CONCURRENT REZONING

The applicant has filed a companion rezoning application (DCI2022-00063) which is being reviewed concurrently with this plan amendment request. The applicant is seeking to rezone the property from Residential Single Family (RS-1) to Residential Planned Development (RPD) to allow multifamily residential development.

Florida Statutes Chapter 163.3184(12) provides that “At the request of an applicant, a local government shall consider an application for zoning changes that would be required to properly enact any proposed plan amendment transmitted pursuant to this subsection.” This requires that Lee County provide concurrent review of the rezoning request.

Even with the recommended adoption of the proposed amendments, the applicant must demonstrate consistency with the Lee Plan, including the proposed amendments, in order for the companion rezoning to receive a favorable recommendation.

SUBJECT PROPERTY

The subject property is currently zoned RS-1 and contains 50 single-family affordable housing units. The subject property was designated as Sub-Outlying Suburban through Ordinance 07-09, the adopting ordinance of CPA2005-00040. Prior to adoption of CPA2005-00040, the property was designated as Outlying Suburban. The Outlying Suburban future land use category allows for a maximum standard density of 3 dwelling units per acre and does not allow for bonus density; however, the subject property and surrounding area were limited to 2 dwelling units per acre through specific language in the Outlying Suburban future land use category at that time.

Prior to the subject property being designated as Outlying Suburban, it was designated as Suburban. The property was within the Suburban future land use category from the inception of the Lee Plan until 1993, when Plan Amendment (PAM) 91-10 was adopted. Plan Amendment 91-10 changed the subject parcel and surrounding area from a mix of Suburban, Central Urban, and Intensive Development to Outlying Suburban. These categories have maximum standard densities ranging from 6 dwelling units an acre to 14 dwelling units an acre.

SURROUNDING PROPERTIES

Nearby uses are primarily residential homes within the Sub-Outlying Suburban and Suburban future land use categories and commercially zoned properties in the Commercial future land use category. Additional detail is provided in Table 1, below.

TABLE 1: SURROUNDING PROPERTIES INFORMATION

	Future Land Use	Zoning	Existing Use
North	Sub-Outlying Suburban	RS-1	Single-Family Residential
East	Sub-Outlying Suburban	RS-1 & RPD, approved for 32 units on ±24 acres	Single-Family Residential & Vacant
South	Suburban	RS-1 & RM-2	Single-Family Residential
West	Sub-Outlying Suburban, Commercial, & Conservation	RS-1 and CPD, approved for 575,000 SF of Commercial on ±39 acres	Single-Family Residential & DOT Operations Facility

Following the changes to the Future Land Use Map from PAM 91-10 and CPA2005-00056, the North Fort Myers Community Plan goal was adopted into the Lee Plan through the adoption of CPA2007-00056. Included in CPA2007-00056 was a Future Land Use Map amendment to redesignate approximately 85.30 acres northwest of the subject property from Suburban, Central Urban, and Sub-Outlying Suburban to Commercial and Conservation Lands. This change was intended to allow property owners to develop in a similar fashion to lands along Pine Island Road within the City of Cape Coral without having to incorporate.

DISCUSSION AND ANALYSIS – MAP 1-A: FUTURE LAND USE MAP

The applicant is requesting to amend the future land use category of the subject property from Sub-Outlying Suburban to Urban Community to allow higher density on the subject property. The current future land use category allows for up to two dwelling units per acre. The proposed future land use category would allow up to six dwelling units per acre with the opportunity to pursue bonus density of 10 dwelling units per acre.

Policy 1.1.4 describes the Urban Community future land use category as “a mixture of relatively intense commercial and residential uses.” Properties to the west are within the Commercial future land use category and have been since 2009. Parcels further north on Barrett Road, within the boundaries of the City of Cape Coral, are currently being developed as multi-family residential properties. The mixture of uses between Pine Island Road and Pondella Road are consistent with the proposed future land use category.

Policy 1.1.11 describes the Sub-Outlying Suburban future land use category as areas of low-density residential uses where infrastructure to support higher density development is not planned or in place. This description is no longer representative of the uses that are within the surrounding area or the level of public infrastructure that is available to the subject property. Multi-family housing is currently under construction within a quarter-mile of the subject parcel, and the adjacent future land use category supports high-intensity commercial uses. The “Service Availability” section of this report analyzes the infrastructure that is available to support the proposed amendment.

Objective 2.2 provides that new development should be directed “to those portions of the future urban areas where adequate public facilities exist or are assured and where compact and contiguous development patterns can be created.” The proposed amendments will allow for an in-fill development project that provides housing within an area where public facilities and services already exist. Consistent

with **Policy 4.1.1** and **Policy 4.1.2**, the subject property is able to connect to potable water and sanitary sewer, as identified in the letter of service availability from Lee County Utilities.

The proposed change to the Future Land Use Map will increase the allowable density on the subject property. As such the proposed amendment should be reviewed for consistency with **Policy 5.1.2** which prohibits residential development “where physical constraints exist, or require the density and design to be adjusted accordingly.” The Policy provides that such constraints or hazards may include flood, storm, or hurricane hazards; unstable soil or geological conditions; environmental limitations; aircraft noise; or other characteristics that may endanger the residential community. There are no characteristics of the property that would prohibit residential development. The subject property is located outside of the Coastal High Hazard Area and is primarily in FEMA Flood Zone X (shaded). A small portion of the property is located in Flood Zone AE, but the majority of the area within Flood Zone AE is in areas designated as preserve or retention on the Master Concept Plan submitted for DCI2022-00063. The proposed amendment is consistent with Policy 5.1.2.

Policy 5.1.3 directs high-density residential developments to locations near employment and shopping centers. The property is centrally located between Pine Island Road, Pondella Road, and US-41, all of which are arterial roadways with commercial uses to support potential residents. This location is also within five miles of downtown Fort Myers, a major employment center for Lee County.

The subject property falls within the North Fort Myers Community Plan Area. Consistent with **Policy 17.3.2**, the applicant conducted a public information meeting within the boundary of the North Fort Myers Community Plan Area on April 4, 2023. A summary of the meeting provided by the applicant states that there were no concerns expressed by those in attendance. At the meeting, the North Fort Myers Design Review Board voted to express support for the project.

Objective 30.1 of the Lee Plan supports the creation of affordable housing options in safe and attractive neighborhoods in the North Fort Myers Community Plan Area, consistent with the applicant’s intended use of the subject property. The amendment will accommodate 150 additional affordable units in an area that has included affordable housing for approximately three decades.

Policy 135.1.2 states that the county will work to form public-private partnerships to produce affordable housing with various non-profits, such as the applicant for the subject case. The concurrent rezoning application includes a provision for bonus density on the subject property, in which the applicant has indicated that the owner intends to provide affordable housing on the site.

Dwelling unit types in the surrounding area have been primarily single-family homes. Recently, multi-family apartments and townhomes have been approved north of the subject property on Barrett Road within the boundaries of the City of Cape Coral. An additional multi-family housing option at this location supports the Lee Plan’s goal of providing different housing options in safe and attractive neighborhoods and is consistent with recent approvals in this area. Allowing for density on the subject property that supports multi-family housing options would further **Objective 135.1, Policy 135.1.9, and Policy 158.1.9** by diversifying the mix of residential unit types within Lee County.

Based on the analysis above, redesignating the subject property from Sub-Outlying Suburban to Urban Community is found to be appropriate and consistent with the Lee Plan.

DISCUSSION AND ANALYSIS – TABLE 1(b): YEAR 2045 ALLOCATIONS

In addition to the requested Future Land Use Map Amendment, staff recommends an amendment to Table 1(b). This amendment is necessary to maintain internal consistency with the 2045 Lee County population accommodations and Policy 1.6.5 of the Lee Plan at time of development order. The Table 1(b) amendment would provide residential acres for the Urban Community future land use category in the North Fort Myers Planning District, consistent with Lee Plan **Goal 5**, which is to provide sufficient land in appropriate locations on the Future Land Use Map to accommodate the 2045 projected population of Lee County. The proposed amendments include adding seven acres of residential development to the Urban Community future land use category in Planning District 19 (North Fort Myers) and subtracting 10 residential acres in the Sub-Outlying Suburban future land use category and 42 acres in the Suburban future land use category of Planning District 19 in order to make the population balance countywide. The proposed changes to Table 1(b) are identified in Attachment 1.

SERVICE AVAILABILITY

The proposed amendment to the Future Land Use Map would increase the allowable density on the subject property. There are adequate potable water, sanitary sewer, solid waste, police, fire/EMS, and school services to accommodate anticipated development on the subject property.

Transportation: The subject property is located on Barrett Road, a two lane undivided road classified by Lee County Department of Transportation as a Major Collector.

Short Range Impacts: Proposed change will not cause any roadway link to fall below the recommended minimum acceptable Level of Service thresholds.

Long Range Impacts: Proposed change will not cause any roadway link to fall below the recommended minimum acceptable Level of Service thresholds.

Transportation concurrency is non-regulatory per Florida Statutes Section 163.3180 and Lee Plan Policy 95.1.3, which provides “Compliance with non-regulatory LOS standards will not be a requirement for continued development permitting, but will be used for facility planning purposes.”

Mass Transit: The subject property is not within ¼ mile of a fixed route corridor and is further than ¼ mile of the nearest bus stop. The 2020 Transit Development Plan does not identify the need for enhanced or additional transit services in the area.

Utilities: The subject property is within the Lee County Utilities future potable water and sanitary sewer service areas as identified on Lee Plan Maps 4-A and 4-B. Lee County Utilities has provided a letter stating that adequate potable water and sanitary sewer services are available to support the increased density.

Solid Waste: The subject property has access to solid waste services. Solid waste collection services will be provided by Lee County using the Lee County Resource Recovery Facility and the Lee-Hendry Regional Landfill.

Fire: The North Fort Myers Fire District indicated that they are capable of providing fire protection to the subject property.

EMS: The subject property has access to Emergency Medical Services. Lee County Emergency Medical Services indicated that they will be able to serve the property from Medic 7 located 2.2 miles from the property. Two other locations are within 5 miles of the property.

Police: The Lee County Sheriff's Office will provide law enforcement services primarily from the North District offices in North Fort Myers. The Sheriff indicated in a letter that development of the subject property will not affect the ability of the Lee County Sheriff's Office to provide core services at this time. The Sheriff's Office requests a Crime Prevention through Environmental Design report at the time of Development Order.

Schools: The School District of Lee County provided a letter stating that capacity is an issue within the Concurrency Service Area (CSA) at the elementary school level, however, capacity is available in the adjacent CSA.

CONCLUSIONS

The proposed amendment will support the Lee Plan's aim to provide affordable, diverse housing options, allowing a density range of 1 dwelling unit per acre to 6 dwelling units per acre, with the potential for bonus density up to 10 dwelling units per acre. The increase in density from the map amendment is consistent with the original Future Land Use Map designation on the subject property. The proposed amendments will allow the applicant to redevelop an existing affordable housing neighborhood to increase Lee County's affordable housing stock.

Staff has reviewed the proposed amendments and provides the following conclusions.

- Similar developments in the surrounding area support the proposed increase in density.
- There are adequate public services available to accommodate anticipated development on the subject property, consistent with Objective 2.2.
- The proposed amendments will not cause any roadway link to fall below the recommended Level of Service in either the 5-year or 10-year planning horizon.
- There are no characteristics of the property that would prohibit residential development, consistent with Policy 5.1.2.
- The proposed amendments will encourage and support multi-family housing options, furthering Objective 135.1, Policy 135.1.9, and Policy 158.1.9.
- The concurrent rezoning request will provide opportunities to address compatibility with surrounding uses.

For the reasons discussed in this staff report, staff recommends that the Board of County Commissioners **adopt** the proposed amendments as provided in Attachment 1.

PART 2
LOCAL PLANNING AGENCY
REVIEW AND RECOMMENDATION

DATE OF PUBLIC HEARING: May 22, 2023

A. LOCAL PLANNING AGENCY REVIEW

The applicant's representatives provided a presentation addressing the requested amendments, subject property, existing and proposed future land use categories, surrounding uses, consistency with the Lee Plan, and concurrent rezoning.

Members of the LPA had questions about: how the community meeting was advertised, what improvements to Barrett Road will be required of the development, how Lee County Housing Authority is funded, and what will happen to the current residents during construction of the multi-family buildings.

Following this, staff made a presentation addressing the requested amendments, subject property, and consistency with the Lee Plan and staff recommendation.

There was one public comment on the proposed amendment. The public comment addressed the advertisement of the community meeting and appropriateness of the surrounding area for the proposed amendment.

B. LOCAL PLANNING AGENCY RECOMMENDATION


A motion was made to recommend that the Board of County Commissioners (BoCC) ***adopt*** CPA2022-00016. The motion passed 4 to 0.

RAYMOND BLACKSMITH	<u>AYE</u>
KEITH DEAN	<u>AYE</u>
DUSTIN GARDNER	<u>ABSENT</u>
DAWN RUSSELL	<u>ABSENT</u>
DON SCHROTENBOER	<u>AYE</u>
STAN STOUDE	<u>AYE</u>
HENRY ZUBA	<u>ABSENT</u>

C. STAFF RECOMMENDATION

Staff recommends that the BoCC ***adopt*** the proposed amendment as provided in Attachment 1.

ATTACHMENT 1



CPA2022-00016




Map Generated: April 2023


- Intensive Development
- Central Urban
- Suburban
- Sub-Outlying Suburban

- Commercial
- Public Facilities
- Conservation Lands - Upland
- Wetlands

- Conservation Lands - Wetland
- City Limits
- Subject Property

Existing Future Land Use





CPA2022-00016



Map Generated: April 2023

- Intensive Development
- Central Urban
- Suburban
- Sub-Outlying Suburban

- Commercial
- Public Facilities
- Conservation Lands - Upland
- Wetlands

- Conservation Lands - Wetland
- City Limits
- Urban Community
- Subject Property

Proposed Future Land Use




Table 1(b) Year 2045 Allocations

Future Land Use Category		Unincorporated County		Planning District									
				District 1 Northeast Lee County	District 2 Boca Grande	District 3 Bonita	District 4 Fort Myers Shores	District 5 Burnt Store	District 6 Cape Coral	District 7 Captiva	District 8 Fort Myers	District 9 Fort Myers Beach	District 10 Gateway / Airport
		Existing	Proposed										
Residential By Future Land Use Category	Intensive Development	1,483	1,483	-	-	-	17	-	21	-	238	-	-
	Central Urban	13,838	13,838	-	-	-	207	-	-	-	230	-	25
	Urban Community	22,676	22,683	813	453	-	475	-	-	-	-	-	150
	Suburban	14,913	14,871	-	-	-	1,950	-	-	-	80	-	-
	Outlying Suburban	3,648	3,638	25	-	-	490	13	3	429	-	-	-
	Sub-Outlying Suburban	1,731	1,731	-	-	-	330	-	-	-	-	-	227
	Commercial	-	-	-	-	-	-	-	-	-	-	-	-
	Industrial	15	15	-	-	-	-	-	-	-	-	-	6
	Public Facilities	-	-	-	-	-	-	-	-	-	-	-	-
	University Community	503	503	-	-	-	-	-	-	-	-	-	-
	Destination Resort Mixed Use Water Dependent	8	8	-	-	-	-	-	-	-	-	-	-
	Burnt Store Marina Village	2	2	-	-	-	-	2	-	-	-	-	-
	Industrial Interchange	-	-	-	-	-	-	-	-	-	-	-	-
	General Interchange	134	134	-	-	-	-	-	-	-	-	-	35
	General Commercial Interchange	-	-	-	-	-	-	-	-	-	-	-	-
	Industrial Commercial Interchange	-	-	-	-	-	-	-	-	-	-	-	-
	University Village Interchange	-	-	-	-	-	-	-	-	-	-	-	-
	New Community	2,104	2,104	1,115	-	-	-	-	-	-	-	-	989
	Airport	-	-	-	-	-	-	-	-	-	-	-	-
	Tradeport	3	3	-	-	-	-	-	-	-	-	-	3
	Rural	7,764	7,764	2,431	-	-	800	730	-	-	-	-	-
	Rural Community Preserve	3,517	3,517	-	-	-	-	-	-	-	-	-	-
	Coastal Rural	1,338	1,338	-	-	-	-	-	-	-	-	-	-
	Outer Island	233	233	2	4	-	1	-	-	169	-	-	-
	Open Lands	2,186	2,186	153	-	-	-	257	-	-	-	-	-
	Density Reduction/ Groundwater Resource	6,974	6,974	131	-	-	-	-	-	-	-	-	-
	Conservation Lands Upland	-	-	-	-	-	-	-	-	-	-	-	-
	Wetlands	-	-	-	-	-	-	-	-	-	-	-	-
	Conservation Lands Wetland	-	-	-	-	-	-	-	-	-	-	-	-
Unincorporated County Total Residential		83,071	83,026	4,669	457	-	4,270	1,002	24	598	548	-	1,435
Commercial		8,916	8,915	300	53	-	450	27	9	125	150	-	1,216
Industrial		4,787	4,787	30	3	-	300	10	15	70	315	-	2,134
Non Regulatory Allocations		-	-										
Public		120,211	120,211	14,191	622	-	4,864	7,323	6	2,340	583	-	9,660
Active AG		21,944	21,944	5,500	-	-	240	90	-	-	-	-	2
Passive AG		13,665	13,665	5,500	-	-	615	100	-	-	-	-	465
Conservation		87,746	87,746	2,458	297	-	1,163	3,186	67	1,595	926	-	2,206
Vacant		26,180	26,224	1,145	28	-	733	766	8	103	17	-	88
Total		366,520	366,520	33,793	1,460	-	12,634	12,505	129	4,831	2,538	-	17,205
Population Distribution (unincorporated Lee County)		584,331	584,331	8,235	1,470	-	35,253	2,179	152	725	5,273	-	23,340

Table 1(b) Year 2045 Allocations

Future Land Use Category		Planning District												
		District 11 Daniels Parkway	District 12 Iona / McGregor	District 13 San Carlos	District 14 Sanibel	District 15 South Fort Myers	District 16 Pine Island	District 17 Lehigh Acres	District 18 Southeast Lee County	District 19		District 20 Buckingham	District 21 Estero	District 22 Bayshore
										North Fort Myers				
										Existing	Proposed			
Residential By Future Land Use Category	Intensive Development	-	-	-	-	801	1	30	-	376	376	-	-	-
	Central Urban	-	656	20	-	3,113	-	7,362	-	2,225	2,225	-	-	-
	Urban Community	-	978	1,255	-	863	540	17,034	-	-	7	115	-	-
	Suburban	-	2,566	2,069	-	1,202	659	-	-	6,387	6,345	-	-	-
	Outlying Suburban	1,253	438	-	-	-	502	-	-	406	396	-	90	-
	Sub-Outlying Suburban	-	-	13	-	-	-	-	-	145	145	66	-	950
	Commercial	-	-	-	-	-	-	-	-	-	-	-	-	-
	Industrial	-	3	3	-	3	-	-	-	-	-	-	-	-
	Public Facilities	-	-	-	-	-	-	-	-	-	-	-	-	-
	University Community	-	-	503	-	-	-	-	-	-	-	-	-	-
	Destination Resort Mixed Use Water Dependent	-	8	-	-	-	-	-	-	-	-	-	-	-
	Burnt Store Marina Village	-	-	-	-	-	-	-	-	-	-	-	-	-
	Industrial Interchange	-	-	-	-	-	-	-	-	-	-	-	-	-
	General Interchange	58	-	-	-	-	-	-	8	14	14	-	-	20
	General Commercial Interchange	-	-	-	-	-	-	-	-	-	-	-	-	-
	Industrial Commercial Interchange	-	-	-	-	-	-	-	-	-	-	-	-	-
	University Village Interchange	-	-	-	-	-	-	-	-	-	-	-	-	-
	New Community	-	-	-	-	-	-	-	-	-	-	-	-	-
	Airport	-	-	-	-	-	-	-	-	-	-	-	-	-
	Tradeport	-	-	-	-	-	-	-	-	-	-	-	-	-
	Rural	1,573	-	99	-	-	227	14	-	454	454	50	-	1,387
	Rural Community Preserve	-	-	-	-	-	-	-	-	-	-	3,517	-	-
	Coastal Rural	-	-	-	-	-	1,338	-	-	-	-	-	-	-
	Outer Island	-	2	-	-	-	55	-	-	-	-	-	-	-
	Open Lands	80	-	-	-	-	-	-	-	30	30	-	-	1,667
	Density Reduction/ Groundwater Resource	-	-	-	-	-	-	-	4,742	-	-	-	-	2,101
	Conservation Lands Upland	-	-	-	-	-	-	-	-	-	-	-	-	-
	Wetlands	-	-	-	-	-	-	-	-	-	-	-	-	-
	Conservation Lands Wetland	-	-	-	-	-	-	-	-	-	-	-	-	-
Unincorporated County Total Residential		2,964	4,650	3,962	-	5,982	3,322	24,440	4,750	10,035	9,991	3,748	90	6,125
Commercial		326	774	938	-	2,012	288	900	118	1,121	1,121	19	18	72
Industrial		5	198	387	-	566	67	218	215	244	244	4	2	4
Non Regulatory Allocations														
Public		3,214	4,898	6,364	-	5,883	4,831	20,267	17,992	10,117	10,117	3,052	653	3,351
Active AG		5	13	5	-	-	2,780	35	12,000	90	90	630	4	550
Passive AG		10	-	5	-	-	70	50	2,500	250	250	2,000	-	2,100
Conservation		1,677	9,786	2,232	-	211	15,489	1,077	41,028	1,607	1,607	382	1,465	895
Vacant		20	55	220	-	4	2,200	14,804	2,400	1,183	1,227	850	130	1,425
Total		8,221	20,374	14,114	-	14,658	29,047	61,791	81,003	24,649	24,649	10,684	2,362	14,523
Population Distribution (unincorporated Lee County)		14,322	44,132	53,556	-	76,582	13,431	162,245	17,369	110,722	110,722	5,951	741	8,653



APPLICATION FOR A COMPREHENSIVE PLAN AMENDMENT - MAP

ProjectName: Barrett Park

ProjectDescription: Amend the future land use map for a 20.14 acre from Sub-Outlying Suburban to Urban Community to allow for the Redevelopment of affordable housing community.

Map(s) to Be Amended: Future Land Use Mapp

State Review Process: ☒ Small-Scale Review ☐ State Coordinated Review ☐ Expedited State Review

1. **Name of Applicant:** Lee County Housing Authority

Address: 14170 Warner Circle

City, State, Zip: North Fort Myers, FL 33903

Phone Number: 239-360-8040

E-mail: marcus@lchauthority.org

2. **Name of Contact:** Daniel DeLisi, AICP

Address: 520 27th Street

City, State, Zip: West Palm Beach, FL 33407

Phone Number: 239-913-7159

E-mail: dan@delisi-inc.com

3. **Owner(s) of Record:** See applicant information.

Address: _____

City, State, Zip: _____

Phone Number: _____

E-mail: _____

4. **Property Location:**

1. SiteAddress: 9251-9500 Westcreek Cir., North Fort Myers, FL

2. STRAP(s): 04-44-24-06-00000.0010

5. **Property Information:**

Total Acreage of Property: 20.14 acres

Total Acreage Included in Request: 20.14

Total Uplands: 20.14

Total Wetlands: 0

Current Zoning: RS-1

Current Future Land Use Category(ies): Sub-Outlying Suburban

Area in Each Future Land Use Category: 20.14 acres

Existing Land Use: Residential units.

6. **Calculation of maximum allowable development under current Lee Plan:**

Residential Units/Density: 50 units

Commercial Intensity: N/A

Industrial Intensity: N/A

7. **Calculation of maximum allowable development with proposed amendments:**

Residential Units/Density: 200 Units

Commercial Intensity: N/A

Industrial Intensity: N/A

Public Facilities Impacts

NOTE: The applicant must calculate public facilities impacts based on the maximum development.

1. Traffic Circulation Analysis: The analysis is intended to determine the affect of the land use change on the Financially Feasible Highway Plan Map 3A (20-year plus horizon) and on the Capital Improvements Element (5-year horizon). Toward that end, an applicant must submit a Traffic Impact Statement (TIS) consistent with Lee County Administrative Code (AC)13-17.

- a. Proposals affecting less than 10 acres, where development parameters are contained within the Traffic Analysis Zone (TAZ) or zones planned population and employment, or where there is no change in allowable density/intensity, may be eligible for a TIS requirement waiver as outlined in the Lee County TIS Guidelines and AC-13-17. Identification of allowable density/intensity in order to determine socio-economic data for affected TAZ(s) must be coordinated with Lee County Planning staff. Otherwise a calculation of trip generation is required consistent with AC-13-17 and the Lee County TIS Guidelines to determine required components of analysis for:
 - i. Total peak hour trip generation less than 50 total trip ends – trip generation.
 - ii. Total peak hour trip generation from 50 to 300 total trip ends – trip generation, trip distribution and trip assignment (manual or Florida Standard Urban Transportation Modeling Structure (FSUTMS) analysis consistent with AC-13-17 and TIS Guidelines), short-term (5 year) and long-range (to current Lee Plan horizon year) segment LOS analysis of the nearest or abutting arterial and major collector segment(s) identified in the Transportation Inventory based on the trip generation and roadway segment LOS analysis criteria in AC-13-17. A methodology meeting is recommended prior to submittal of the application to discuss use of FSUTMS, any changes to analysis requirements, or a combined CPA and Zoning TIS short term analysis.
 - iii. Total peak hour trip generation is over 300 total trip ends - trip generation, mode split, trip distribution and trip assignment (manual or FSUTMS analysis consistent with AC-13-17 and TIS Guidelines), short-term (five-year) and long-range (to current Lee Plan horizon year) segment LOS analysis of arterial and collector segments listed in the Transportation Inventory. LOS analysis will include any portion of roadway segments within an area three miles offset from the boundary of the application legal description metes and bounds survey. LOS analysis will also include any additional segments in the study area based on the roadway segment LOS analysis criteria in AC-13-17. A methodology meeting is required prior to submittal of the application.
- b. Map amendment - greater than 10 acres -Allowable density/intensity will be determined by Lee County Planning staff.

2. Provide an existing and future conditions analysis for the following (see Policy 95.1.3):

- a. Sanitary Sewer
- b. Potable Water
- c. Surface Water/Drainage Basins
- d. Parks, Recreation, and Open Space
- e. Public Schools

Analysis for each of the above should include (but is not limited to) the following (see the Lee County Concurrency Management Report):

- a Franchise Area, Basin, or District in which the property is located
- b Current LOS, and LOS standard of facilities serving the site
- c Projected 2030 LOS under existing designation
- d Projected 2030 LOS under proposed designation
- e Existing infrastructure, if any, in the immediate area with the potential to serve the subject property
- f Improvements/expansions currently programmed in 5 year CIP, 6-10 year CIP, and long range improvements
- g Provide a letter of service availability from the appropriate utility for sanitary sewer and potable water

In addition to the above analysis, provide the following for potable water:

- a. Determine the availability of water supply within the franchise area using the current water use allocation (Consumptive Use Permit) based on the annual average daily withdrawal rate.
- b. Include the current demand and the projected demand under the existing designation, and the projected demand under the proposed designation.
- c. Include the availability of treatment facilities and transmission lines for reclaimed water for irrigation.
- d. Include any other water conservation measures that will be applied to the site (see Goal 54).

3. Provide a letter from the appropriate agency determining the adequacy/provision of existing/proposed support facilities, including:

- a. Fire protection with adequate response times
- b. Emergency medical service (EMS) provisions
- c. Law enforcement
- d. Solid Waste
- e. Mass Transit
- f. Schools

In reference to above, the applicant must supply the responding agency with the information from application items 5, 6, and 7 for their evaluation. This application must include the applicant's correspondence/request to the responding agency.

Environmental Impacts

Provide an overall analysis of the character of the subject property and surrounding properties, and assess the site's suitability for the proposed change based upon the following:

1. A map of the Plant Communities as defined by the Florida Land Use Cover and Classification system (FLUCCS).
2. A map and description of the soils found on the property (identify the source of the information).
3. A topographic map depicting the property boundaries and 100-year flood prone areas indicated (as identified by FEMA).
4. A map delineating the property boundaries on the most recent Flood Insurance Rate Map.
5. A map delineating wetlands, aquifer recharge areas, and rare & unique uplands.
6. A table of plant communities by FLUCCS with the potential to contain species (plant and animal) listed by federal, state or local agencies as endangered, threatened or species of special concern. The table must include the listed species by FLUCCS and the species status (same as FLUCCS map).

Impacts on Historic Resources

List all historic resources (including structure, districts, and/or archaeologically sensitive areas) and provide an analysis of the proposed change's impact on these resources. The following should be included with the analysis:

1. A map of any historic districts and/or sites listed on the Florida Master Site File which are located on the subject property or adjacent properties.
2. A map showing the subject property location on the archaeological sensitivity map for Lee County.

Internal Consistency with the Lee Plan

1. Discuss how the proposal affects established Lee County population projections, Lee Plan Table 1(b) and the total population capacity of the Lee Plan Future Land Use Map.
2. List all goals and objectives of the Lee Plan that are affected by the proposed amendment or that affect the subject property. This analysis should include an evaluation of all relevant policies under each goal and objective.
3. Describe how the proposal affects adjacent local governments and their comprehensive plans.

State Policy Plan and Regional Policy Plan

List State Policy Plan and Regional Policy Plan goals, strategies and actions, and policies which are relevant to this plan amendment.

Justify the proposed amendment based upon sound planning principles

Support all conclusions made in this justification with adequate data and analysis.

Planning Communities/Community Plan Area Requirements

If located within a planning community/community plan area, provide a meeting summary document of the required public informational session [Lee Plan Goal 17].

Sketch and Legal Description

The certified legal description(s) and certified sketch of the description for the property subject to the requested change. A metes and bounds legal description must be submitted specifically describing the entire perimeter boundary of the property with accurate bearings and distances for every line. The sketch must be tied to the state plane coordinate system for the Florida West Zone (North America Datum of 1983/1990 Adjustment) with two coordinates, one coordinate being the point of beginning and the other an opposing corner. If the subject property contains wetlands or the proposed amendment includes more than one land use category a metes and bounds legal description, as described above, must be submitted in addition to the perimeter boundary of the property for each wetland or future land use category.

SUBMITTAL REQUIREMENTS

Clearly label all submittal documents with the exhibit name indicated below.

For each map submitted, the applicant will be required to submit a 24"x36" version and 8.5"x11" reduced map for inclusion in public hearing packets.

MINIMUM SUBMITTAL ITEMS (3 Copies)

☐	Completed Application (Exhibit – M1)
☐	Filing Fee (Exhibit – M2)
☐	Disclosure of Interest (Exhibit – M3)
☐	Surrounding Property Owners List, Mailing Labels, and Map For All Parcels Within 500 Feet of the Subject Property (Exhibit – M3)
☐	Future Land Use Map - Existing and Proposed (Exhibit – M4)
☐	Map and Description of Existing Land Uses (Not Designations) of the Subject Property and Surrounding Properties (Exhibit – M5)
☐	Map and Description of Existing Zoning of the Subject Property and Surrounding Properties (Exhibit – M6)
☐	Signed/Sealed Legal Description and Sketch of the Description for Each FLUC Proposed (Exhibit – M7)
☐	Copy of the Deed(s) of the Subject Property (Exhibit – M8)
☐	Aerial Map Showing the Subject Property and Surrounding Properties (Exhibit – M9)
☐	Authorization Letter From the Property Owner(s) Authorizing the Applicant to Represent the Owner (Exhibit – M10)
☐	Lee Plan Analysis (Exhibit – M11)
☐	Environmental Impacts Analysis (Exhibit – M12)
☐	Historic Resources Impact Analysis (Exhibit – M13)
☐	Public Facilities Impacts Analysis (Exhibit – M14)
☐	Traffic Circulation Analysis (Exhibit – M15)
☐	Existing and Future Conditions Analysis - Sanitary Sewer, Potable Water, Surface Water/Drainage Basins, Parks and Rec, Open Space, Public Schools (Exhibit – M16)
☐	Letter of Determination For the Adequacy/Provision of Existing/Proposed Support Facilities - Fire Protection, Emergency Medical Service, Law Enforcement, Solid Waste, Mass Transit, Schools (Exhibit – M17)
☐	State Policy Plan and Regional Policy Plan (Exhibit – M18)
☐	Justification of Proposed Amendment (Exhibit – M19)
☐	Planning Communities/Community Plan Area Requirements (Exhibit – M20)

APPLICANT – PLEASE NOTE:

Once staff has determined the application is sufficient for review, 15 complete copies will be required to be submitted to staff. These copies will be used for Local Planning Agency hearings, Board of County Commissioners hearings, and State Reviewing Agencies. Staff will notify the applicant prior to each hearing or mail out to obtain the required copies.

If you have any questions regarding this application, please contact the Planning Section at (239)533-8585.


AFFIDAVIT

I, Marcus D. Goodson, certify that I am the owner or authorized representative of the property described herein, and that all answers to the questions in this application and any sketches, data, or other supplementary matter attached to and made a part of this application, are honest and true to the best of my knowledge and belief. I also authorize the staff of Lee County Community Development to enter upon the property during normal working hours for the purpose of investigating and evaluating the request made through this application.

Marcus D. Goodson 11/22/22
Signature of Applicant Date

Marcus D. Goodson
Printed Name of Applicant

STATE OF FLORIDA
COUNTY OF LEE



The foregoing instrument was sworn to (or affirmed) and subscribed before me by means of ☒ physical presence or ☐ onlinenotarization on November 22, 2022 (date) by

(name of person providing oath or affirmation), who is personally known to me or who has produced Marcus D. Goodson (type of identification) as identification.

K. Shenia Davis
Signature of Notary Public

K. Shenia Davis
(Name typed, printed or stamped)

**DISCLOSURE OF INTEREST
AFFIDAVIT**

BEFORE ME this day appeared Marcus Goodson, who, being first duly sworn and deposed says:

1. That I am the record owner, or a legal representative of the record owner, of the property that is located at 9262 Westcreek Circle, North Fort Myers, FL 33903 and is the subject of an Application for zoning action (hereinafter the "Property").

2. That I am familiar with the legal ownership of the Property and have full knowledge of the names of all individuals that have an ownership interest in the Property or a legal entity owning an interest in the Property.

[OPTIONAL PROVISION IF APPLICANT IS CONTRACT PURCHASER: In addition, I am familiar with the individuals that have an ownership interest in the legal entity that is under contract to purchase the Property.]

3. That, unless otherwise specified in paragraph 6 below, no Lee County Employee, County Commissioner, or Hearing Examiner has an Ownership Interest in the Property or any legal entity (Corporation, Company, Partnership, Limited Partnership, Trust, etc.) that has an Ownership Interest in the Property or that has contracted to purchase the Property.

4. That the disclosure identified herein does not include any beneficial Ownership Interest that a Lee County Employee, County Commissioner, or Hearing Examiner may have in any entity registered with the Federal Securities Exchange Commission or registered pursuant to Chapter 517, whose interest is for sale to the general public.

5. That, if the Ownership Interest in the Property changes and results in this affidavit no longer being accurate, the undersigned will file a supplemental Affidavit that identifies the name of any Lee County Employee, County Commissioner, or Hearing Examiner that subsequently acquires an interest in the Property.

6. Disclosure of Interest held by a Lee County Employee, County Commissioner, or Hearing Examiner.

	Name and Address	Percentage of Ownership
N/A		

Under penalty of perjury, I declare that I have read the foregoing and the facts alleged are true to the best of my knowledge and belief.



Property Owner
Marcus D. Goodson


Print Name

*****NOTE: NOTARY PUBLIC IS NOT REQUIRED FOR ADMINISTRATIVE APPROVALS*****
ALL OTHER APPLICATION TYPES MUST BE NOTARIZED


STATE OF FLORIDA
COUNTY OF LEE

The foregoing instrument was sworn to (or affirmed) and subscribed before me by means of ☒ physical presence or ☐ online notarization, on November 22, 2022 (date) by Marcus D. Goodson (name of person providing oath or affirmation), who is personally known to me or who has produced _____ (type of identification) as identification.

STAMP/SEAL
SHENIA DAVIS
NOTARY PUBLIC
Cumberland County
North Carolina
Commission Expires 2/2/2028



Signature of Notary Public




- Legend**
- Cape Coral
 - Subject Property
- Future Urban Areas**
- Sub-Outlying Suburban
 - Intensive Development
 - Industrial
 - Public Facilities
 - Commercial
 - Suburban
 - Central Urban
 - Urban Community
- Non-Urban Areas**
- Conservation Lands - Wetland
 - Wetlands

DELISI
Land Use Planning & Water Policy

Future Land Use Map
Exhibit M4a

user/community
0 500 1,000 Feet
N








**SKETCH AND DESCRIPTION
OF A PARCEL OF LAND LYING IN
SECTION 4, TOWNSHIP 44 SOUTH, RANGE 24 EAST,
LEE COUNTY, FLORIDA**

LEGAL DESCRIPTION:

A PARCEL OF LAND LYING IN THE STATE OF FLORIDA, COUNTY OF LEE, BEING A PORTION OF SECTION 4, TOWNSHIP 44 SOUTH, RANGE 24 EAST, AND BEING ALL OF BARRETT PARK ACCORDING TO THE PLAT THEREOF RECORDED IN PLAT BOOK 50, PAGES 5 THROUGH 8 OF THE PUBLIC RECORDS OF LEE COUNTY, FLORIDA AND MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BEGIN AT THE NORTHWEST CORNER OF SAID BARRETT PARK; THENCE S.89°53'53"E., ALONG THE BOUNDARY OF SAID PLAT, FOR A DISTANCE OF 1252.85 FEET TO A POINT ON THE WESTERLY RIGHT OF WAY OF BARRETT ROAD, A 60' RIGHT OF WAY; THENCE S.04°22'31"E., ALONG SAID RIGHT OF WAY AND BOUNDARY OF SAID PLAT, FOR 195.14 FEET; THENCE S.89°50'22"E., ALONG THE SOUTH RIGHT OF WAY LINE OF SAID BARRETT ROAD AND THE BOUNDARY OF SAID PLAT, FOR A DISTANCE OF 60.38 FEET; THENCE S.04°26'45"E., ALONG THE BOUNDARY OF SAID PLAT, FOR A DISTANCE OF 655.90 FEET TO THE SOUTHEAST CORNER; THENCE N.89°45'39"W., ALONG THE BOUNDARY OF SAID PLAT, FOR A DISTANCE OF 983.78 FEET; THENCE N.04°29'50"W., ALONG THE BOUNDARY OF SAID PLAT, FOR A DISTANCE OF 679.95 FEET; THENCE N.89°57'20"W., ALONG THE BOUNDARY OF SAID PLAT, FOR A DISTANCE OF 328.39 FEET; THENCE N.04°34'10"W., ALONG THE BOUNDARY OF SAID PLAT, FOR A DISTANCE OF 169.22 FEET TO THE POINT OF BEGINNING.

PARCEL CONTAINS 20.14 ACRES, MORE OR LESS.



Digitally signed
by Denis
OConnell
Date: 2023.04.06
10:12:04 -04'00'

BY: _____
DENIS J. O'CONNELL JR.
PROFESSIONAL SURVEYOR AND MAPPER
FLORIDA CERTIFICATE NO. LS# 5430

REVISED 1/16/23 -
ADD STATE PLANE COORDS
REVISED 4/06/23 -
PER COUNTY COMMENTS

NOT VALID WITHOUT THE SIGNATURE AND
THE ORIGINAL RAISED SEAL OF A FLORIDA
LICENSED SURVEYOR AND MAPPER.

NOTES:

BEARINGS ARE BASED ON THE NORTH LINE OF BARRETT PARK, PLAT BOOK 50, PAGE 5, PUBLIC RECORDS OF LEE COUNTY, FLORIDA AS BEING S 89°53'53" E.

2. DISTANCES ARE IN FEET AND DECIMALS THEREOF.


3. PARCEL IS SUBJECT TO EASEMENTS, RESERVATIONS OR RESTRICTIONS AND RIGHT-OF-WAYS (RECORDED AND UNRECORDED, WRITTEN AND UNWRITTEN).

4. RECORDING INFORMATION SHOWN HEREON RELATES TO THE PUBLIC RECORDS OF LEE COUNTY, FLORIDA.

5. THE STATE PLANE COORDINATES SHOWN HEREON ARE IN FEET, FLORIDA WEST ZONE, NORTH AMERICAN DATUM OF 1983 (1990 ADJUSTMENT) BASED UPON CONTINUOUSLY OPERATING FLORIDA PERMANENT REFERENCE NETWORK (FPRN) STATIONS MAINTAINED BY THE FLORIDA DEPARTMENT OF TRANSPORTATION.

TITLE: LEGAL DESCRIPTION			
		METRON SURVEYING & MAPPING, LLC LAND SURVEYORS · PLANNERS LB# 7071	
FILE NAME: 15318sk.dwg	FIELD BOOK/PAGE: 728/1-2,10-11	PROJECT NO.: 15318	SHEET: 1 OF 2
EXHIBIT DATE: 11/30/22	DRAWN BY: BUD	SCALE: 1" = 200'	CHECKED BY: DJO
		FILE NO. (S-T-R)	4-44-24

SKETCH AND DESCRIPTION OF A PARCEL LYING IN SECTION 4, TOWNSHIP 44 SOUTH, RANGE 24 EAST, LEE COUNTY, FLORIDA



NOTES:

BEARINGS ARE BASED ON THE NORTH LINE OF BARRETT PARK, PLAT BOOK 50, PAGE 5, PUBLIC RECORDS OF LEE COUNTY, FLORIDA AS BEING S 89°53'53" E.

2. DISTANCES ARE IN FEET AND DECIMALS THEREOF.

3. PARCEL IS SUBJECT TO EASEMENTS, RESERVATIONS OR RESTRICTIONS AND RIGHT-OF-WAYS (RECORDED AND UNRECORDED, WRITTEN AND UNWRITTEN).

4. RECORDING INFORMATION SHOWN HEREON RELATES TO THE PUBLIC RECORDS OF LEE COUNTY, FLORIDA.

5. THE STATE PLANE COORDINATES SHOWN HEREON ARE IN FEET, FLORIDA WEST ZONE, NORTH AMERICAN DATUM OF 1983 (1990 ADJUSTMENT) BASED UPON CONTINUOUSLY OPERATING FLORIDA PERMANENT REFERENCE NETWORK (FPRN) STATIONS MAINTAINED BY THE FLORIDA DEPARTMENT OF TRANSPORTATION.

LEGEND:

P.O.C. = POINT OF COMMENCEMENT
P.O.B. = POINT OF BEGINNING
R/W = ROADWAY EASEMENT
SEC = SECTION
TWP = TOWNSHIP
RNG = RANGE

TITLE: SKETCH OF DESCRIPTION



METRON
SURVEYING & MAPPING, LLC

LAND SURVEYORS-PLANNERS

LB# 7071

10970 S. CLEVELAND AVE.
SUITE #605
FORT MYERS, FLORIDA 33907
PHONE: (239) 275-8575
FAX: (239) 275-8457

www.metronfl.com

FILE NAME: 15318sk.dwg	FIELD BOOK/PAGE: 728/1-2,10-11	PROJECT NO.: 15318	SHEET: 2 OF 2
EXHIBIT DATE: 11/30/22	DRAWN BY: BUD	SCALE: 1"= 200'	CHECKED BY: DJO
			FILE NO. (S-T-R) 4-44-24

Name:

ROGER E. O'HALLORAN

Address:

COURTHOUSE P/U BOX 36

This instrument Prepared by:

O'Halloran, Johnson, Waltemyer & Huss

Address:

P.O. Box 540

Fort Myers, Florida 33902-0540

Property Appraisers Parcel Identification (Folio) Number(s):

04-44-24-00-00028.0000

Grantee(s) S.S. #s):

WARRANTY DEED
STATUTORY
F.S. 689.02

RAMCO FORM 4-1

OR2409 PG3285

3428789

SPACE ABOVE THIS LINE FOR PROCESSING DATA

SPACE ABOVE THIS LINE FOR RECORDING DATA

(Wherever used herein the terms "first party" and "second party" shall include singular and plural, heirs, legal representatives, and assigns of individuals, and the successors and assigns of corporations, wherever the context so admits or requires)

This Indenture, Made this 27th day of July, A.D. 1993,
Between **BRADLEY ASSOCIATES**, A Florida General Partnership
of the County of Pinellas, in the State of Florida, party of the first part, and
LEE COUNTY HOUSING AUTHORITY, A Public Body Corporate and Politic
created and existing under the Laws of the State of Florida,
of the County of Lee, in the State of Florida, whose post office address is
14170 Warner Circle N. W., Fort Myers, FL
party of the second part.

Witnesseth, That the said party of the first part, for and in consideration of the sum of
Dollars,
to it in hand paid by the said party of the second part, the receipt whereof is hereby acknowledged,
has granted, bargained, and sold to the said party of the second part, its successors,
following described land, situate, and being in the County of Lee, State of Florida,
to-wit:

SEE DESCRIPTION SCHEDULE ATTACHED

Documentary Tax Pd. \$ 23,237.20
Intangible Tax Pd.
\$

[Signature]
RECORD VERIFIED - CHARLIE GREEN, CLERK
By: SUSAN THOMPSON

And the said party of the first part does hereby fully warrant the title to said land, and will defend
the same against the lawful claims of all persons whomsoever.

In Witness Whereof, The said party of the first part has hereunto set its hand
and seal the day and year first above written.

Signed, sealed and delivered in the presence of:

[Signature]
Witness Signature (as to First Grantee)

SACQUELINE K. MARABLE
Printed Name

[Signature]
Witness Signature (as to First Grantee)

ARTHUR K. KIMBLE, JR.
Printed Name

Witness Signature (as to Co-Grantee, if any)

Printed Name

Witness Signature (as to Co-Grantee, if any)

Printed Name

STATE OF FLORIDA
COUNTY OF LEE

I HEREBY CERTIFY that on this day, before me, an officer duly authorized in the State aforesaid and in the County aforesaid to take
acknowledgments, personally appeared GREGORY A. NICHOLS, GENERAL MANAGER AND
ASSOCIATE PARTNER to me known to be the person described in and
who executed the foregoing instrument and he acknowledged before me that he executed the same.

WITNESS my hand and official seal in the County and State last aforesaid this 27th day of July, A.D. 1993.
I.D. Presented:



Bradley Associates, a Florida General Partnership

BY:

[Signature]
Gregory A. Nichols, General Manager and
Associate Partner

2120 Drew St., Clearwater, FL 34618
Post Office Address

Co-Grantee Signature, if any

Printed Name

Post Office Address

Notary Signature

[Signature]
SACQUELINE K. MARABLE
Printed Notary Signature
#00019631

My Commission Expires:

NOTARY PUBLIC STATE OF FLORIDA
MY COMMISSION EXP. JULY 7, 1994
BONDED THRU GENERAL INS. UND.

LEGAL DESCRIPTION

A TRACT OF LAND LYING IN THE SOUTHEAST QUARTER (S.E.1/4) OF SECTION 4, TOWNSHIP 44 SOUTH, RANGE 24 EAST, LEE COUNTY, FLORIDA, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

COMMENCING AT THE SOUTHWEST CORNER OF THE NORTHWEST QUARTER (N.W.1/4) OF THE SOUTHEAST QUARTER (S.E.1/4) OF SAID SECTION 4; THENCE RUN N.04° 34' 10" W. ALONG THE WEST LINE OF SAID FRACTION FOR 678.90 FEET TO THE POINT OF BEGINNING; THENCE CONTINUE N.04° 34' 10" W. ALONG SAID WEST LINE FOR 169.22 FEET; THENCE RUN S.89° 53' 53" E. FOR 1252.85 FEET TO A POINT ON THE WESTERLY RIGHT OF WAY OF BARRETT ROAD; THENCE RUN S.04° 22' 31" E. ALONG SAID WESTERLY RIGHT OF WAY LINE FOR 195.14 FEET TO A POINT ON THE SOUTHERLY RIGHT OF WAY LINE OF BARRETT ROAD; THENCE RUN S.89° 50' 22" E. ALONG SAID SOUTHERLY RIGHT OF WAY LINE FOR 60.38 FEET; THENCE RUN S.04° 26' 45" E. FOR 655.90 FEET; THENCE RUN N.89° 45' 39" W. FOR 983.78 FEET; THENCE RUN N.04° 29' 50" W. FOR 679.95 FEET; THENCE RUN N.89° 57' 20" W. FOR 328.39 FEET TO THE POINT OF BEGINNING.

TRACT HEREIN DESCRIBED CONTAINS 20.14± ACRES.

ALSO DESCRIBED (AND PLATTED) AS "BARRETT PARK", A SUBDIVISION, AS RECORDED IN PLAT BOOK 50, PAGES 5 THROUGH 8, PUBLIC RECORDS OF LEE COUNTY, FLORIDA.

OR 2409 PG 3286



Bradley Associates

POST OFFICE BOX 6975 • 2120 DREW STREET • CLEARWATER, FLORIDA 34618 • TELEPHONE: (813) 442-3117 • FAX: (813) 442-4231

RESOLUTION BY THE PARTNERS OF BRADLEY ASSOCIATES, A FLORIDA GENERAL PARTNERSHIP

The undersigned partners of Bradley Associates do herewith authorize Gregory A. Nichols, to act on behalf of Bradley Associates and its partners in the execution of all required documents for the sale of the project known as Barrett Park (HUD Project Number FL29-P128-004) to the Lee County Housing Authority. The undersigned being all the partners of Bradley Associates.


Agreed this _____ day of July, 1993.



Richard B. Funk


Date

STATE OF FLORIDA
COUNTY OF PINELLAS


The foregoing instrument was acknowledged before me this 16th day of July, 1993 by Richard B. Funk, Partner, on behalf of Bradley Associates, a Florida General Partnership. He is personally known to me and did not take an oath.




Jo Ane Tillman, Notary Public


Jack L. Wallick

7-15-93
Date



Sanford Goldston

7-18-93
Date

STATE OF OHIO
COUNTY OF FRANKLIN

The foregoing instrument was acknowledged before me this 19th day of July, 1993 by Jack L. Wallick and Sanford Goldston, Partners, on behalf of Bradley Associates, a Florida General Partnership.

ISABEL H. JOHNSON
NOTARY PUBLIC, STATE OF OHIO
MY COMMISSION EXPIRES NOV 25, 1993



OR2409 PG3287

CHARLIE GREEN LEE CIV. PL.
93 JUL 27 PM 4:50





Lee Plan Consistency

Exhibit - M11

The proposed map amendment is consistent with the Lee Plan and is being submitted concurrent with a Planned Development application on the subject property to allow for the development of a 200-unit multi-family community. The map amendment designates the subject property within the Urban Community Future Land Use category. Due to its location, infrastructure availability and surrounding uses the subject property is in an ideal location to provide affordable units to residents of Lee County. Below is an analysis of how the proposed rezoning implements the goals, objectives and policies of the Lee County Comprehensive Plan.

POLICY 1.1.4: The Urban Community future land use category are areas characterized by a mixture of relatively intense commercial and residential uses. The residential development in these areas will be at slightly lower densities than other future urban categories described in this plan. As vacant properties within this category are developed, the existing base of public services will need to be maintained which may include expanding and strengthening them accordingly. As in the Central Urban future land use category, predominant land uses in this category will be residential, commercial, public and quasi-public, and limited light industrial with future development encouraged to be mixed use, as described in Objective 11.1, where appropriate. The standard density range is from one dwelling unit per acre (1 du/acre) to six dwelling units per acre (6 du/acre), with a maximum total density of ten dwelling units per acre (10 du/acre). The maximum total density may be increased to fifteen dwelling units per acre (15 du/acre) utilizing Greater Pine Island Transfer of Development Units.

The Urban Community land use category allows for a standard density of up to 6 dwelling units per acre and a maximum density of 10 dwelling units per acre for the provision of affordable units. The proposed rezoning requests 200 dwelling units on 20.14 acres, just slightly less than 10 dwelling units per acre. All 200 dwelling units are being proposed as affordable units developed by the Lee County Housing Authority.

POLICY 1.1.11: The Sub-Outlying Suburban future land use category is characterized by low density residential areas. Generally the infrastructure needed for higher density development is not planned or in place. This future land use category will be placed in areas where higher densities would be incompatible or where there is a desire to retain a low-density community character. Industrial land uses are not permitted. The standard density range is from one dwelling unit per acre (1 du/acre) to two dwelling units per acre (2 du/acre). Bonus densities are not allowed.

The subject property includes 50 residential units on approximately 20 acres, a density that is greater than the Sub-Outlying Suburban land use category will allow. The Sub-Outlying future land use category was created in 2009, well after the subject property was developed. The purpose of this future land use category, as stated in Policy 1.1.11 is for areas where “the infrastructure needed for higher density development is not planned or in place”. This is simply not the case for subject property. The subject property is surrounded by and in very close proximity to urban services, included multiple schools, parks, a fire station within 1 tenth of a mile, two arterial roads, Pondella and Pine Island Roads that are running parallel and separated by less than a mile. The subject property has direct access to a collector road and is within a half mile of each of the two arterial roads. Furthermore, there are multi family developments on both the north and south sides of Barrett Road less than 1/3 mile in each direction of the subject property. While there are some remaining large lot, lower density residential units, that is more indicative of a neighborhood in transition rather than a land use pattern. The Sub-Outlying Suburban future land use category is inappropriate for the subject property as it currently exists and for the area to more efficiently utilize the urban services that exist.

POLICY 1.5.1: Permitted land uses in Wetlands consist of very low density residential uses and recreational uses that will not adversely affect the ecological functions of wetlands. All development in Wetlands must be consistent with Goal 124. The maximum density is one dwelling unit per twenty acres (1 du/20 acre) except as otherwise provided in Table 1(a) and Chapter XIII.

An approximately 4.3-acre portion of the subject property is wetland. As reflected on the Master Concept Plan, the wetland area on the subject property will remain in conservation.

OBJECTIVE 2.1: DEVELOPMENT LOCATION. Contiguous and compact growth patterns will be promoted through the rezoning process to contain urban sprawl, minimize energy costs, conserve land, water, and natural resources, minimize the cost of services, and prevent development patterns where large tracts of land are bypassed in favor of development more distant from services and existing communities.

The proposed development is an in-fill redevelopment project. The subject property already includes 50 affordable units. There is significant urban development in close proximity of the property on all sides. The location of affordable units on the urban infill property is consistent with the intent of Objective 2.1.

POLICY 2.1.1: Most residential, commercial, industrial, and public development is expected to occur within the designated future urban areas on the Future Land Use Map through the assignment of very low densities to the non-urban categories.

The proposed development is located in a “Future Urban Area” as designated on the Future Land Use Map.

OBJECTIVE 2.2: DEVELOPMENT TIMING. Direct new growth to those portions of the future urban areas where adequate public facilities exist or are assured and where compact and contiguous development patterns can be created. Development orders and permits (as defined in §163.3164, Fla. Stat.) will be granted only when consistent with the provisions of §163.3202(2)(g) and § 163.3180, Fla. Stat. and the concurrency requirements in the LDC.

The subject property is in an existing urban area where public facilities already exist. Schools, parks, fire, EMS, utilities, roads are all located in proximity to the property. Tropical Isles Elementary School and North Fort Myers Highschool are both located approximately ½ mile to the south of the subject property. North Fort Myers Fire State #2 is located approximately 0.1 miles from the subject property. In addition, the property is located in proximity to Lee Tran bus routes, ¼ mile from Bus Routes 595 and 70.

POLICY 2.2.1: Rezoning and DRI proposals will be evaluated as to the availability and proximity of the road network; central sewer and water lines; community facilities and services such as schools, EMS, fire and police protection, and other public facilities; compatibility with surrounding land uses; and any other relevant facts affecting the public health, safety, and welfare.

As stated above, the subject property has access to roads, sewer, water and community facilities. The proposed development is an urban area with urban land uses on all sides and in very close proximity to public services.

GOAL 5: RESIDENTIAL LAND USES. To accommodate the projected population of Lee County in the year 2045 in appropriate locations, guided by the Future Land Use Map, and in attractive and safe neighborhoods with a variety of price ranges and housing types.

The proposed development provides a much-needed housing type – housing priced for low and moderate income families. The proposed rezoning will implement Goal 5 through accommodating additional residential development in an existing urban area for an underserved population.

POLICY 5.1.1: Residential developments requiring rezoning and meeting Development of County Impact (DCI) thresholds must be developed as planned developments except if located within the Mixed Use Overlay.

The proposed development is being rezoned as a Planned Development in accordance with Policy 5.1.1.

POLICY 5.1.2: Prohibit residential development where physical constraints or hazards exist, or require the density and design to be adjusted accordingly. Such

constraints or hazards include but are not limited to flood, storm, or hurricane hazards; unstable soil or geologic conditions; environmental limitations; aircraft noise; or other characteristics that may endanger the residential community.

The subject property is outside of the Coastal High Hazard Area. There are no hazards or limitations on the subject property that would preclude or limit residential development. Any proposed development will have to meet the South Florida Water Management District's storm water, water quality and wetland permitting requirements. The site will be elevated to not be exposed to risk of flooding.

POLICY 5.1.3: During the rezoning process, direct high-density residential developments to locations that are near employment and shopping centers; are close to parks and schools; and are accessible to mass transit and bicycle facilities.

The proposed development is in a location in very close proximity to public facilities and employment centers. The property is within ½ mile of both an Elementary and a high school, within ¼ mile of Lee Tran service and bus stops, and approximately 3.5 miles from downtown Fort Myers, the urban hub of Lee County, and central employment base for both governmental and corporate offices.

POLICY 5.1.5: Protect existing and future residential areas from any encroachment of uses that are potentially destructive to the character and integrity of the residential environment. Requests for conventional rezonings will be denied in the event that the buffers provided in the LDC, Chapter 10, are not adequate to address potentially incompatible uses in a satisfactory manner. If such uses are proposed in the form of a planned development or special exception and generally applicable development regulations are deemed to be inadequate, conditions will be attached to minimize or eliminate the potential impacts or, where no adequate conditions can be devised, the application will be denied altogether. The LDC will continue to require appropriate buffers for new developments.

The proposed rezoning is being done as a planned development to include proper conditions that ensure compatibility with surrounding uses. The proposed development is a redevelopment project and will fit in with the surrounding urban neighborhood.

POLICY 5.1.8: Provide for adequate locations of low- and moderate-income housing through the rezoning process, the provision of public facilities and services, and the elimination of unnecessary administrative and legal barriers.

The proposed development will be comprised entirely of affordable housing, a much-needed housing product in Lee County. The property is ideally located in close proximity to public services and employment centers.

OBJECTIVE 30.1: NEIGHBORHOODS AND HOUSING. To support the creation and preservation of affordable housing options in safe and attractive neighborhoods.

The subject property is currently developed as an affordable housing community. The proposed redevelopment will allow the property to accommodate more affordable units within North Fort Myers in a safe and attractive neighborhood, consistent with Objective 30.1

POLICY 30.1.4: Encourage development of affordable housing options on property with the following characteristics: located within the Intensive Development, Central Urban, and Urban Community on the Future Land Use Map; located where central water/sewer service is available; and located within walking distance of mass transit, commercial and personal services, and parks and recreation facilities.

The proposed redevelopment is located consistent with Policy 30.1.4 and represents an opportunity for redevelopment of an affordable housing neighborhood to accommodate more affordable units. The subject property is located where central water/sewer service is available; and located within walking distance of mass transit, commercial and personal services, and parks and recreation facilities. Lee Tran service is less than a ½ mile from the subject property to both the north and the south, there are several parks located within a two-mile radius of the property, including the North Fort Myers Community Pool, with is less than a mile to the south of the subject property, and North Fort Myers Highschool which is just to the south of the pool. There are commercial areas located within 1-2 miles all along Pine Island Road, Pondella Road and US 41.

POLICY 124.1.1: Ensure that development in wetlands is limited to very low density residential uses and uses of a recreational, open space, or conservation nature that are compatible with wetland functions. The maximum density in the Wetlands category is one unit per 20 acres, except that one single family residence will be permitted on lots meeting the standards in Chapter XIII, and except that owners of wetlands adjacent to Intensive Development, General Interchange, Central Urban, Urban Community, Suburban, New Community, Outlying Suburban, and Sub-Outlying Suburban areas may transfer densities to developable contiguous uplands under common ownership (see Table 1(a)).

As reflected on the Master Concept Plan, the wetland area on the subject property will remain in conservation.

GOAL 125: WATER QUALITY. To ensure that water quality is maintained or improved for the protection of the environment and people of Lee County.

OBJECTIVE 125.1: Maintain high water quality, meeting or exceeding state and federal water quality standards.

POLICY 125.1.2: New development and additions to existing development must not degrade surface and ground water quality.

Any redevelopment of the subject property will be required to obtain an environmental resource permit from the South Florida Water Management District. As part of this permit process the applicant must demonstrate to the SFWMD that development will not degrade water quality. This "reasonable assurance" is necessary for the issuance of the federal Section 404 permit from the Department of Environmental Protection (DEP) and ensures that all State and Federal water quality standards are being met.

POLICY 125.1.3: The design, construction, and maintenance of artificial drainage systems must provide for retention or detention areas and vegetated swale systems that minimize nutrient loading and pollution of freshwater and estuarine systems.

The proposed redevelopment will include both wet and dry detention areas too meet water quality standards.

POLICY 126.1.1: Natural water system features which are essential for retention, detention, purification, runoff, recharge, and maintenance of stream flows and groundwater levels shall be identified, protected, and managed.

The natural creek on the north side of the property is being preserved and will not be impacted.

POLICY 126.1.4: Development designs must provide for maintaining or improving surface water flows, groundwater levels, and lake levels at or above existing conditions.

The natural creek on the north side of the property is being preserved and will not be impacted.

GOAL 135: MEETING HOUSING NEEDS. To provide decent, safe, and sanitary housing in suitable neighborhoods at affordable costs to meet the needs of the present and future residents of the County.

The proposed development implements Goal 135 through providing affordable housing in Lee County.

POLICY 135.1.2: The County will continue efforts to form public-private partnerships to produce affordable housing for very-low, low and moderate-income households with local private non-profit housing agencies, local for profit developers, local lenders, the Lee County Housing Authority (LCHA), and the Lee County Housing Finance Authority (LCHFA).

The plan amendment and rezoning are being proposed by the Lee County Housing Authority. It is the County's stated policy to assist the applicant in the provision of much needed affordable housing.

POLICY 135.1.4: Provide for housing bonus density to stimulate the construction of very-low, low and moderate income affordable housing in Lee County.

The proposed rezoning is requesting approval of bonus density on the property to allow for the entire property to be developed with affordable units.

POLICY 135.1.8: The County will provide through the rezoning process for the location of adequate sites for very-low, low- and moderate-income residential development including mobile homes, and housing for special needs populations as defined in § 420.0004, Fla. Stat.

This rezoning application requests that the county implement Policy 135.1.8 through the approval of the proposed affordable housing development.

OBJECTIVE 135.4: AFFORDABLE HOUSING. The County will provide adequate locations for housing for very-low, low- and moderate-income persons to meet their housing needs. Increasing the supply of affordable housing for very-low and low income housing needs will be a priority. In combination with allowing varied types of housing, the County will examine opportunities to expand affordable housing to mitigate the affordable housing needs identified in the Affordable Housing Needs Assessment.

The proposed development will implement Objective 135.4 through providing affordable housing in Lee County.

POLICY 135.4.12: Encourage affordable housing projects that are consistent with density, use, and land development provisions and located where: County concentrations of very-low and low-income households are avoided; public services are provided; and, environmentally sensitive areas are protected.

The North Fort Myers area is economically diverse, with a number of low, moderate and high income communities. The proposed redevelopment is an opportunity to provide additional affordable units in proximity to major employment centers where affordable housing is needed. Given the diverse nature of the area, the development of the proposed community does not represent a "concentration" of low-income households.

As stated above, the subject property is located in an area where full urban services are available, including utilities, recreational opportunities, schools, employment and transit.

Finally, as demonstrated in the attached protected species survey, the subject property is not located in an area of environmental sensitivity. The property is in a highly urban area and the subject site has already been developed with residential units.

POLICY 135.4.13: Lee County will examine opportunities to increase the availability of affordable housing and provide adequate sites for affordable housing through options such as: alternative use, density, and dimensional standards; expedited permit processing; dedicated funding source; inclusionary housing mitigation programs; linkage fee programs; community land trusts; and, resale controls and equity sharing.

The proposed development requests 200 units on 20.14 acres. In order to provide the product type to meet the needs of the community, additional density is needed. The proposed density request is consistent with Policy 135.4.13.

POLICY 135.4.14: Lee County will maintain the Affordable Housing Bonus Density program which provides bonus density for the provision of site-built affordable dwelling units and provides bonus density for cash contributions into the Lee County Affordable Housing Trust Fund.

The proposed planned development application includes a request for bonus density units, consistent with Policy 135.4.14.

Barrett Park 20± Acre Parcel

Section 4, Township 44 South, Range 24 East
Lee County, Florida

Protected Species Assessment

November 2022

Prepared for:

**Marcus Goodson
Lee County Housing Authority
14170 Warner Circle
North Fort Myers, FL 33903**

Prepared by:

***DexBender*
4470 Camino Real Way, Suite 101
Fort Myers, FL 33966
(239) 334-3680**

INTRODUCTION

The 20.14± acre project is located within a portion of Section 4, Township 44 South, Range 24 East, North Fort Myers, Lee County, Florida. The land is bordered to the north by single-family homes, to the east by Barrett Road and single-family homes, to the south by commercial and undeveloped land, and to the west by single-family homes and undeveloped land.

SITE CONDITIONS

The majority of the site consists of residential developments with a variety of mowed grasses and scattered trees with an established wetland conservation area in the eastern portion.

VEGETATIVE CLASSIFICATIONS

The predominant vegetation associations were mapped in the field on 2022 digital 1" = 150' scale aerial photography. The project boundary was obtained from the Lee County Property Appraiser's Website and inserted into the digital aerial. Six vegetation associations were identified using the Florida Land Use, Cover and Forms Classification System (FLUCCS). Figure 1 depicts the approximate location and configuration of these vegetation associations and Table 1 summarizes the acreages by FLUCCS Code. A brief description of each FLUCCS Code is provided below. In general, as the density of exotics increases the density and diversity of native plants in the canopy, midstory, and ground cover strata decreases.

Table 1. Acreage Summary by FLUCCS Code

FLUCCS CODE	DESCRIPTION	ACREAGE
110	Residential	13.14
411E	Pine Flatwoods invaded by Exotics (5-9%)	0.46
438E1	Mixed Hardwoods Invaded by Exotics (10-25%)	1.54
510	Stream	0.23
510D	Ditch	0.44
617E2	Mixed Wetland Hardwoods Invaded by Exotics	4.33
Total		20.14

FLUCCS Code 110, Residential

These areas contain single-family homes with mowed bahia grass (*Paspalum notatum*), pusley (*Richardia scabra*), whitehead broom (*Spermacoce verticillata*), and broomsedge (*Andropogon* sp.). Widely scattered live oak (*Quercus virginiana*) and slash pine (*Pinus elliotii*) are also present along with various ornamentals.



FLUCCS	Description	Acreage
110	Residential	13.14 ac.
411E	Pine Flatwoods Invaded by Exotics (5-9%)	0.46 ac.
438E1	Mixed hardwoods Invaded by Exotics (10-25%)	1.54 ac.
510	Stream	0.23 ac.
510D	Ditch	0.44 ac.
617E2	Mixed Wetland Hardwoods Invaded by Exotics (26-50%)	4.33 ac.
	Total	20.14 ac.

1. Property boundary was obtained from Delis Inc.
2. Mapping based on photointerpretation of 2022 aerial photography and ground truthing in November 2022.
3. Protected species assessment conducted on November 22, 2022.
4. Delineation of potential jurisdictional features is preliminary and subject to field review/approval by the applicable regulatory agencies.

December 02, 2022 8:42:12 a.m.
Drawing: LCHA-1.DWG

PERMIT USE ONLY, NOT FOR CONSTRUCTION

Barrett Park ±20 Acre Parcel

D B DEXBENDER
ENVIRONMENTAL CONSULTING
FORT MYERS 239-334-3680

FLUCCS Code 411E, Pine Flatwoods Invaded by Exotics (5-9%)

The southernmost portion of the conservation area to the east primarily consists of slash pine with earleaf acacia (*Acacia auriculiformis*) and Brazilian pepper (*Schinus terebinthifolius*).

FLUCCS Code 438E1, Mixed Hardwoods Invaded by Exotics (10-25%)

This area contains live oak, cabbage palm (*Sabal palmetto*), laurel oak (*Quercus laurifolia*), Brazilian pepper (*Schinus terebinthifolius*), guinea grass (*Panicum maximum*), caesarweed (*Urena lobata*), ragweed (*Ambrosia artemisiifolia*), whitehead broom, Spanish needles (*Bidens alba*), grape vine (*Vitis* sp.), and swamp fern (*Blechnum serrulatum*).

FLUCCS Code 510, Stream

A stream running through the northern portion of the site has banks vegetated by cabbage palm, laurel oak, and swamp fern.

FLUCCS Code 510D, Ditch

The drainage ditch within the northern portion of the site consists of coinwort (*Centella asiatica*), pennywort (*Hydrocotyle umbellata*), torpedo grass (*Panicum repens*), joint vetch (*Aeschynomene americana*), willow (*Salix caroliniana*), primrose willow (*Ludwigia* sp.), spikerush (*Eleocharis* sp.), cattail (*Typha* sp.).

FLUCCS Code 617E2, Mixed Wetland Hardwoods Invaded by Exotics

The majority of the east conservation area is inundated with 6"-12" of standing water and contains laurel oak, cabbage palm, live oak, java plum (*Syzygium cumini*), swamp fern, Brazilian pepper, wild coffee (*Psychotria nervosa*), and greenbrier (*Smilax* sp.).

SURVEY METHOD

Lee County Protected Species Ordinance No. 89-34 lists several protected species of animals that could potentially occur on-site based on the general vegetative associations found on the subject parcel. Each habitat type was surveyed for the occurrence of these and any other listed species likely to occur in the specific habitat types. The survey was conducted using meandering linear pedestrian belt transects. This survey methodology is based on the Lee County administratively approved Meandering Transect Methodology. As part of this survey all live trees and snags were inspected for the evidence of cavities that could potentially be used as roosts by the Florida bonneted bat (*Eumops floridanus*). In order to provide at least 80 percent visual coverage of habitat types listed in Ordinance No. 89-34, the transects were spaced approximately 50 feet apart. The approximate locations of all direct sighting or signs (such as tracks, nests, and droppings) of a listed species were denoted on the aerial photography. The 1" = 150' scale aerial Protected Species Assessment map (Figure 1) depicts the approximate location of the survey transects and the results of the survey. The listed species survey was conducted during the mid-morning hours of November 22nd, 2022. During the survey the weather was cool and overcast.

Species listed as endangered, threatened, or species of special concern by the FWC and/or FWS that could potentially occur on the subject parcel according to the Lee County Protected Species Ordinance are shown in Table 2. This list from the Lee County Protected Species Ordinance is general in nature, does not necessarily reflect existing conditions within or adjacent to the 20.14± acre property, and is provided for general informational purposes only.

Prior to conducting the protected species survey, a search of the FWC listed species database was conducted to determine the known occurrence of listed species in the project area. This search revealed no known protected species occurring on or immediately adjacent to the site.

Table 2. Listed Species That Could Potentially Occur On-site

FLUCCS CODE	Percent Survey Coverage	Species Name	Present	Absent
110	80	None		
411	80	Eastern Indigo Snake (<i>Drymarchon corais couperi</i>)		√
		Gopher Tortoise (<i>Gopherus polyphemus</i>)		√
		Red-cockaded Woodpecker (<i>Picoides borealis</i>)		√
		Southeastern American Kestrel (<i>Falco sparverius paulus</i>)		√
		Big Cypress Fox Squirrel (<i>Sciurus niger avicennia</i>)		√
		Florida Panther (<i>Felis concolor coryi</i>)		√
		Beautiful Pawpaw (<i>Deeringothamnus pulchellus</i>)		√
		Fakahatchee Burmannia (<i>Burmannia flava</i>)		√
		Florida Coontie (<i>Zamia floridana</i>)		√
		Satinleaf (<i>Chrysophyllum olivaeforme</i>)		√
438	80	None		
510	80	American Alligator (<i>Alligator mississippiensis</i>)		√
		Little Blue Heron (<i>Egretta caerulea</i>)		√
		Reddish Egret (<i>Egretta rufescens</i>)		√
		Roseate Spoonbill (<i>Ajaia ajaja</i>)		√
		Tricolored Heron (<i>Egretta tricolor</i>)		√
		Everglades Mink (<i>Mustela vison evergladensis</i>)		√

FLUCCS CODE	Percent Survey Coverage	Species Name	Present	Absent
510D	80	American Alligator (<i>Alligator mississippiensis</i>)		√
		Little Blue Heron (<i>Egretta caerulea</i>)		√
		Reddish Egret (<i>Egretta rufescens</i>)		√
		Roseate Spoonbill (<i>Ajaia ajaja</i>)		√
		Tricolored Heron (<i>Egretta tricolor</i>)		√
		Everglades Mink (<i>Mustela vison evergladensis</i>)		√
617	80	Little Blue Heron (<i>Egretta caerulea</i>)		√
		Tricolored Heron (<i>Egretta tricolor</i>)		√
		Florida Panther (<i>Felis concolor coryi</i>)		√

SURVEY RESULTS

Florida Bonneted Bat



No dead trees containing potential cavities entrances were identified (Figure 1). No live trees with cavities or artificial structures were observed on-site.

Other Listed Species

No other species listed by either the FWS or the FWC were observed on the site during the protected species survey conducted November 22nd, 2022. There is the potential for periodic opportunistic foraging by both listed and non-listed species of wading birds within the onsite wetlands, borrow areas, and ditches. In addition to the site inspections, a search of the FWC species database revealed no additional known protected species within or immediately adjacent to the project limits.

Y:\LCHA-1\PSA2020.docx

SECTION: 4
TOWNSHIP: 44 S
RANGE: 24 E



Map Unit	Soil Name	Acreage
39	Isles fine sand, frequently ponded	2.04 ac.
102	Cypress Lake fine sand - Urban land complex	17.28 ac.
131	Pompano fine sand - Urban land complex	0.80 ac.
141	Cocoa fine sand - Urban land complex	0.02 ac.
		Total: 20.14 ac.

Notes:
1. Property boundary is was obtained from Delisi Inc.
2. Soils information obtained from the NRCS Web Soil Survey.

December 02, 2022 8:42:12 a.m.
Drawing: LCHA-1.DWG

PERMIT USE ONLY, NOT FOR CONSTRUCTION

SECTION: 4
TOWNSHIP: 44 S
RANGE: 24 E



FLUCCS	Description	Acreage
110	Residential	13.14 ac.
411E	Pine Flatwoods Invaded by Exotics (5-9%)	0.46 ac.
438E1	Mixed hardwoods Invaded by Exotics (10-25%)	1.54 ac.
510	Stream	0.23 ac.
510D	Ditch	0.44 ac.
617E2	Mixed Wetland Hardwoods Invaded by Exotics (26-50%)	4.33 ac.
		Total 20.14 ac.

- Notes:
1. Property boundary was obtained from Delisi Inc.
 2. Mapping based on photointerpretation of 2022 aerial photography and ground truthing in November 2022.
 3. Delineation of potential jurisdictional features is preliminary and subject to field review/approval by the applicable regulatory agencies.

December 02, 2022 8:42:12 a.m.
Drawing: LCHA-1.DWG

PERMIT USE ONLY, NOT FOR CONSTRUCTION

Vegetation Map

Barrett Park ±20 Acre Parcel

BDEXBENDER
ENVIRONMENTAL CONSULTING
FORT MYERS 239-334-3680

Impacts to Historic Resources
Exhibit M-13

In accordance with the attached letter from the Division of Historic Resources, the subject property contains no known historic resources. The attached Archeological Sensitivity Map shows the property as being located partially within the Archeologically Sensitive 2 Zone.

Daniel DeLisi

From: Vovsi, Eman M. <Eman.Vovsi@DOS.MyFlorida.com>
Sent: Tuesday, November 22, 2022 11:10 AM
To: Daniel DeLisi
Subject: RE: Letter on Historic Resources
Attachments: Template_102.pdf

Completed; no cultural resources detected
Kind regards,

Eman M. Vovsi, Ph.D.
Sr. Data Base Analyst – Florida Department of State
Bureau of Historic Preservation - Florida Master Site File – Tallahassee, FL 32399-0250 – Phone:
850.245.6377 – e-mail: Eman.Vovsi@DOS.MyFlorida.com

"Due to and depending on the requested information, work load and limited staffing, it may take longer than usual to get a response. Thank you for your patience and understanding during this time."

From: Daniel DeLisi <dan@delisi-inc.com>
Sent: Monday, November 21, 2022 4:53 PM
To: FMSFILE <FMSFILE@dos.myflorida.com>
Subject: FW: Letter on Historic Resources

EMAIL RECEIVED FROM EXTERNAL SOURCE

The attachments/links in this message have been scanned by Proofpoint.

Greetings,

The attached is a request to search for previously recorded cultural resources on the subject property. I have attached the appropriate form, and a property boundary overlaid on an aerial. If you should require any additional information, please do not hesitate to contact me.


Best regards.

Daniel DeLisi, AICP
DeLisi, Inc.
dan@delisi-inc.com
www.delisi-inc.com





Source: Esri, Maxar, Earthstar Geographics, and the GIS User Community



TRAFFIC IMPACT STATEMENT

FOR

**BARRETT PARK
COMPREHENSIVE PLAN AMENDMENT
& REZONING**

(PROJECT NO. F2210.03)

PREPARED BY:
TR Transportation Consultants, Inc.
Certificate of Authorization Number: 27003
2726 Oak Ridge Court, Suite 503
Fort Myers, Florida 33901-9356
(239) 278-3090

November 19, 2022

CONTENTS

- I. INTRODUCTION**
- II. EXISTING CONDITIONS**
- III. PROPOSED COMPREHENSIVE PLAN AMENDMENT**
- IV. TRIP GENERATION**
- V. COMPREHENSIVE PLAN AMENDMENT ANALYSIS**
- VI. ZONING ANALYSIS**
- VII. CONCLUSION**

I. INTRODUCTION

TR Transportation Consultants, Inc. has conducted a traffic impact statement to fulfill requirements set forth by the Lee County Department of Community Development for projects seeking an amendment to the Comprehensive Land Use Plan and re-zoning approval. The subject site is located at 9262 Westcreek Circle in Lee County, Florida.

Figure 1 illustrates the approximate location of the subject site.

The analysis in this report will determine the impacts of change in land use on the approximately 20-acre subject site from Sub-Outlying Suburban to Urban Community as well as a zoning amendment to permit the development of up to 200 multi-family residential dwelling units. The transportation related impacts of the proposed Comprehensive Plan amendment will be assessed based on evaluation of the long range impact (20-year horizon) and short range impact (5-year horizon) the proposed amendment would have on the existing and future roadway infrastructure. The transportation related impacts of the proposed rezoning will be evaluated based on the estimated build-out year of the project and the impacts the proposed rezoning will have on the surrounding roadway infrastructure. Access to the subject site will continue be provided to Barrett Road via an existing full site access drive.

This report examines the impact of the development on the surrounding roadways. Trip generation and assignments to the various roadways within the study area will be completed and analysis conducted to determine the impacts of the development on the surrounding roadways.

II. EXISTING CONDITIONS

The subject site is currently occupied by 50 single-family dwelling units, which will be demolished as part of this project. This subject site is generally bordered by residential uses to the north, east, south and west.



Barrett Road is a two lane undivided Major Collector within the vicinity of the subject site. Barrett Road has a posted speed limit of 30 mph and is under the jurisdiction of the Lee County Department of Transportation.

III. PROPOSED COMPREHENSIVE PLAN AMENDMENT

The proposed Map Amendment would change the future land use designation on the approximate 20-acre subject site from Sub-Outlying Suburban to Urban Community. For the trip generation purposes, the permitted development under the existing land use category was assumed to consist of the 50 single-family dwelling units that are currently on site. Under the proposed land use change, the site would be allowed to be developed with up to 200 multi-family residential dwelling units based on 10 units per acre. **Table 1** summarizes the land use that is constructed today under the existing land use designation and the intensity of uses that would be permitted under the proposed land use designation.

Table 1
Comprehensive Plan Amendment
Land Uses

Existing/ Proposed	Land Use Category	Intensity
Existing	Sub-Outlying Suburban	50 Single-Family Dwelling Units *
Proposed	Urban Community	200 Multi-Family Dwelling Units

*Existing development on site.

IV. TRIP GENERATION

The trip generation for the proposed development was determined by referencing the Institute of Transportation Engineer's (ITE) report, titled *Trip Generation Manual*, 11th Edition. Land Use Code 210 (Single-Family Detached Housing) was utilized for the trip generation purposes of the existing single-family residential uses on site. Land Use Code 220 (Multifamily Housing Low-Rise) was utilized for the generation purposes of the proposed development under the proposed Urban Community land use category. The

equations from these land uses are included in the Appendix of this report for reference. **Table 2** outlines the anticipated weekday AM and PM peak hour trip generation based on the existing development on site. **Table 3** outlines the anticipated weekday AM and PM peak hour trip generation based on the proposed land use category. The daily trip generation is also indicated in both tables.

Table 2
Comprehensive Plan Amendment
Trip Generation Based on Existing Use

Land Use	Weekday AM Peak Hour			Weekday PM Peak Hour			Daily (2-way)
	In	Out	Total	In	Out	Total	
Single-Family Detached Housing (50 Dwelling Units)	10	30	40	33	19	52	533

Table 3
Comprehensive Plan Amendment
Trip Generation Based on Proposed Land Use

Land Use	Weekday AM Peak Hour			Weekday PM Peak Hour			Daily (2-way)
	In	Out	Total	In	Out	Total	
Multifamily Housing Low-Rise (200 Dwelling Units)	20	65	85	67	40	107	1,357

Table 4 indicates the trip generation difference between the existing development on site and the development that would be permitted under the proposed land use category.

Table 4
Comprehensive Plan Amendment
Trip Generation – Resultant Trip Change

Land Use	A.M. Peak Hour			P.M. Peak Hour			Daily (2-way)
	In	Out	Total	In	Out	Total	
Proposed Land Use	20	65	85	67	40	107	1,357
Existing Land Use	-10	-30	-40	-33	-19	-52	-533
Resultant Trip Change	+10	+35	+45	+34	+21	+55	+824

The positive number shown as the resultant trip change in Table 4 indicates that the trip generation will be increased as a result of this land use change action.

V. COMPREHENSIVE PLAN AMENDMENT ANALYSIS

As mentioned previously, the proposed Map Amendment would change the future land use designation on the approximate 20-acre subject site from Sub-Outlying Suburban to Urban Community. The transportation related impacts of the proposed Comprehensive Plan Amendment were evaluated pursuant to the criteria in the application document. This included an evaluation of the long range impact (20-year horizon) and short range impact (5-year horizon) the proposed amendment would have on the existing and future roadway infrastructure.

Long Range Impacts (20-year horizon)

The Lee County Metropolitan Planning Organization's (MPO) 2045 Long Range Transportation Plan was reviewed to determine if any future roadway improvements were planned in the vicinity of the subject site. Based on the review, Pine Island Road west of Hancock Creek Boulevard was shown to be widened to a six-lane facility. There are no other improvements within the vicinity of the subject site on the Long Range Transportation Plan.

The Lee County Metropolitan Planning Organization's (MPO) long range transportation plan along with the FDOT District One travel model were also reviewed in order to determine the impacts the amendment would have on the surrounding area. The base 2045 loaded network volumes were determined for the roadways within the study area. The PM peak hour trips to be generated from the project as shown in Table 3 were then added to the projected 2045 background volumes. The Level of Service for those roadways were then evaluated. The Level of Service threshold volumes for County maintained roadways were obtained from *Lee County's Generalized Peak Hour Directional Service Volumes* table. The Level of Service threshold volumes for State maintained roadways were derived based on the *Florida Department of Transportation Generalized Peak Hour Directional Volumes for Florida's Urbanized Areas, Table 7*. Both documents are attached to the Appendix of this report for reference.

The results of the analysis indicate that the proposed change to the land use category on the subject parcel will not cause any roadway link to fall below the recommended minimum acceptable Level of Service thresholds as recommended in Policy 37.1.1 of the Lee County Comprehensive Plan. US 41 south of Hancock Bridge Parkway and Business 41 south of Pondella Road were both shown to operate below the adopted LOS standards in 2045 in the Background traffic conditions and not as a result of adding the minimal number of additional trips from the project. Therefore, no changes to the adopted long range transportation plan are required as result of the proposed land use change. Attached **Table 1A** and **Table 2A** reflect the Level of Service analysis based on the 2045 conditions.

Short Range Impacts (5-year horizon)

The 2022/2022-2025/2026 Lee County Transportation Capital Improvement Plan and the 2023-2027 Florida Department of Transportation Adopted Work Program were reviewed to determine the short term impacts the proposed land use change would have on the surrounding roadways. Based on the review, there are no programmed improvements in the vicinity of the subject site.

The proposed map amendment will increase the overall trip generation potential of the subject site by approximately 55 vehicles during the weekday P.M. peak hour. **Table 3A** and **Table 4A** attached to this report indicate the projected 5-year planning Level of Service on the area roadways based on the uses that would be permitted under the proposed land use change. The existing peak hour, peak season, peak direction traffic volumes on the various roadway links maintained by Lee County were obtained from the most recent Lee County *Public Facilities Level of Service and Concurrency Report*. The existing peak hour, peak season, peak direction traffic volumes for state maintained roadways were obtained from the most recent *FDOT's District One LOS Spreadsheet*.

The existing peak hour, peak season, peak direction traffic volumes were then factored by the appropriate annual growth rates in order to obtain the 2027 background traffic conditions on the area roadway network. The growth rates for each roadway were calculated based on historical traffic data obtained from the FDOT's *Florida Traffic Online* resource as well as the traffic data from the latest *Lee County Traffic Count Report*. Due to lack of historical traffic data on Barrett Road, an annual growth rate of 2% compounded annually was assumed. Based on the projected traffic distribution, the roadway link data was analyzed for the year 2027 without the proposed amendment and year 2027 with the proposed amendment. Traffic data obtained from the aforementioned Lee County and FDOT resources is attached to the Appendix of this report for reference.

The results of the analysis indicate that the addition of the trips as a result of the proposed amendment to the projected 2027 volumes will not cause any roadway links to fall below the minimum acceptable Level of Service standards. US 41 south of Hancock Bridge Parkway and Pine Island Road west of Del Prado Boulevard were both shown to operate below the adopted LOS standards in 2027 in the Background traffic conditions and not as a result of adding the minimal number of additional trips from the project. All remaining analyzed roadways were shown operate within their adopted minimum Level of Service standards. Therefore, no modifications will be necessary to the Lee County or FDOT short term capital improvement programs.


VI. ZONING ANALYSIS

An analysis was also completed to support the rezoning on the approximate 20-acre subject site to allow a development of up to 200 multi-family residential dwelling units. The trips the proposed development is anticipated to generate, as shown in the Table 3, were assigned to the surrounding roadway network. The trips were assigned based upon the routes drivers are anticipated to utilize to approach the subject site. **Figure 2** illustrates the anticipated trip distribution. Also shown in Figure 2, is the site traffic assignment of the proposed development.

F2210.03



BARRETT RD.



SITE

LEGEND

- ← 000 WEEKDAY AM PEAK HOUR SITE TRAFFIC
- ← (000) WEEKDAY PM PEAK HOUR SITE TRAFFIC
- ← 20% → PERCENT TRIP DISTRIBUTION

In order to determine which roadway segments surrounding the site will be significantly impacted as outlined in the Lee County Traffic Impact Statement Guidelines, **Table 5A**, contained in the Appendix, was created. This table indicates which roadway links will experience a significant impact as a result of the added development traffic. Significant impact is defined as any roadway projected to experience greater than 10% of the Peak Hour – Peak Direction Level of Service “C” volumes. The Level of Service threshold volumes were derived based on the Lee County’s *Generalized Peak Hour Directional Service Volumes* table. Based on the information contained within Table 5A, Barrett Road south of the site is the only roadway segment that is anticipated to be significantly impacted as a result of the proposed development.

Level of Service Analysis

The future Level of Service analysis was based on projected build-out year of the project, or year 2027. Based on this horizon year, a growth rate was applied to the existing traffic conditions for all roadway links in the study area. Due to lack of historical traffic data on Barrett Road, a minimum annual growth rate of 2% compounded annually was assumed. Based on the project distribution illustrated on Table 5A, the link data was analyzed for the year 2027 without the development and year 2027 with the development.

Table 6A in the Appendix of the report indicates the methodology utilized to obtain the year 2027 background and build-out traffic volumes. The existing peak hour, peak season, peak direction traffic volumes on the roadway links maintained by the Lee County were obtained from the most recent Lee County *Public Facilities Level of Service and Concurrency Report*. The existing peak hour, peak season, peak direction traffic volumes were then factored by the appropriate annual growth rates in order to obtain the 2027 background traffic conditions on the area roadway network.

Figure 3 indicates the year 2027 peak hour – peak direction traffic volumes and Level of Service for the various roadway links within the study area. Noted on Figure 3 is the peak hour – peak direction volume and Level of Service of each link should no development occur on the subject site and the peak hour – peak direction volume and Level of Service for the weekday A.M. and P.M. peak hours with the development traffic added to the roadways. This figure is derived from Table 6A contained in the Appendix.

As can be seen from Figure 3, the roadway links analyzed as part of this report will not be adversely impacted as a result of the proposed rezoning request. Barrett Road was shown to operate at acceptable Level of Service “C” in 2027 both with and without the proposed development. Therefore, roadway capacity improvements will not be warranted as a result of the additional traffic to be generated by the proposed rezoning request.

Intersection Analysis

Intersection analysis was performed at the proposed site access drive on Barrett Road utilizing the latest version of the *Highway Capacity Software (HCS[®])*. The analysis was based on the projected 2027 weekday A.M. and P.M. peak hour traffic conditions with the project traffic conditions. Traffic counts were conducted at the intersection of Barrett Road and Westcreek Circle between the hours of 7:00 to 9:00 A.M. and 4:00 to 6:00 P.M. on November 3, 2022. The peak hour turning movements were then adjusted for peak season conditions based on the peak season factor data as provided by FDOT in their *Florida Traffic Online* resource. The FDOT peak season correction factor is included in the Appendix of this report for reference.

The existing weekday peak hour traffic volumes were then increased by a growth rate factor to determine the projected 2027 background turning movement volumes. The turning volumes projected to be added to the intersection as illustrated on Figure 2 were then added to the 2027 background volumes to estimate the future 2027 traffic volumes with the project. These volumes are based on the data from the spreadsheets contained in the Appendix of this report titled *Development of Future Year Background Turning Volumes*.

F2210.03

BARRETT RD.

118 - "C"
(138 - "C")
[138 - "C"]



SITE

118 - "C"
(164 - "C")
[165 - "C"]

LEGEND

XXX - "C" 2027 PEAK SEASON PEAK HOUR PEAK DIRECTION
EXISTING TRAFFIC AND LEVEL OF SERVICE
DESIGNATION

(XXX - "C") 2027 PEAK SEASON PEAK HOUR PEAK DIRECTION
EXISTING PLUS AM PEAK DIRECTION PROJECT TRAFFIC
AND LEVEL OF SERVICE DESIGNATION

[XXX - "C"] 2027 PEAK SEASON PEAK HOUR PEAK DIRECTION
EXISTING PLUS PM PEAK DIRECTION PROJECT
TRAFFIC AND LEVEL OF SERVICE DESIGNATION

The results of the intersection analysis indicate all approaches to operate at an acceptable Level of Service in 2027 with the project trips added to the intersection in the AM and PM peak hour traffic conditions. Therefore, no intersection capacity improvements are warranted as a result of this analysis. *HCS*® summary sheets are attached to the Appendix of this report for reference.

VII. CONCLUSION

The proposed project is located at 9262 Westcreek Circle in Lee County, Florida. Based upon the roadway link Level of Service analysis conducted as a part of this report for both the Comprehensive Plan amendment and rezoning request, the development of the subject site meets the requirements set forth by the Lee County Comprehensive Plan and Land Development Code in that there is sufficient capacity available to accommodate the new trips that will be generated by the proposed development. Therefore, no roadway capacity improvements will be warranted as a result of the additional traffic to be generated by the proposed Comprehensive Plan Amendment and Rezoning requests.

The 2045 Financially Feasible Roadway network and the short term 5-year Capital Improvement Program currently in place in the Lee County will not require any modification in order to accommodate the proposed Land Use Change. The rezoning analysis also indicates that the subject site will not have an adverse impact on the surrounding roadway network. Therefore, no roadway capacity improvements are necessary to accommodate the proposed development.

The results of the intersection analysis at the proposed site access drive on Barrett Road indicate all approaches to operate at an acceptable Level of Service in 2027 with the project trips added to the intersection in the AM and PM peak hour traffic conditions. Therefore, no intersection capacity improvements are warranted as a result of this analysis.

APPENDIX

TABLES 1A & 2A
2045 LOS ANALYSIS

TABLE 1A
LEVEL OF SERVICE THRESHOLDS
2045 LONG RANGE TRANSPORTATION ANALYSIS - BARRETT PARK

ROADWAY	ROADWAY SEGMENT	2045 E + C NETWORK LANES		GENERALIZED SERVICE VOLUMES				
		# Lanes	Roadway Designation	LOS A	LOS B	LOS C	LOS D	LOS E
				VOLUME	VOLUME	VOLUME	VOLUME	VOLUME
Barrett Rd	N. of Site	2LU	Collector	0	0	310	660	740
	S. of Site	2LU	Collector	0	0	310	660	740
Pine Island Rd (SR 78)	W. of Del Prado Blvd	6LD	Arterial	0	0	3,087	3,171	3,171
	W. of Barret Rd	4LD	Arterial	0	0	2,005	2,100	2,100
	E. of Barret Rd	4LD	Arterial	0	0	2,005	2,100	2,100
	E. of US 41	4LD	Arterial	0	0	2,005	2,100	2,100
Pondella Rd	W. of Barret Rd	4LD	Arterial	0	250	1,840	1,960	1,960
	E. of Barret Rd	4LD	Arterial	0	250	1,840	1,960	1,960
	E. of US 41	4LD	Arterial	0	250	1,840	1,960	1,960
Orange Grove Blvd	S. of Pondella Rd	4LD	Collector	0	0	770	1,510	1,600
	S. of Iris Dr	4LD	Collector	0	0	770	1,510	1,600
Hancock Bridge Pkwy	W. of Orange Grove Blvd	4LD	Arterial	0	250	1,840	1,960	1,960
	W. of Del Prado Blvd	4LD	Arterial	0	250	1,840	1,960	1,960
Del Prado Blvd	S. of Hancock Bridge Pkwy	6LD	Arterial	0	400	2,840	2,940	2,940
US 41	N. of Pine Island Rd	4LD	Arterial	0	0	2,005	2,100	2,100
	S. of Hancock Bridge Pkwy	4LD	Arterial	0	0	2,005	2,100	2,100
Business 41	S. of Pondella Rd	6LD	Arterial	0	0	3,087	3,171	3,171
	N. of Pondella Rd	6LD	Arterial	0	0	3,087	3,171	3,171
	N. of Pine Island Rd	4LD	Arterial	0	0	2,005	2,100	2,100

- Denotes the LOS Standard for each roadway segment

* Level of Service Thresholds for Lee County roadways were taken from the Generalized Peak Hour Directional Service Volume tables for Urbanized Areas (dated April 2016)

* Level of Service Thresholds for State maintained roadways were taken from FDOT's Generalized Peak Hour Directional Volumes for Florida's Urbanized Areas Table 7.

TABLE 2A
2045 ROADWAY LINK LEVEL OF SERVICE CALCULATIONS
BARRETT PARK

TOTAL PM PEAK HOUR PROJECT TRAFFIC = 107 VPH IN= 67 OUT= 40

ROADWAY	ROADWAY SEGMENT	2045	COUNTY PCS / FDOT SITE #	AADT	K-100 FACTOR	100TH HIGHEST	D	PM PK HR	2045		PROJECT	PK DIR	2045 BACKGROUND PLUS PROJ	
		FSUTMS AADT		BACKGROUND TRAFFIC		HOUR PK DIR 2-WAY VOLUME		PEAK DIRECTION	PK HR PEAK TRAFFIC VOLUMES & LOS	LOS		PM PROJ TRAFFIC	PEAK DIRECTION TRAFFIC VOLUMES & LOS	LOS
Barrett Rd	N. of Site	2,938	34	2,938	0.096	282	0.62	SOUTH	175	C	30%	20	195	C
	S. of Site	4,285	34	4,285	0.096	411	0.62	SOUTH	255	C	70%	47	302	C
Pine Island Rd (SR 78)	W. of Del Prado Blvd	52,351	120038	52,351	0.090	4,712	0.57	WEST	2,686	C	8%	5	2,691	C
	W. of Barret Rd	39,597	126049	39,597	0.090	3,564	0.57	WEST	2,031	D	15%	10	2,041	D
	E. of Barret Rd	40,903	125042	40,903	0.090	3,681	0.57	WEST	2,098	D	15%	10	2,108	F
	E. of US 41	29,245	120003	29,245	0.090	2,632	0.57	EAST	1,500	C	5%	3	1,503	C
Pondella Rd	W. of Barret Rd	31,553	34	31,553	0.096	3,029	0.62	WEST	1,878	D	25%	17	1,895	D
	E. of Barret Rd	33,206	34	33,206	0.096	3,188	0.62	WEST	1,977	F	45%	30	2,007	F
	E. of US 41	38,272	34	38,272	0.096	3,674	0.62	WEST	2,278	F	15%	10	2,288	F
Orange Grove Blvd	S. of Pondella Rd	9,240	34	9,240	0.096	887	0.62	SOUTH	550	C	25%	17	567	C
	S. of Iris Dr	10,301	34	10,301	0.096	989	0.62	SOUTH	613	C	20%	13	626	C
Hancock Bridge Pkwy	W. of Orange Grove Blvd	26,855	17	26,855	0.102	2,739	0.63	WEST	1,726	C	15%	10	1,736	C
	W. of Del Prado Blvd	31,026	17	31,026	0.102	3,165	0.63	WEST	1,994	F	5%	3	1,997	F
Del Prado Blvd	S. of Hancock Bridge Pkwy	50,870	40	50,870	0.087	4,426	0.51	NORTH	2,257	C	10%	7	2,264	C
US 41	N. of Pine Island Rd	36,830	125029	36,830	0.090	3,315	0.531	NORTH	1,760	C	5%	3	1,763	C
	S. of Hancock Bridge Pkwy	65,324	126001	65,324	0.090	5,879	0.531	NORTH	3,122	F	25%	17	3,139	F
Business 41	S. of Pondella Rd	78,159	126041	78,159	0.090	7,034	0.526	NORTH	3,700	F	15%	10	3,710	F
	N. of Pondella Rd	55,461	125043	55,461	0.090	4,991	0.526	NORTH	2,625	C	5%	3	2,628	C
	N. of Pine Island Rd	40,282	125027	40,282	0.090	3,625	0.526	NORTH	1,907	C	5%	3	1,910	C

¹ The 2045 Pk Hr Pk Direction Traffic Volumes were calculated by adjusting the 2045 AADT volumes obtained from the adopted FSUTMS model by the appropriate K and D factors.

* The K-100 and D factors for County maintained roadways were obtained from Lee County Traffic Count Report.

Note: Due to lack of traffic data in the Lee County Traffic Count Report, the K-100 and D factors for Barrett Road were assumed from Lee County PCS #34.

Note: Due to lack of traffic data in the Lee County Traffic Count Report, the K-100 and D factors for Orange Grove Boulevard were assumed from Lee County PCS #34.

* The K-100 and D factors for FDOT maintained roadways were obtained from Florida Traffic Online resource.

TABLES 3A & 4A
5-YEAR LOS ANALYSIS

**TABLE 3A
LEVEL OF SERVICE THRESHOLDS
BARRETT PARK**

<u>ROADWAY</u>	<u>ROADWAY SEGMENT</u>	<u># LANES</u>	<u>ROADWAY DESIGNATION</u>	GENERALIZED SERVICE VOLUMES				
				LOS A	LOS B	LOS C	LOS D	LOS E
				<u>VOLUME</u>	<u>VOLUME</u>	<u>VOLUME</u>	<u>VOLUME</u>	<u>VOLUME</u>
Barrett Rd	N. of Site	2LU	Collector	0	0	310	660	740
	S. of Site	2LU	Collector	0	0	310	660	740
Pine Island Rd (SR 78)	W. of Del Prado Blvd	4LD	Arterial	0	0	2,005	2,100	2,100
	W. of Barret Rd	4LD	Arterial	0	0	2,005	2,100	2,100
	E. of Barret Rd	4LD	Arterial	0	0	2,005	2,100	2,100
	E. of US 41	4LD	Arterial	0	0	2,005	2,100	2,100
Pondella Rd	W. of Barret Rd	4LD	Arterial	0	250	1,840	1,960	1,960
	E. of Barret Rd	4LD	Arterial	0	250	1,840	1,960	1,960
	E. of US 41	4LD	Arterial	0	250	1,840	1,960	1,960
Orange Grove Blvd	S. of Pondella Rd	4LD	Collector	0	0	770	1,510	1,600
	S. of Iris Dr	4LD	Collector	0	0	770	1,510	1,600
Hancock Bridge Pkwy	W. of Orange Grove Blvd	4LD	Arterial	0	250	1,840	1,960	1,960
	W. of Del Prado Blvd	4LD	Arterial	0	250	1,840	1,960	1,960
Del Prado Blvd	S. of Hancock Bridge Pkwy	6LD	Arterial	0	400	2,840	2,940	2,940
US 41	N. of Pine Island Rd	4LD	Arterial	0	0	2,005	2,100	2,100
	S. of Hancock Bridge Pkwy	4LD	Arterial	0	0	2,005	2,100	2,100
Business 41	S. of Pondella Rd	6LD	Arterial	0	0	3,087	3,171	3,171
	N. of Pondella Rd	6LD	Arterial	0	0	3,087	3,171	3,171
	N. of Pine Island Rd	4LD	Arterial	0	0	2,005	2,100	2,100

- Denotes the LOS Standard for each roadway segment

* Level of Service Thresholds for Lee County arterials/collectors taken from the Generalized Peak Hour Directional Service Volume tables for Urbanized Areas (dated April 2016)

* Level of Service Thresholds for State maintained roadways were taken from FDOT's Generalized Peak Hour Directional Volumes for Florida's Urbanized Areas Table 7.

**TABLE 4A
LEE COUNTY TRAFFIC COUNTS AND CALCULATIONS
BARRETT PARK**

TOTAL PROJECT TRAFFIC AM =	85	VPH	IN =	20	OUT=	65
TOTAL PROJECT TRAFFIC PM =	107	VPH	IN=	67	OUT=	40

ROADWAY	ROADWAY SEGMENT	LCDOT PCS OR BASE YR		2021 ADT	YRS OF GROWTH. ¹	ANNUAL RATE	2020/2021	2027			PERCENT			2027			2027		
							PK HR	PK HR	PK SEASON	BCKGRND				BCKGRND					
							PK SEASON	PEAK DIRECTION	V/C	PROJECT	AM PROJ	PM PROJ	+ AM PROJ	V/C	+ PM PROJ	V/C			
							PEAK DIR. ²	VOLUME	LOS	Ratio	TRAFFIC	TRAFFIC	TRAFFIC	VOLUME	LOS	Ratio	VOLUME	LOS	Ratio
Barrett Rd	N. of Site	N/A	N/A	N/A	N/A	2.00%	103	118	C	0.16	30%	20	20	138	C	0.19	138	C	0.19
	S. of Site	N/A	N/A	N/A	N/A	2.00%	103	118	C	0.16	70%	46	47	164	C	0.22	165	C	0.22
Pine Island Rd (SR 78)	W. of Del Prado Blvd	120038	39,500	47,500	15	2.00%	2,437	2,744	F	1.31	8%	5	5	2,750	F	1.31	2,750	F	1.31
	W. of Barret Rd	126049	24,214	29,000	13	2.00%	1,488	1,676	C	0.80	15%	10	10	1,685	C	0.80	1,686	C	0.80
	E. of Barret Rd	125042	31,500	35,500	15	2.00%	1,821	2,051	D	0.98	15%	10	10	2,060	D	0.98	2,061	D	0.98
	E. of US 41	120003	34,000	31,000	15	2.00%	1,590	1,791	C	0.85	5%	3	3	1,794	C	0.85	1,794	C	0.85
Pondella Rd	W. of Barret Rd	34	17,700	23,600	9	3.25%	736	921	C	0.47	25%	16	17	937	C	0.48	937	C	0.48
	E. of Barret Rd	34	17,700	23,600	9	3.25%	1,101	1,377	C	0.70	45%	29	30	1,406	C	0.72	1,407	C	0.72
	E. of US 41	34	17,700	23,600	9	3.25%	1,094	1,368	C	0.70	15%	10	10	1,378	C	0.70	1,378	C	0.70
Orange Grove Blvd	S. of Pondella Rd	121269	9,200	10,300	6	2.00%	614	705	C	0.44	25%	16	17	722	C	0.45	722	C	0.45
	S. of Iris Dr	121269	9,200	10,300	6	2.00%	614	705	C	0.44	20%	13	13	718	C	0.45	719	C	0.45
Hancock Bridge Pkwy	W. of Orange Grove Blvd	292	20,900	22,700	8	2.00%	1,414	1,624	C	0.83	15%	10	10	1,634	C	0.83	1,634	C	0.83
	W. of Del Prado Blvd	292	20,900	22,700	8	2.00%	949	1,090	C	0.56	5%	3	3	1,093	C	0.56	1,093	C	0.56
Del Prado Blvd	S. of Hancock Bridge Pkwy	40	45,200	45,000	9	2.00%	2,038	2,341	C	0.80	10%	7	7	2,348	C	0.80	2,348	C	0.80
US 41	N. of Pine Island Rd	125029	29,000	26,000	15	2.00%	1,362	1,534	C	0.73	5%	3	3	1,537	C	0.73	1,537	C	0.73
	S. of Hancock Bridge Pkwy	126001	41,636	43,000	13	2.00%	1,996	2,248	F	1.07	25%	16	17	2,264	F	1.08	2,265	F	1.08
Business 41	S. of Pondella Rd	126041	25,223	45,500	13	4.64%	1,715	2,252	C	0.71	15%	10	10	2,261	C	0.71	2,262	C	0.71
	N. of Pondella Rd	125043	33,500	30,500	15	2.00%	1,715	1,931	C	0.61	5%	3	3	1,935	C	0.61	1,935	C	0.61
	N. of Pine Island Rd	125027	17,800	21,000	15	2.00%	994	1,119	C	0.53	5%	3	3	1,123	C	0.53	1,123	C	0.53

1 AGR for all roadways was calculated based the historical traffic data obtained from the Lee County Traffic Count Report and Florida Traffic Online webpage.

1 Due to lack of historical traffic data on Barrett Road, a minimum annual growth rate of 2% compounded annually was assumed.

2 Current peak hour peak season peak direction traffic volumes for all County roadways were obtained from the 2021 Lee County Public Facilities Level of Service and Concurrency Report.

2 Due to lack of traffic data, the current peak hour peak season peak direction traffic volumes for Hancock Bridge Pkwy west of Del Prado Blvd was obtained by adjusting the 2021 AADT by appropriate K and D factors (Station No. 124166).

2 Current peak hour peak season peak direction traffic volume for all State roadways was obtained from the 2021 FDOT's District One LOS Spreadsheet.

TABLES 5A & 6A
REZONING LOS ANALYSIS

**TABLE 5A
LEVEL OF SERVICE THRESHOLDS
BARRETT PARK**

TOTAL AM PEAK HOUR PROJECT TRAFFIC =	85 VPH	IN=	20	OUT=	65
TOTAL PM PEAK HOUR PROJECT TRAFFIC =	107 VPH	IN=	67	OUT=	40

ROADWAY	ROADWAY SEGMENT	# LANES	ROADWAY DESIGNATION	LOS A	LOS B	LOS C	LOS D	LOS E	PERCENT		
				VOLUME	VOLUME	VOLUME	VOLUME	VOLUME	PROJECT TRAFFIC	PROJECT TRAFFIC	PROJ/ LOS C
Barrett Rd	N. of Site	2LU	Collector	0	0	310	660	740	30%	20	6.5%
	S. of Site	2LU	Collector	0	0	310	660	740	70%	47	15.1%
Pondella Rd	W. of Barret Rd	4LD	Arterial	0	250	1,840	1,960	1,960	25%	17	0.9%
	E. of Barret Rd	4LD	Arterial	0	250	1,840	1,960	1,960	45%	30	1.6%

- Denotes the LOS Standard for each roadway segment

* Level of Service Thresholds for Lee County arterials/collectors taken from the Generalized Peak Hour Directional Service Volume tables for Urbanized Areas (dated April 2016)

**TABLE 6A
LEE COUNTY TRAFFIC COUNTS AND CALCULATIONS
BARRETT PARK**

TOTAL PROJECT TRAFFIC AM =	85	VPH	IN =	20	OUT=	65
TOTAL PROJECT TRAFFIC PM =	107	VPH	IN=	67	OUT=	40

ROADWAY	ROADWAY SEGMENT	LCDOT PCS OR FDOT SITE #	BASE YR ADT	2018/2019 ADT	YRS OF GROWTH. ¹	ANNUAL RATE	2020	2027			PERCENT PROJECT	2027			2027				
							PK HR	PK HR	PK SEASON	V/C		BCKGRND			BCKGRND				
							PK SEASON	PEAK DIRECTION	V/C			AM PROJ	PM PROJ	+ AM PROJ	V/C	+ PM PROJ	V/C		
							PEAK DIR. ²	VOLUME										LOS	Ratio
Barrett Rd	N. of Site	N/A	N/A	N/A	N/A	2.00%	103	118	C	0.16	30%	20	20	138	C	0.19	138	C	0.19
	S. of Site	N/A	N/A	N/A	N/A	2.00%	103	118	C	0.16	70%	46	47	164	C	0.22	165	C	0.22

¹ Due to lack of historical traffic data on Barrett Road, a minimum annual growth rate of 2% compounded annually was assumed.

² Current peak hour peak season peak direction traffic volumes for all County roadways were obtained from the 2021 Lee County Public Facilities Level of Service and Concurrency Report.

**FDOT GENERALIZED PEAK HOUR
DIRECTIONAL VOLUMES FOR
FLORIDA'S URBANIZED AREAS
TABLE 7**

TABLE 7

Generalized **Peak Hour Directional** Volumes for Florida's
Urbanized Areas

January 2020

INTERRUPTED FLOW FACILITIES						UNINTERRUPTED FLOW FACILITIES					
STATE SIGNALIZED ARTERIALS						FREEWAYS					
Class I (40 mph or higher posted speed limit)						Core Urbanized					
Lanes	Median	B	C	D	E	Lanes	B	C	D	E	
1	Undivided	*	830	880	**	2	2,230	3,100	3,740	4,080	
2	Divided	*	1,910	2,000	**	3	3,280	4,570	5,620	6,130	
3	Divided	*	2,940	3,020	**	4	4,310	6,030	7,490	8,170	
4	Divided	*	3,970	4,040	**	5	5,390	7,430	9,370	10,220	
						6	6,380	8,990	11,510	12,760	
Class II (35 mph or slower posted speed limit)						Urbanized					
Lanes	Median	B	C	D	E	Lanes	B	C	D	E	
1	Undivided	*	370	750	800	2	2,270	3,100	3,890	4,230	
2	Divided	*	730	1,630	1,700	3	3,410	4,650	5,780	6,340	
3	Divided	*	1,170	2,520	2,560	4	4,550	6,200	7,680	8,460	
4	Divided	*	1,610	3,390	3,420	5	5,690	7,760	9,520	10,570	
Non-State Signalized Roadway Adjustments						Freeway Adjustments					
(Alter corresponding state volumes by the indicated percent.)						Auxiliary Lane Ramp Metering					
Non-State Signalized Roadways - 10%						+ 1,000 + 5%					
Median & Turn Lane Adjustments						UNINTERRUPTED FLOW HIGHWAYS					
Lanes	Median	Exclusive Left Lanes	Exclusive Right Lanes	Adjustment Factors		Lanes	Median	B	C	D	E
1	Divided	Yes	No	+5%		1	Undivided	580	890	1,200	1,610
1	Undivided	No	No	-20%		2	Divided	1,800	2,600	3,280	3,730
Multi	Undivided	Yes	No	-5%		3	Divided	2,700	3,900	4,920	5,600
Multi	Undivided	No	No	-25%							
-	-	-	Yes	+5%							
One-Way Facility Adjustment						Uninterrupted Flow Highway Adjustments					
Multiply the corresponding directional volumes in this table by 1.2						Lanes	Median	Exclusive left lanes	Adjustment factors		
						1	Divided	Yes	+5%		
						Multi	Undivided	Yes	-5%		
						Multi	Undivided	No	-25%		
BICYCLE MODE²						¹ Values shown are presented as peak hour directional volumes for levels of service and are for the automobile/truck modes unless specifically stated. This table does not constitute a standard and should be used only for general planning applications. The computer models from which this table is derived should be used for more specific planning applications. The table and deriving computer models should not be used for corridor or intersection design, where more refined techniques exist. Calculations are based on planning applications of the HCM and the Transit Capacity and Quality of Service Manual.					
(Multiply vehicle volumes shown below by number of directional roadway lanes to determine two-way maximum service volumes.)						² Level of service for the bicycle and pedestrian modes in this table is based on number of vehicles, not number of bicyclists or pedestrians using the facility.					
Paved Shoulder/Bicycle Lane Coverage	B	C	D	E		³ Buses per hour shown are only for the peak hour in the single direction of the higher traffic flow.					
0-49%	*	150	390	1,000		* Cannot be achieved using table input value defaults.					
50-84%	110	340	1,000	>1,000		** Not applicable for that level of service letter grade. For the automobile mode, volumes greater than level of service D become F because intersection capacities have been reached. For the bicycle mode, the level of service letter grade (including F) is not achievable because there is no maximum vehicle volume threshold using table input value defaults.					
85-100%	470	1,000	>1,000	**		Source: Florida Department of Transportation Systems Implementation Office https://www.fdot.gov/planning/systems/					
PEDESTRIAN MODE²											
(Multiply vehicle volumes shown below by number of directional roadway lanes to determine two-way maximum service volumes.)											
Sidewalk Coverage	B	C	D	E							
0-49%	*	*	140	480							
50-84%	*	80	440	800							
85-100%	200	540	880	>1,000							
BUS MODE (Scheduled Fixed Route)³											
(Buses in peak hour in peak direction)											
Sidewalk Coverage	B	C	D	E							
0-84%	> 5	≥ 4	≥ 3	≥ 2							
85-100%	> 4	≥ 3	≥ 2	≥ 1							

**LEE COUNTY GENERALIZED PEAK
HOUR DIRECTIONAL SERVICE
VOLUMES TABLE**

TRAFFIC DATA
FDOT FLORIDA TRAFFIC ONLINE

FLORIDA DEPARTMENT OF TRANSPORTATION
TRANSPORTATION STATISTICS OFFICE
2021 HISTORICAL AADT REPORT

COUNTY: 12 - LEE

SITE: 0038 - SR 78, SOUTHWEST OF DEL PRADO BLVD CP CORAL LC366

YEAR	AADT		DIRECTION 1	DIRECTION 2	*K FACTOR	D FACTOR	T FACTOR
2021	47500 C	E	23000	W 24500	9.00	57.00	11.30
2020	46000 E	E	0	W 0	9.00	54.00	6.20
2019	45500 E	E	0	W 0	9.00	56.00	8.20
2018	45000 F	E	22500	W 22500	9.00	53.30	9.30
2017	44000 C	E	22000	W 22000	9.00	53.20	5.20
2016	42000 C	E	21000	W 21000	9.00	57.10	5.20
2015	40500 C	E	20500	W 20000	9.00	56.60	5.20
2014	38500 F	E	19000	W 19500	9.00	56.60	5.00
2013	37500 C	E	18500	W 19000	9.00	57.20	5.00
2012	41000 C	E	20500	W 20500	9.00	57.10	4.90
2011	39500 F	E	19000	W 20500	9.00	56.70	6.20
2010	40500 C	E	19500	W 21000	10.19	55.56	6.20
2009	39500 C	E	19500	W 20000	9.18	58.15	5.10
2008	41000 C	E	20500	W 20500	9.84	57.71	10.00
2007	37000 C	E	18500	W 18500	10.16	54.76	10.00
2006	39500 C	E	19500	W 20000	10.23	54.38	11.80

AADT FLAGS: C = COMPUTED; E = MANUAL ESTIMATE; F = FIRST YEAR ESTIMATE
S = SECOND YEAR ESTIMATE; T = THIRD YEAR ESTIMATE; R = FOURTH YEAR ESTIMATE
V = FIFTH YEAR ESTIMATE; 6 = SIXTH YEAR ESTIMATE; X = UNKNOWN
*K FACTOR: STARTING WITH YEAR 2011 IS STANDARDK, PRIOR YEARS ARE K30 VALUES

FLORIDA DEPARTMENT OF TRANSPORTATION
TRANSPORTATION STATISTICS OFFICE
2021 HISTORICAL AADT REPORT

COUNTY: 12 - LEE

SITE: 6049 - SR 78/PINE ISLAND RD, 2000' E OF PONDELLA RD, PTMS 5026, LCPR 49

YEAR	AADT	DIRECTION 1	DIRECTION 2	*K FACTOR	D FACTOR	T FACTOR
2021	29000 T	0	0	9.00	57.00	9.90
2020	28500 S	0	0	9.00	54.00	6.90
2019	30000 F	0	0	9.00	56.00	7.70
2018	29927 C	0	0	9.00	55.30	8.00
2017	29000 F	0	0	9.00	55.30	7.40
2016	28134 C	E 13295	W 14839	9.00	55.30	7.00
2015	27364 C	E 12864	W 14500	9.00	56.60	5.90
2014	26000 C	E 11982	W 14018	9.00	57.10	5.90
2013	23162 C	E 10634	W 12528	9.00	57.10	5.40
2012	23695 C	E 10824	W 12871	9.00	57.10	5.60
2011	22431 C	E 11193	W 11238	9.00	55.60	6.00
2010	22902 C	E 11333	W 11569	10.19	55.56	5.40
2009	24948 C	E 11439	W 13509	9.18	58.15	5.50
2008	24214 C	E 11059	W 13155	9.42	57.15	5.50

AADT FLAGS: C = COMPUTED; E = MANUAL ESTIMATE; F = FIRST YEAR ESTIMATE
S = SECOND YEAR ESTIMATE; T = THIRD YEAR ESTIMATE; R = FOURTH YEAR ESTIMATE
V = FIFTH YEAR ESTIMATE; 6 = SIXTH YEAR ESTIMATE; X = UNKNOWN
*K FACTOR: STARTING WITH YEAR 2011 IS STANDARDK, PRIOR YEARS ARE K30 VALUES

FLORIDA DEPARTMENT OF TRANSPORTATION
TRANSPORTATION STATISTICS OFFICE
2021 HISTORICAL AADT REPORT

COUNTY: 12 - LEE

SITE: 5042 - SR 78, WEST OF SR 45/US 41 (LC364)

YEAR	AADT	DIRECTION 1	DIRECTION 2	*K FACTOR	D FACTOR	T FACTOR
2021	35500 C	E 17000	W 18500	9.00	57.00	8.40
2020	36500 E	E 0	W 0	9.00	54.00	6.30
2019	36000 C	E 0	W 0	9.00	56.00	7.80
2018	35500 C	E 17000	W 18500	9.00	53.30	7.20
2017	34500 C	E 16500	W 18000	9.00	53.20	7.10
2016	33000 C	E 16000	W 17000	9.00	57.10	5.80
2015	30500 C	E 14500	W 16000	9.00	56.60	5.60
2014	28000 F	E 13500	W 14500	9.00	56.60	4.70
2013	27000 C	E 13000	W 14000	9.00	57.20	4.70
2012	26000 C	E 12500	W 13500	9.00	57.10	5.40
2011	24000 F	E 11500	W 12500	9.00	56.70	5.80
2010	25000 C	E 12000	W 13000	10.19	55.56	5.80
2009	29500 C	E 14500	W 15000	9.18	58.15	5.30
2008	30500 C	E 14500	W 16000	9.84	57.71	6.60
2007	29500 C	E 14000	W 15500	10.16	54.76	9.10
2006	31500 C	E 15000	W 16500	10.23	54.38	10.90

AADT FLAGS: C = COMPUTED; E = MANUAL ESTIMATE; F = FIRST YEAR ESTIMATE
S = SECOND YEAR ESTIMATE; T = THIRD YEAR ESTIMATE; R = FOURTH YEAR ESTIMATE
V = FIFTH YEAR ESTIMATE; 6 = SIXTH YEAR ESTIMATE; X = UNKNOWN
*K FACTOR: STARTING WITH YEAR 2011 IS STANDARDK, PRIOR YEARS ARE K30 VALUES

FLORIDA DEPARTMENT OF TRANSPORTATION
TRANSPORTATION STATISTICS OFFICE
2021 HISTORICAL AADT REPORT

COUNTY: 12 - LEE

SITE: 0003 - SR 78/PINE ISLAND RD, WEST OF SR 739/US 41B LC365

YEAR	AADT		DIRECTION 1	DIRECTION 2	*K FACTOR	D FACTOR	T FACTOR
----	-----		-----	-----	-----	-----	-----
2021	31000 C	E	15500	W 15500	9.00	57.00	9.90
2020	32500 E	E	0	W 0	9.00	54.00	6.90
2019	32000 E	E	0	W 0	9.00	56.00	7.10
2018	31500 C	E	16000	W 15500	9.00	53.30	7.50
2017	29500 C	E	14500	W 15000	9.00	53.20	7.60
2016	32500 C	E	16000	W 16500	9.00	57.10	6.60
2015	30000 C	E	15000	W 15000	9.00	56.60	6.20
2014	26000 F	E	12500	W 13500	9.00	56.60	5.80
2013	25000 C	E	12000	W 13000	9.00	57.20	5.80
2012	26000 C	E	12500	W 13500	9.00	57.10	6.00
2011	26500 F	E	13000	W 13500	9.00	56.70	5.60
2010	27500 C	E	13500	W 14000	10.19	55.56	5.60
2009	28000 C	E	14000	W 14000	9.18	58.15	6.80
2008	32500 C	E	16000	W 16500	9.84	57.71	5.50
2007	33500 C	E	17000	W 16500	10.16	54.76	8.50
2006	34000 C	E	17000	W 17000	10.23	54.38	10.10

AADT FLAGS: C = COMPUTED; E = MANUAL ESTIMATE; F = FIRST YEAR ESTIMATE
S = SECOND YEAR ESTIMATE; T = THIRD YEAR ESTIMATE; R = FOURTH YEAR ESTIMATE
V = FIFTH YEAR ESTIMATE; 6 = SIXTH YEAR ESTIMATE; X = UNKNOWN
*K FACTOR: STARTING WITH YEAR 2011 IS STANDARDK, PRIOR YEARS ARE K30 VALUES

FLORIDA DEPARTMENT OF TRANSPORTATION
TRANSPORTATION STATISTICS OFFICE
2021 HISTORICAL AADT REPORT

COUNTY: 12 - LEE

SITE: 1269 - ORANGE GROVE BLVD, BTWN TROPIC TERRACE AND JAVA WAY

YEAR	AADT		DIRECTION 1		DIRECTION 2	*K FACTOR	D FACTOR	T FACTOR
----	-----		-----		-----	-----	-----	-----
2021	10300 C	N	4800	S	5500	9.00	57.00	5.30
2020	11500 E	N	0	S	0	9.00	59.30	6.90
2019	11000 F	N		S		9.00	59.60	7.70
2018	10600 C	N	4900	S	5700	9.00	53.30	8.00
2017	9400 S	N		S		9.00	59.80	7.40
2016	9400 F	N	4300	S	5100	9.00	51.60	7.00
2015	9200 C	N	4200	S	5000	9.00	55.50	5.90

AADT FLAGS: C = COMPUTED; E = MANUAL ESTIMATE; F = FIRST YEAR ESTIMATE
 S = SECOND YEAR ESTIMATE; T = THIRD YEAR ESTIMATE; R = FOURTH YEAR ESTIMATE
 V = FIFTH YEAR ESTIMATE; 6 = SIXTH YEAR ESTIMATE; X = UNKNOWN
 *K FACTOR: STARTING WITH YEAR 2011 IS STANDARDK, PRIOR YEARS ARE K30 VALUES

FLORIDA DEPARTMENT OF TRANSPORTATION
TRANSPORTATION STATISTICS OFFICE
2021 HISTORICAL AADT REPORT

COUNTY: 12 - LEE

SITE: 5029 - SR 45/US 41, N OF DIPLOMAT PKWY E LC419

YEAR	AADT		DIRECTION 1	DIRECTION 2	*K FACTOR	D FACTOR	T FACTOR
2021	26000 C	N	12500	S 13500	9.00	53.10	6.20
2020	31500 C	N	15500	S 16000	9.00	52.80	4.10
2019	30000 C	N	14500	S 15500	9.00	53.30	4.70
2018	29500 C	N	14500	S 15000	9.00	53.30	4.30
2017	24000 C	N	12000	S 12000	9.00	53.20	4.90
2016	29500 C	N	14500	S 15000	9.00	56.20	4.10
2015	28500 C	N	14000	S 14500	9.00	54.50	3.90
2014	27000 C	N	13500	S 13500	9.00	54.60	3.70
2013	23500 C	N	11500	S 12000	9.00	59.70	5.30
2012	23500 C	N	11500	S 12000	9.00	54.30	4.30
2011	27500 C	N	13000	S 14500	9.00	55.00	4.00
2010	28500 C	N	13500	S 15000	10.32	57.60	4.50
2009	26000 C	N	12500	S 13500	10.24	54.47	5.20
2008	27000 C	N	13000	S 14000	10.37	58.94	3.90
2007	28500 C	N	13000	S 15500	10.16	54.76	5.30
2006	29000 C	N	13500	S 15500	10.23	54.38	7.30

AADT FLAGS: C = COMPUTED; E = MANUAL ESTIMATE; F = FIRST YEAR ESTIMATE

S = SECOND YEAR ESTIMATE; T = THIRD YEAR ESTIMATE; R = FOURTH YEAR ESTIMATE

V = FIFTH YEAR ESTIMATE; 6 = SIXTH YEAR ESTIMATE; X = UNKNOWN

*K FACTOR: STARTING WITH YEAR 2011 IS STANDARDK, PRIOR YEARS ARE K30 VALUES

FLORIDA DEPARTMENT OF TRANSPORTATION
TRANSPORTATION STATISTICS OFFICE
2021 HISTORICAL AADT REPORT

COUNTY: 12 - LEE

SITE: 6001 - US 41, 200' N OF NORTH KEY DRIVE, PTMS 31, LCPR 01

YEAR	AADT	DIRECTION 1	DIRECTION 2	*K FACTOR	D FACTOR	T FACTOR
2021	43000 T	0	0	9.00	53.10	5.00
2020	42000 S	0	0	9.00	52.80	4.10
2019	44000 F	0	0	9.00	53.30	5.80
2018	44428 C	0	0	9.00	70.50	4.20
2017	45500 F	0	0	9.00	70.50	4.30
2016	44122 C	N 24770	S 19352	9.00	70.50	4.60
2015	42005 C	N 23725	S 18280	9.00	70.70	4.10
2014	41448 C	N 23450	S 17998	9.00	70.70	3.30
2013	36427 C	N 21131	S 15296	9.00	70.70	3.30
2012	40000 F	N 0	S 0	9.00	71.80	4.00
2011	40125 C	N 24031	S 16094	9.00	71.80	3.90
2010	39989 C	N 23279	S 16710	9.98	71.78	3.40
2009	41563 C	N 24046	S 17517	9.84	72.83	4.10
2008	41636 C	N 23985	S 17651	9.84	72.83	4.70

AADT FLAGS: C = COMPUTED; E = MANUAL ESTIMATE; F = FIRST YEAR ESTIMATE
S = SECOND YEAR ESTIMATE; T = THIRD YEAR ESTIMATE; R = FOURTH YEAR ESTIMATE
V = FIFTH YEAR ESTIMATE; 6 = SIXTH YEAR ESTIMATE; X = UNKNOWN
*K FACTOR: STARTING WITH YEAR 2011 IS STANDARDK, PRIOR YEARS ARE K30 VALUES

FLORIDA DEPARTMENT OF TRANSPORTATION
TRANSPORTATION STATISTICS OFFICE
2021 HISTORICAL AADT REPORT

COUNTY: 12 - LEE

SITE: 6041 - SR 739/US 41B, 500' N OF EDISON BRIDGE, PTMS 19, LCPR 41

YEAR	AADT	DIRECTION 1	DIRECTION 2	*K FACTOR	D FACTOR	T FACTOR
2021	45500 C	N 23500	S 22000	9.00	52.60	8.20
2020	29000 X	0	0	9.00	51.70	9.20
2019	30500 X	0	0	9.00	52.00	5.90
2018	30500 E	0	0	9.00	52.30	6.10
2017	30000 S	0	0	9.00	53.20	6.20
2016	29000 F	0	0	9.00	57.90	5.60
2015	28057 C	N 16835	S 11222	9.00	72.80	6.40
2014	25845 C	N 15006	S 10839	9.00	72.80	5.80
2013	25072 C	N 14006	S 11066	9.00	72.80	6.70
2012	25000 C	N 13419	S 11581	9.00	72.80	5.30
2011	25865 C	N 13419	S 12446	9.00	71.60	5.90
2010	25948 C	N 13447	S 12501	11.43	71.72	5.60
2009	25736 C	N 13260	S 12476	11.19	71.69	6.10
2008	25223 C	N 12629	S 12594	12.36	78.72	5.80

AADT FLAGS: C = COMPUTED; E = MANUAL ESTIMATE; F = FIRST YEAR ESTIMATE
S = SECOND YEAR ESTIMATE; T = THIRD YEAR ESTIMATE; R = FOURTH YEAR ESTIMATE
V = FIFTH YEAR ESTIMATE; 6 = SIXTH YEAR ESTIMATE; X = UNKNOWN
*K FACTOR: STARTING WITH YEAR 2011 IS STANDARDK, PRIOR YEARS ARE K30 VALUES

FLORIDA DEPARTMENT OF TRANSPORTATION
TRANSPORTATION STATISTICS OFFICE
2021 HISTORICAL AADT REPORT

COUNTY: 12 - LEE

SITE: 4166 - HANCOCK BRIDGE ROAD, EAST OF SANTA BARBARA BLVD.

YEAR	AADT	DIRECTION 1	DIRECTION 2	*K FACTOR	D FACTOR	T FACTOR
2021	18500 C	E 8000	W 10500	9.00	57.00	4.00
2020	18500 E	E 0	W 0	9.00	53.40	4.10
2019	18000 F	E	W	9.00	53.80	3.60
2018	17500 C	E 7500	W 10000	9.00	53.30	3.60
2017	16000 E	E	W	9.00	55.20	10.10
2016	16000 S	E 6700	W 9300	9.00	51.60	3.00
2015	15800 F	E 6600	W 9200	9.00	55.50	3.00
2014	15100 C	E 6300	W 8800	9.00	55.20	3.00
2013	15700 S	E 6800	W 8900	9.00	55.00	5.10
2012	15700 F	E 6800	W 8900	9.00	55.30	5.50
2011	15800 C	E 6800	W 9000	9.00	55.20	6.00

AADT FLAGS: C = COMPUTED; E = MANUAL ESTIMATE; F = FIRST YEAR ESTIMATE
S = SECOND YEAR ESTIMATE; T = THIRD YEAR ESTIMATE; R = FOURTH YEAR ESTIMATE
V = FIFTH YEAR ESTIMATE; 6 = SIXTH YEAR ESTIMATE; X = UNKNOWN
*K FACTOR: STARTING WITH YEAR 2011 IS STANDARDK, PRIOR YEARS ARE K30 VALUES

**TRAFFIC DATA FROM THE LEE
COUNTY CONCURRENCY REPORT**

9/23/2021

LEE COUNTY Road Link Volumes (County- and State-Maintained Roadways)

LINK NO	NAME	ROADWAY LINK		ROAD TYPE	PERFORMANCE STANDARD		2020 100TH HIGHEST HOUR		FORECAST FUTURE		NOTES
		FROM	TO		LOS	CAPACITY	LOS	VOLUME	LOS	VOLUME	
00100	A & W BULB RD	GLADIOLUS DR	McGREGOR BLVD	2LN	E	860	C	410	C	431	
00200	ALABAMA RD	SR 82	MILWAUKEE BLVD	2LN	E	990	C	270	C	284	
00300	ALABAMA RD	MILWAUKEE BLVD	HOMESTEAD RD	2LN	E	990	C	355	C	373	
00400	ALEXANDER BELL	SR 82	MILWAUKEE BLVD	2LN	E	990	D	571	D	600	
00500	ALEXANDER BELL	MILWAUKEE BLVD	LEELAND HEIGHTS	2LN	E	990	D	571	E	664	Shadow Lakes
00590	ALICO RD	US 41	DUSTY RD	4LD	E	1,980	B	1,171	B	1,230	
00600	ALICO RD	DUSTY RD	LEE RD	6LD	E	2,960	B	1,171	B	1,532	Alico Business Park
00700	ALICO RD	LEE RD	THREE OAKS PKWY	6LD	E	2,960	B	1,171	B	1,419	Three Oaks Regional Center
00800	ALICO RD	THREE OAKS PKWY	I-75	6LD	E	2,960	B	2,051	B	2,156	EEPCO Study
00900	ALICO RD	I-75	BEN HILL GRIFFIN BLVD	6LD	E	2,960	B	1,061	B	1,208	EEPCO Study
01000	ALICO RD	BEN HILL GRIFFIN BLVD	GREEN MEADOW DR	2LN	E	1,100/1,840	C	378	E	782	4 Ln constr 2018, EEPCO Study*
01050	ALICO RD	GREEN MEADOW DR	CORKSCREW RD	2LN	E	1,100	B	131	B	224	EEPCO Study
01200	BABCOCK RD	US 41	ROCKEFELLER CIR	2LN	E	860	C	55	C	162	old count
01400	BARRETT RD	PONDELLA RD	PINE ISLAND RD	2LN	E	860	C	103	C	116	old count projection(2009)
01500	BASS RD	SUMMERLIN RD	GLADIOLUS DR	4LN	E	1,790	C	607	C	865	
01600	BAYSHORE RD (SR 78)	BUS 41	NEW POST RD/HART RD	4LD	D	2,100	C	1,750	C	1,925	
01700	BAYSHORE RD (SR 78)	HART RD	SLATER RD	4LD	D	2,100	C	1,774	C	2,236	
01800	BAYSHORE RD (SR 78)	SLATER RD	I-75	4LD	D	2,100	C	1,191	C	1,462	
01900	BAYSHORE RD (SR 78)	I-75	NALLE RD	2LN	D	924	C	691	C	877	
02000	BAYSHORE RD (SR 78)	NALLE RD	SR 31	2LN	D	924	C	532	C	673	
02100	BEN HILL GRIFFIN PKWY	CORKSCREW RD	FGCU ENTRANCE	4LD	E	2,000	B	1,403	B	1,475	
02200	BEN HILL GRIFFIN PKWY	FGCU BOULEVARD S	COLLEGE CLUB DR	4LD	E	2,000	B	1,403	B	1,475	
02250	BEN HILL GRIFFIN PKWY	COLLEGE CLUB DR	ALICO RD	6LD	E	3,000	A	1,129	A	1,221	
26950	BEN HILL GRIFFIN PKWY	ALICO RD	TERMINAL ACCESS RD	4LD	E	1,980	A	985	A	1,035	
02300	BETH STACEY BLVD	23RD ST	HOMESTEAD RD	2LN	E	860	C	346	C	518	
02400	BONITA BEACH RD	HICKORY BLVD	VANDERBILT DR	4LD	E	1,900	C	651	C	685	Constrained In City Plan *
02500	BONITA BEACH RD	VANDERBILT DR	US 41	4LD	E	1,900	C	1,494	C	1,571	Constrained In City Plan
02600	BONITA BEACH RD	US 41	OLD 41	4LD	E	1,860	C	1,532	C	1,610	Constrained, old count projection(2010)
02700	BONITA BEACH RD	OLD 41	IMPERIAL ST	6LD	E	2,800	C	1,818	C	1,910	Constrained In City Plan(2010)
02800	BONITA BEACH RD	IMPERIAL ST	W OF I-75	6LD	E	2,800	C	1,995	C	2,097	Constrained In City Plan
02900	BONITA BEACH RD	E OF I-75	BONITA GRAND DR	4LD	E	2,020	B	667	B	701	Constrained In City Plan
02950	BONITA BEACH RD	BONITA GRANDE DR	END OF CO. MAINTAINED	4LD	E	2,020	B	667	B	701	Constrained In City Plan
03100	BONITA GRANDE DR	BONITA BEACH RD	E TERRY ST	2LN	E	860	D	692	E	782	old count projection(2009)
03200	BOYSCOUT RD	SUMMERLIN RD	US 41	6LN	E	2,520	E	1,766	E	1,856	
03300	BRANTLEY RD	SUMMERLIN RD	US 41	2LN	E	860	C	275	C	289	
03400	BRIARCLIFF RD	US 41	TRIPLE CROWN CT	2LN	E	860	C	157	C	165	
03500	BROADWAY RD (ALVA)	SR 80	N RIVER RD	2LN	E	860	C	299	C	314	old count projection(2009)
03700	BUCKINGHAM RD	SR 82	GUNNERY RD	2LN	E	990	D	477	D	501	
03730	BUCKINGHAM RD	GUNNERY RD	ORANGE RIVER BLVD	2LN	E	990	C	383	C	403	
03800	BUCKINGHAM RD	ORANGE RIVER BLVD	SR 80	2LN	E	990	D	529	E	884	Buckingham 345, Portico
03900	BURNT STORE RD	SR 78	VAN BUREN PKWY	4LD	E	2,950	B	923	B	970	
04000	BURNT STORE RD	VAN BUREN PKWY	COUNTY LINE	2LN	E	1,140	C	506	C	604	
04200	BUS 41 (N TAMIAMI TR, SR 78)	CITY LIMITS (N END EDIS)	PONDELLA RD	6LD	D	3,171	C	1,249	C	1,554	
04300	BUS 41 (N TAMIAMI TR, SR 78)	PONDELLA RD	SR 78	6LD	D	3,171	C	1,249	C	1,554	
04400	BUS 41 (N TAMIAMI TR, SR 78)	SR 78	LITTLETON RD	4LD	D	2,100	C	1,000	C	1,275	
04500	BUS 41 (N TAMIAMI TR, SR 78)	LITTLETON RD	US 41	4LD	D	2,100	C	614	C	827	
04600	CAPE CORAL BRIDGE	DEL PRADO BLVD	McGREGOR BLVD	4LB	E	4,000	D	3,053	D	3,209	
04700	CAPTIVA DR	BLIND PASS	SOUTH SEAS	2LN	E	860	C	267	C	302	Constrained, old count(2010)
04800	CEMETERY RD	BUCKINGHAM RD	HIGGINS AVE	2LN	E	860	C	328	C	345	
04900	CHAMBERLIN PKWY	AIRPORT ENT	DANIELS PKWY	4LN	E	1,790	C	105	C	150	Port Authority maintained
05000	COCONUT RD	WEST END	VIA VENETTO BLVD	2LN	E	860	C	268	C	420	Estero maintains to east
05100	COLLEGE PKWY	McGREGOR BLVD	WINKLER RD	6LD	E	2,980	D	2,292	D	2,409	*
05200	COLLEGE PKWY	WINKLER RD	WHISKEY CREEK DR	6LD	E	2,980	D	2,059	D	2,164	
05300	COLLEGE PKWY	WHISKEY CREEK DR	SUMMERLIN RD	6LD	E	2,980	D	2,059	D	2,164	
05400	COLLEGE PKWY	SUMMERLIN RD	US 41	6LD	E	2,980	D	1,815	D	1,907	
05500	COLONIAL BLVD	McGREGOR BLVD	SUMMERLIN RD	6LD	E	2,840	D	3,049	D	3,204	*
05600	COLONIAL BLVD	SUMMERLIN RD	US 41	6LD	E	2,840	D	2,821	D	2,965	
06200	COLONIAL BLVD	DYNASTY DR	SR 82	6LD	D	3,040	B	2,241	C	2,355	*
06300	COLUMBUS BLVD	SR 82	MILWAUKEE BLVD	2LN	E	860	C	100	C	105	old count
06400	CONSTITUTION BLVD	US 41	CONSTITUTION CIR	2LN	E	860	C	217	C	245	old count projection(2010)
06500	CORBETT RD	SR 78 (PINE ISLAND RD)	LITTLETON RD	2LN	E	860	C	22	C	226	old count, added VA clinic(2009)
06600	CORKSCREW RD	US 41	THREE OAKS PKWY	4LD	E	1,900	C	1,007	C	1,272	Galleria at Corkscrew
06700	CORKSCREW RD	THREE OAKS PKWY	W OF I-75	4LD	E	1,900	D	2,129	D	2,238	
06800	CORKSCREW RD	E OF I-75	BEN HILL GRIFFIN BLVD	4LD	E	1,900	C	1,022	C	1,234	
06900	CORKSCREW RD	BEN HILL GRIFFIN BLVD	ALICO RD	4LD	E	1,960	C	1,181	C	1,393	
07000	CORKSCREW RD	ALICO RD	COUNTY LINE	2LN	E	1,140	C	499	E	978	EEPCO Study, The Place, Verdiana Village
07100	COUNTRY LAKES BLVD	LUCKETT RD	TICE ST	2LN	E	860	C	143	C	293	old count projection(2010)
07200	CRYSTAL DR	US 41	METRO PKWY	2LN	E	860	C	336	C	353	
07300	CRYSTAL DR	METRO PKWY	PLANTATION RD	2LN	E	860	C	225	C	237	

9/23/2021

LEE COUNTY Road Link Volumes (County- and State-Maintained Roadways)

LINK NO	NAME	ROADWAY LINK		ROAD TYPE	PERFORMANCE STANDARD		2020 100TH HIGHEST HOUR		FORECAST FUTURE		NOTES
		FROM	TO		LOS	CAPACITY	LOS	VOLUME	LOS	VOLUME	
20900	PINE ISLAND RD	STRINGFELLOW RD	BURNST STORE RD	2LN	E	950	E	594	E	644	Constrained
21400	PINE ISLAND RD (SR 78)	CITY LIMITS E OF BARRETT RD	US 41	4LD	D	2,100	C	1,621	D	2,037	
21500	PINE ISLAND RD (SR 78)	US 41	BUS 41	4LD	D	2,100	C	1,580	C	1,855	
21600	PINE RIDGE RD	SAN CARLOS BLVD	SUMMERLIN RD	2LN	E	860	C	489	C	535	*
21700	PINE RIDGE RD	SUMMERLIN RD	GLADIOLUS DR	2LN	E	860	C	293	D	552	Heritage Isle*
21800	PINE RIDGE RD	GLADIOLUS DR	MCGREGOR BLVD	2LN	E	860	C	293	C	308	
21900	PLANTATION RD	SIX MILE PKWY	DANIELS PKWY	2LN	E	860	C	285	C	414	Intermed Park
22000	PLANTATION RD	DANIELS PKWY	IDLEWILD ST	2LN	E	860	D	740	D	778	FDOT Metro Pkwy 6-laning
22050	PLANTATION RD	IDLEWILD ST	COLONIAL BLVD	4LN	E	1,790	C	510	C	536	
22100	PONDELLA RD	SR 78	ORANGE GROVE BLVD	4LD	E	1,890	B	736	B	774	*
22200	PONDELLA RD	ORANGE GROVE BLVD	US 41	4LD	E	1,890	B	1,101	B	1,176	
22300	PONDELLA RD	US 41	BUS 41	4LD	E	1,890	B	1,094	B	1,150	
22400	PRITCHETT PKWY	SR 78	RICH RD	2LN	E	860	C	73	C	541	old count, Stoneybrook North(2009)
22500	RANCHETTE RD	PENZANCE BLVD	IDLEWILD ST	2LN	E	860	C	93	C	98	
22600	RICH RD	SLATER RD	PRITCHETT PKWY	2LN	E	860	C	55	C	62	old count projection(2009)
22700	RICHMOND AVE	LEELAND HEIGHTS	E 12TH ST	2LN	E	860	C	77	C	89	
22800	RICHMOND AVE	E 12TH ST	GREENBRIAR BLVD	2LN	E	860	C	77	C	81	
23000	SAN CARLOS BLVD (SR 865)	MANTANZAS PASS B.	MAIN ST	2LD	D	970		1,022		1,151	Constrained
23100	SAN CARLOS BLVD (SR 865)	MAIN ST	SUMMERLIN RD	4LD	D	2,100	C	1,022	C	1,151	PD&E Study
23180	SAN CARLOS BLVD (SR 865)	SUMMERLIN RD	KELLY RD	2LD	D	970	C	689	C	767	
23200	SAN CARLOS BLVD (SR 865)	KELLY RD	GLADIOLUS DR	4LD	D	2,100	C	689	C	767	
23230	SAN CARLOS BLVD	US 41	THREE OAKS PKWY	2LN	E	860	C	418	C	471	*
23260	SANBEL BLVD	US 41	LEE RD	2LN	E	860	D	591	D	621	
23300	SANBEL CAUSEWAY	SANBEL SHORELINE	TOLL PLAZA	2LN	E	1,140	E	937	E	985	
23400	SHELL POINT BLVD	MCGREGOR BLVD	PALM ACRES	2LN	E	860	C	294	C	309	*
23500	SIX MILE PKWY (SR 739)	US 41	METRO PKWY	4LD	D	2,100	C	1,512	C	1,764	
23600	SIX MILE CYPRESS	METRO PKWY	DANIELS PKWY	4LD	E	2,000	B	1,481	B	1,556	
23700	SIX MILE CYPRESS	DANIELS PKWY	WINKLER EXT.	4LD	E	1,900	B	1,069	B	1,272	
23800	SIX MILE CYPRESS	WINKLER EXT.	CHALLENGER BLVD	4LD	E	1,900	B	1,038	B	1,091	
23900	SIX MILE CYPRESS	CHALLENGER BLVD	COLONIAL BLVD	6LD	E	2,860	A	1,038	A	1,091	
24000	SLATER RD	SR 78	NALLE GRADE RD	2LN	E	1,010	C	399	C	419	*
24100	SOUTH POINTE BLVD	CYPRESS LAKE DR	COLLEGE PKWY	2LD	E	910	D	640	D	673	*
24200	SR 31 (ARCADIA RD)	SR 80	SR 78	2LN	D	970	C	652	C	831	PD&E/SEIR Study
24300	SR 31 (ARCADIA RD)	SR 78	COUNTY LINE	2LN	C	820	B	460	B	669	PD&E/SEIR Study
24400	STALEY RD	TICE	ORANGE RIVER BLVD	2LN	E	860	C	211	C	237	*
24500	STRINGFELLOW RD	1ST AVE	BERKSHIRE RD	2LN	E	1,060	B	315	D	672	Constrained
24600	STRINGFELLOW RD	BERKSHIRE RD	PINE ISLAND RD	2LN	E	1,060	B	315	C	448	Constrained
24700	STRINGFELLOW RD	PINE ISLAND RD	PINELAND RD	2LN	E	1,060	D	712	E	813	Constrained
24800	STRINGFELLOW RD	PINELAND RD	MAIN ST	2LN	E	1,060	D	712	E	809	
24900	SUMMERLIN RD	MCGREGOR BLVD	KELLY COVE RD	4LD	E	1,980	A	1,243	A	1,306	
25000	SUMMERLIN RD	KELLY COVE RD	SAN CARLOS BLVD	4LD	E	1,980	A	1,243	A	1,306	
25100	SUMMERLIN RD	SAN CARLOS BLVD	PINE RIDGE RD	6LD	E	3,000	A	1,896	A	2,126	
25200	SUMMERLIN RD	PINE RIDGE RD	BASS RD	6LD	E	3,000	A	1,896	A	1,993	
25300	SUMMERLIN RD	BASS RD	GLADIOLUS DR	6LD	E	3,000	A	1,896	A	1,993	
25400	SUMMERLIN RD	GLADIOLUS DR	CYPRESS LAKE DR	4LD	E	1,900	C	1,517	C	1,618	
25500	SUMMERLIN RD	CYPRESS LAKE DR	COLLEGE PKWY	6LD	E	2,880	B	1,489	B	1,565	
25600	SUMMERLIN RD	COLLEGE PKWY	PARK MEADOW DR	6LD	E	2,880	B	1,526	B	1,604	
25700	SUMMERLIN RD	PARK MEADOW DR	BOY SCOUT	6LD	E	2,880	B	1,526	B	1,604	
25800	SUMMERLIN RD	BOY SCOUT	MATHEWS DR	4LD	E	1,820	D	1,189	D	1,250	
25900	SUMMERLIN RD	MATHEWS DR	COLONIAL BLVD	4LD	E	1,820	D	1,189	D	1,250	
26000	SUNRISE BLVD	BELL BLVD	COLUMBUS BLVD	2LN	E	860	C	42	C	53	Old Count
26100	SUNSHINE BLVD	SR 82	23RD ST SW	2LN	E	1,010	C	443	C	466	*
26150	SUNSHINE BLVD	23RD ST SW	LEE BLVD	2LN	E	1,010	C	443	C	466	*
26200	SUNSHINE BLVD	LEE BLVD	W 12TH ST	2LN	E	1,010	E	730	E	767	*
26300	SUNSHINE BLVD	W 12TH ST	W 75TH ST	2LN	E	860	D	600	D	630	
26400	SW 23RD ST	GUNNERY RD	SUNSHINE BLVD	2LN	E	860	E	855		1,012	Copperhead
26500	THREE OAKS PKWY	COCONUT RD	ESTERO PKWY	4LD	E	1,940	B	1,502	B	1,685	
26600	THREE OAKS PKWY	ESTERO PKWY	SAN CARLOS BLVD	4LD	E	1,940	B	855	B	964	
26700	THREE OAKS PKWY	SAN CARLOS BLVD	ALICO RD	4LD	E	1,940	B	855	B	1,198	
26800	TICE ST	SR 80	ORTIZ AVE	2LN	E	860	C	199	C	209	
26900	TICE ST	ORTIZ AVE	STALEY RD	2LN	E	860	C	188	D	701	Elementry U.
27000	TREELINE AVE	TERMINAL ACCESS RD	DANIELS PKWY	4LD	E	1,980	A	1,050	A	1,288	Harley Davidson
27030	TREELINE AVE	DANIELS PKWY	AMBERWOOD RD	4LD	E	1,980	A	799	A	840	
27070	TREELINE AVE	AMBERWOOD RD	COLONIAL BLVD	4LD	E	1,980	A	793	A	833	
29800	US 41 (S TAMIAI TR)	OLD 41	CORKSCREW RD	6LD	D	3,171	C	2,020	C	2,273	
29900	US 41 (S TAMIAI TR)	CORKSCREW RD	SANBEL BLVD	6LD	D	3,171	C	1,901	C	2,354	
30000	US 41 (S TAMIAI TR)	SANBEL BLVD	ALICO RD	6LD	D	3,171	C	2,069	C	2,812	
30100	US 41 (S TAMIAI TR)	ALICO RD	ISLAND PARK RD	6LD	D	3,171	C	2,069	C	2,467	

9/23/2021

LEE COUNTY Road Link Volumes (County- and State-Maintained Roadways)

LINK NO.	NAME	ROADWAY LINK		ROAD TYPE	PERFORMANCE STANDARD		2020 100TH HIGHEST HOUR		FORECAST FUTURE		NOTES
		FROM	TO		LOS	CAPACITY	LOS	VOLUME	LOS	VOLUME	
13400	IMMOKALEE RD (SR 82)	BELL BLVD	COUNTY LINE	4LD	D	3,240	B	569	B	698	
13500	IMPERIAL PKWY	COUNTY LINE	BONITA BEACH RD	4LD	E	1,920	B	1,009	B	1,061	
13550	IMPERIAL PKWY	E TERRY ST	COCONUT RD	4LD	E	1,920	B	973	B	1,023	
13600	IONA RD	DAVIS RD	McGREGOR BLVD	2LN	E	860	C	381	C	460	*
13700	ISLAND PARK RD	PARK RD	US 41	2LN	E	860	C	75	C	247	
13800	JOEL BLVD	BELL BLVD	18TH ST	4LN	E	2,120	B	625	B	835	Joel Blvd CPD
13900	JOEL BLVD	18TH ST	SR 80	2LN	E	1,010	D	490	D	515	
14000	JOHN MORRIS RD	BUNCHE BEACH	SUMMERLIN RD	2LN	E	860	C	63	C	71	old count projection
14100	JOHN MORRIS RD	SUMMERLIN RD	IONA RD	2LN	E	860	C	256	C	269	*
14200	KELLY RD	McGREGOR BLVD	SAN CARLOS BLVD	2LN	E	860	C	282	C	296	
14300	KELLY RD	SAN CARLOS BLVD	PINE RIDGE RD	2LN	E	860	C	106	C	120	old count projection(2010)
14500	LAUREL DR	BUS 41	BREEZE DR	2LN	E	860	C	430	C	458	
14600	LEE BLVD	SR 82	ALVIN AVE	6LD	E	2,840	B	2,335	B	2,454	
14700	LEE BLVD	ALVIN AVE	GUNNERY RD	6LD	E	2,840	B	2,037	B	2,216	
14800	LEE BLVD	GUNNERY RD	HOMESTEAD RD	6LD	E	2,840	B	2,257	B	2,372	
14900	LEE BLVD	HOMESTEAD RD	WILLIAMS AVE	4LD	E	1,980	B	1,006	B	1,057	
14930	LEE BLVD	WILLIAMS AVE	LEELAND HEIGHTS	2LN	E	1,020	C	1,006		1,057	
15000	LEE RD	SAN CARLOS BLVD	ALICO RD	2LN	E	860	C	544	D	614	old count projection(2015)
15100	LEELAND HEIGHTS	HOMESTEAD RD	JOEL BLVD	4LN	E	1,800	B	832	B	867	*
15200	LEONARD BLVD	GUNNERY RD	WESTGATE BLVD	2LN	E	860	E	843		917	
15300	LITTLETON RD	CORBETT RD	US 41	2LN	E	860	C	470	C	494	
15400	LITTLETON RD	US 41	BUS 41	2LN	E	860	C	496	C	522	
15500	LUCKETT RD	ORTIZ AVE	I-75	2LN	E	880	B	338	B	413	4 Ln design & ROW
15600	LUCKETT RD	I-75	COUNTRY LAKES DR	2LN	E	860	C	304	C	319	
15700	MAPLE DR*	SUMMERLIN RD	2ND AVE	2LN	E	860	C	77	C	89	old count projection
15800	McGREGOR BLVD	SANBELT PLAZA	HARBOR DR	4LD	E	1,960	B	1,176	B	1,236	
15900	McGREGOR BLVD	HARBOR DR	SUMMERLIN RD	4LD	E	1,960	B	1,105	B	1,162	
16000	McGREGOR BLVD	SUMMERLIN RD	KELLY RD	4LD	E	1,960	A	943	A	1,001	
16100	McGREGOR BLVD	KELLY RD	GLADIOLUS DR	4LD	E	1,960	A	943	A	991	
16200	McGREGOR BLVD (SR 867)	OLD McGREGOR BLVD/G	IONA LOOP RD	4LD	D	2,100	C	1,451	C	1,625	
16300	McGREGOR BLVD (SR 867)	IONA LOOP RD	PINE RIDGE RD	4LD	D	2,100	C	1,599	C	1,625	
16400	McGREGOR BLVD (SR 867)	PINE RIDGE RD	CYPRESS LAKE DR	4LD	D	2,100	C	1,599	C	1,798	
16500	McGREGOR BLVD (SR 867)	CYPRESS LAKE DR	COLLEGE PKWY	4LD	D	2,100	C	1,599	C	1,798	
16600	McGREGOR BLVD (SR 867)	COLLEGE PKWY	WINKLER RD	2LN	D	974	C	727	C	802	Constrained
16700	McGREGOR BLVD (SR 867)	WINKLER RD	TANGLEWOOD BLVD	2LN	D	970		1,057		1,168	Constrained
16800	McGREGOR BLVD (SR 867)	TANGLEWOOD BLVD	COLONIAL BLVD	2LN	D	970		1,057		1,168	Constrained
16900	METRO PKWY (SR 739)	SIX MILE PKWY	DANIELS PKWY	6LD	D	3,171	C	977	C	1,376	
17000	METRO PKWY (SR 739)	DANIELS PKWY	CRYSTAL DR	4LD	D	2,100	C	1,140	C	1,452	
17100	METRO PKWY (SR 739)	CRYSTAL DR	DANLEY DR	4LD	D	2,100	C	1,303	C	1,623	
17200	METRO PKWY (SR 739)	DANLEY DR	COLONIAL BLVD	4LD	D	2,100	C	1,349	C	1,880	
	MICHAEL RIPPE PKWY	US41	SIX MILES PKWY	6LD	D	3,171	C	1,070	C	1,537	
17600	MILWAUKEE BLVD	ALABAMA BLVD	BELL BLVD	2LN	E	860	C	171	C	180	*
17700	MILWAUKEE BLVD	BELL BLVD	COLUMBUS BLVD	2LN	E	860	C	171	C	184	*
17800	MOODY RD	HANCOCK B. PKWY	PONDELLA RD	2LN	E	860	C	183	C	206	old count projection(2009)
17900	NALLE GRADE RD	SLATER RD	NALLE RD	2LN	E	860	C	64	C	67	*
18000	NALLE RD	SR 78	NALLE GRADE RD	2LN	E	860	C	114	C	133	*
18100	NEAL RD	ORANGE RIVER BLVD	BUCKINGHAM RD	2LN	E	860	C	120	C	126	*
18200	NO RIVER RD	SR 31	FRANKLIN LOCK RD	2LN	E	1,140	A	164	B	283	
18300	NO RIVER RD	FRANKLIN LOCK RD	BROADWAY RD	2LN	E	1,140	A	164	B	309	
18400	NO RIVER RD	BROADWAY RD	COUNTY LINE	2LN	E	1,140	A	113	A	146	
18900	OLGA RD*	SR 80 W	SR 80 E	2LN	E	860	C	82	C	95	old count projection
19100	ORANGE GROVE BLVD	CLUB ENTR.	HANCOCK B. PKWY	2LN	E	860	C	393	C	488	old count(2009)
19200	ORANGE GROVE BLVD	HANCOCK B. PKWY	PONDELLA RD	4LN	E	1,790	C	514	C	645	
19300	ORANGE RIVER BLVD	SR 80	STALEY RD	2LN	E	1,000	D	510	D	536	
19400	ORANGE RIVER BLVD	STALEY RD	BUCKINGHAM RD	2LN	E	1,000	D	510	D	544	
19500	ORIOLE RD	SAN CARLOS BLVD	ALICO RD	2LN	E	860	C	147	C	154	
19600	ORTIZ AVE	COLONIAL BLVD	SR 82	2LN	E	900	C	805	C	846	
19700	ORTIZ AVE	SR 82	LUCKETT RD	2LN	E	900	C	838	C	880	4 Ln design & ROW
19800	ORTIZ AVE	LUCKETT RD	SR 80	2LN	E	900	B	350	B	368	4 Ln design & ROW
19900	PALM BEACH BLVD (SR 80)	PROSPECT AVE	ORTIZ AVE	4LD	D	2,100	C	1,096	C	1,210	
20000	PALM BEACH BLVD (SR 80)	ORTIZ AVE	I-75	6LD	D	3,171	C	1,096	C	1,205	
20100	PALM BEACH BLVD (SR 80)	I-75	SR 31	6LD	D	3,171	C	1,619	C	2,006	
20200	PALM BEACH BLVD (SR 80)	SR 31	BUCKINGHAM RD	4LD	D	2,100	C	1,619	C	1,905	
20300	PALM BEACH BLVD (SR 80)	BUCKINGHAM RD	WERNER DR	4LD	D	3,280	B	1,764	C	2,208	
20330	PALM BEACH BLVD (SR 80)	WERNER DR	JOEL BLVD	4LD	C	2,210	C	1,402	C	1,797	
20400	PALM BEACH BLVD (SR 80)	JOEL BLVD	HENDRY CO. LINE	4LD	C	2,210	B	1,224	C	1,541	
20500	PALONINO LN	DANIELS PKWY	PENZANCE BLVD	2LN	E	860	C	466	C	489	
20600	PARK MEADOWS DR	SUMMERLIN RD	US 41	2LN	E	860	C	196	C	206	
20800	PENZANCE BLVD	RANCHETTE RD	SIX MILE PKWY	2LN	E	860	C	147	C	159	

9/23/2021

LEE COUNTY Road Link Volumes (County- and State-Maintained Roadways)

LINK NO.	NAME	ROADWAY LINK		ROAD TYPE	PERFORMANCE STANDARD		2020 100TH HIGHEST HOUR		FORECAST FUTURE		NOTES
		FROM	TO		LOS	CAPACITY	LOS	VOLUME	LOS	VOLUME	
07400	CYPRESS LAKE DR	McGREGOR BLVD	SOUTH POINT BLVD	4LD	E	1,940	D	1,131	D	1,189	
07500	CYPRESS LAKE DR	SOUTH POINT BLVD	WINKLER RD	4LD	E	1,940	D	1,392	D	1,463	
07600	CYPRESS LAKE DR	WINKLER RD	SUMMERLIN RD	4LD	E	1,940	D	1,392	D	1,463	
07700	CYPRESS LAKE DR	SUMMERLIN RD	US 41	6LD	E	2,940	D	2,161	D	2,271	
07800	DANIELS PKWY	US 41	METRO PKWY	6LD	E	2,680	D	2,263	D	2,378	
07900	DANIELS PKWY	METRO PKWY	SIX MILE PKWY	6LD	E	2,680	D	2,109	E	2,520	Constrained
08000	DANIELS PKWY	SIX MILE PKWY	PALOMINO LN	6LD	E	3,040	E	3,030		3,303	Constrained
08100	DANIELS PKWY	PALOMINO LN	I-75	6LD	E	3,040	E	3,030		3,185	Constrained
08200	DANIELS PKWY	I-75	TREELINE AVE	6LD	E	3,260	A	2,396	B	2,518	
08300	DANIELS PKWY	TREELINE AVE	CHAMBERLIN PKWY	6LD	E	3,260	A	2,396	B	2,518	
08400	DANIELS PKWY	CHAMBERLIN PKWY	GATEWAY BLVD	6LD	E	3,260	B	2,737	B	2,876	
08500	DANIELS PKWY	GATEWAY BLVD	SR 82	4LD	E	2,160		2,355		2,632	Sky Walk, Timber Creek*
08600	DANLEY DR	US 41	METRO PKWY	2LN	E	860	C	273	C	304	
08700	DAVIS RD	McGREGOR BLVD	IONA RD	2LN	E	860	C	15	C	29	old count projection(2010)
08800	DEL PRADO BLVD	CAPE CORAL PKWY	SE 46TH ST	6LD	E	2,660	C	1,404	C	1,586	old count projection(2009)
08900	DEL PRADO BLVD	SE 46TH ST	CORONADO PKWY	6LD	E	2,660	C	1,404	C	1,586	old count projection(2009)
09000	DEL PRADO BLVD	CORONADO PKWY	CORNWALLIS PKWY	6LD	E	2,660	D	1,769	D	1,859	
09100	DEL PRADO BLVD	CORNWALLIS PKWY	CORAL POINT DR	6LD	E	2,660	D	2,090	D	2,196	
09200	DEL PRADO BLVD	CORAL POINT DR	HANCOCK B. PKWY	6LD	E	2,800	D	2,038	D	2,142	
09300	DEL PRADO BLVD	HANCOCK B. PKWY	SR 78	6LD	E	2,800	C	1,555	C	1,635	*
09400	DEL PRADO BLVD	US 41	SLATER RD	2LN	E	860	C	435	C	715	Crane Landing
09700	EAST 21ST ST	JOEL BLVD	GRANT AVE	2LN	E	860	C	29	C	30	*
09800	ESTERO BLVD	BIG CARLOS PASS BRIDGE	PESCADORA AVE	2LN	E	726	A	336	A	354	Constrained*
09900	ESTERO BLVD	PESCADORA AVE	VOORHIS ST	2LN	E	726	B	601	C	631	Constrained*
10000	ESTERO BLVD	VOORHIS ST	TROPICAL SHORES WAY	2LN	E	726	B	601	C	631	Constrained*
10100	ESTERO BLVD	TROPICAL SHORES WAY	CENTER ST	2LN	E	671		716		779	Constrained, old count(2010)
14400	ESTERO PKWY	US 41	THREE OAKS PKWY	4LD	E	2,000	B	790	B	1,083	East & West Cypress View*
14450	ESTERO PKWY	THREE OAKS PKWY	BEN HILL GRIFFIN PKWY	4LD	E	2,000	B	876	B	921	*
10200	EVERGREEN RD	US 41	BUS 41	2LN	E	860	C	100	C	116	old count projection
10300	FIDDLESTICKS BLVD	GUARDHOUSE	DANIELS PKWY	2LN	E	860	C	403	C	436	
10400	POWLER ST	US 41	N AIRPORT RD	6LD	E	2,300	D	1,251	D	1,315	
10500	POWLER ST	N AIRPORT RD	COLONIAL BLVD	6LD	E	2,300	D	1,496	D	1,572	
10800	GASPARILLA BLVD	FIFTH ST	COUNTY LINE	2LN	E	860	C	240	C	267	Constrained*
	GATEWAY BLVD	DANIELS PKWY	GATEWAY LAKES BLVD	4LD	E	1,790	C	1,233	C	1,296	
	GATEWAY BLVD	GATEWAY LAKES BLVD	SR82	2LN	E	860	C	505	C	531	Old Count
10900	GLADIOLUS DR	McGREGOR BLVD	PINE RIDGE RD	4LD	E	1,840	C	550	C	578	
11000	GLADIOLUS DR	PINE RIDGE RD	BASS RD	4LD	E	1,840	C	1,217	C	1,352	
11100	GLADIOLUS DR	BASS RD	WINKLER RD	6LD	E	2,780	C	1,217	C	1,279	
11200	GLADIOLUS DR	WINKLER RD	SUMMERLIN RD	6LD	E	2,780	B	1,217	B	1,279	
11300	GLADIOLUS DR	SUMMERLIN RD	US 41	6LD	E	2,780	C	2,089	C	2,195	
11400	GREENBRIAR BLVD	RICHMOND AVE	JOEL BLVD	2LN	E	860	C	75	C	79	*
11500	GUNNERY RD	SR 82	LEE BLVD	4LD	E	1,920	B	1,548	B	1,643	
11600	GUNNERY RD	LEE BLVD	BUCKINGHAM RD	2LN	E	1,020	C	870	C	1,005	
11700	HANCOCK BRIDGE PKWY	DEL PRADO BLVD	NE 24TH AVE	4LD	E	1,880	B	1,024	B	1,076	
11800	HANCOCK BRIDGE PKWY	NE 24TH AVE	ORANGE GROVE BLVD	4LD	E	1,880	B	1,414	B	1,486	
11900	HANCOCK BRIDGE PKWY	ORANGE GROVE BLVD	MOODY RD	4LD	E	1,880	B	1,394	B	1,465	
12000	HANCOCK BRIDGE PKWY	MOODY RD	US 41	4LD	E	1,880	B	1,394	B	1,465	
12100	HART RD	SR 78	TUCKER LANE	2LN	E	860	C	357	C	375	*
12200	HICKORY BLVD	BONITA BEACH RD	McLAUGHLIN BLVD	2LN	E	890	E	529	E	556	Constrained*
12300	HICKORY BLVD	McLAUGHLIN BLVD	MELODY LANE	2LN	E	890	E	529	E	556	Constrained*
12400	HICKORY BLVD	MELODY LANE	ESTERO BLVD	2LN	E	890	E	529	E	556	Constrained*
12480	HOMESTEAD RD	SR 82	MILWAUKEE BLVD	2LN	E	1,010	D	526	E	696	*
12490	HOMESTEAD RD	MILWAUKEE BLVD	SUNRISE BLVD	2LN	E	1,010	D	526	E	696	*
12500	HOMESTEAD RD	SUNRISE BLVD	LEELAND HEIGHTS	4LN	E	2,960	C	526	C	696	4 lane under construction
12600	HOMESTEAD RD	LEELAND HEIGHTS	LEE BLVD	4LN	E	2,960	C	963	C	1,059	
31800	I-75	BONITA BEACH RD	CORKSCREW RD	6LF	D	5,620	D	5,557		6,562	
31900	I-75	CORKSCREW RD	ALICO RD	6LF	D	5,620	D	4,907	E	5,804	
32000	I-75	ALICO RD	DANIELS PKWY	6LF	D	6,620	C	4,972	C	5,632	
32100	I-75	DANIELS PKWY	COLONIAL BLVD	6LF	D	5,620	C	4,544	D	5,435	
	I-75	COLONIAL BLVD	M.L.K.(SR 82)	6LF	D	5,620	C	4,336	D	5,036	
32300	I-75	M.L.K.(SR 82)	LUCKETT RD	6LF	D	5,620	C	4,596	D	5,253	
32400	I-75	LUCKETT RD	SR 80	6LF	D	6,620	B	4,363	C	4,933	
32500	I-75	SR 80	SR 78	6LF	D	6,620	B	3,635	B	4,145	
32600	I-75	SR 78	COUNTY LINE	6LF	C	4,670	B	2,696	B	2,990	
12700	IDLEWILD ST	METRO PKWY	RANCHETTE RD	2LN	E	860	C	200	C	210	
13000	IMMOKALEE RD (SR 82)	E OF COLONIAL BLVD	GATEWAY BLVD	6LD	D	3,171	C	1,701	C	2,177	
13100	IMMOKALEE RD (SR 82)	GATEWAY BLVD	GUNNERY RD	6LD	D	3,171	C	1,191	C	1,532	
13200	IMMOKALEE RD (SR 82)	GUNNERY RD	ALABAMA RD	6LD	D	4,860	B	1,385	B	1,683	
13300	IMMOKALEE RD (SR 82)	ALABAMA RD	BELL BLVD	4LD	D	3,240	B	564	B	688	

TRAFFIC DATA FROM LEE COUNTY
TRAFFIC COUNT REPORT

PCS 34 - Pondella Road east of Betmar Blvd

2021 AADT = 23,600 VPD

Hour	EB	WB	Total
0	0.28%	0.48%	0.75%
1	0.18%	0.30%	0.48%
2	0.18%	0.25%	0.42%
3	0.25%	0.18%	0.42%
4	0.48%	0.23%	0.71%
5	1.25%	0.57%	1.82%
6	2.82%	1.82%	4.64%
7	4.09%	2.45%	6.54%
8	3.43%	2.51%	5.94%
9	2.85%	2.49%	5.34%
10	2.76%	2.74%	5.50%
11	2.82%	3.04%	5.86%
12	2.88%	3.34%	6.22%
13	2.90%	3.46%	6.36%
14	2.95%	3.68%	6.63%
15	2.97%	4.22%	7.20%
16	3.01%	4.87%	7.88%
17	2.88%	5.08%	7.97%
18	2.42%	3.66%	6.08%
19	1.75%	2.59%	4.34%
20	1.29%	1.99%	3.27%
21	1.01%	1.51%	2.52%
22	0.70%	1.14%	1.84%
23	0.47%	0.78%	1.25%


Month of Year	Fraction
January	0.93
February	1.00
March	1.07
April	1.04
May	1.00
June	1.01
July	0.97
August	0.96
September	0.95
October	1.04
November	1.03
December	1.01

Day of Week	Fraction
Sunday	0.65
Monday	1.04
Tuesday	1.09
Wednesday	1.11
Thursday	1.11
Friday	1.13
Saturday	0.86


Directional Factor		
AM	0.63	EB
PM	0.62	WB

Design Hour Volume		
#	Volume	Factor
5	2403	0.102
10	2388	0.101
20	2351	0.100
30	2336	0.099
50	2306	0.098
100	2261	0.098
150	2224	0.094
200	2197	0.093

Hour of Day



Month of Year



PCS 17 - Hancock Bridge Pkwy west of Beau Dr

2021 AADT = 21,100 VPD

Hour	EB	WB	Total
0	0.26%	0.50%	0.75%
1	0.16%	0.31%	0.47%
2	0.14%	0.28%	0.42%
3	0.18%	0.17%	0.35%
4	0.34%	0.15%	0.49%
5	0.94%	0.35%	1.29%
6	2.63%	0.94%	3.57%
7	4.75%	1.68%	6.43%
8	3.89%	2.00%	5.88%
9	3.00%	2.21%	5.21%
10	2.91%	2.49%	5.40%
11	2.94%	2.88%	5.82%
12	3.03%	3.36%	6.39%
13	2.94%	3.53%	6.47%
14	2.99%	3.80%	6.79%
15	2.98%	4.34%	7.32%
16	3.05%	5.14%	8.19%
17	3.02%	5.48%	8.49%
18	2.42%	3.78%	6.21%
19	1.75%	2.82%	4.57%
20	1.36%	2.16%	3.52%
21	1.04%	1.68%	2.72%
22	0.70%	1.25%	1.95%
23	0.45%	0.84%	1.30%


Month of Year	Fraction
January	0.98
February	1.04
March	1.09
April	1.05
May	0.98
June	0.98
July	0.93
August	0.92
September	0.96
October	1.01
November	1.03
December	1.03

Day of Week	Fraction
Sunday	0.68
Monday	1.03
Tuesday	1.09
Wednesday	1.11
Thursday	1.1
Friday	1.13
Saturday	0.84


Directional Factor		
AM	0.74	EB
PM	0.63	WB

Design Hour Volume		
#	Volume	Factor
5	2336	0.111
10	2315	0.110
20	2280	0.108
30	2238	0.106
50	2210	0.105
100	2156	0.102
150	2119	0.100
200	2085	0.099

Hour of Day



Month of Year



PCS 40 - Del Prado Blvd south of Four Mile Cove Pkwy

2021 AADT =

45,000 VPD

Hour	NB	SB	Total
0	0.37%	0.31%	0.67%
1	0.22%	0.20%	0.42%
2	0.18%	0.16%	0.35%
3	0.15%	0.14%	0.29%
4	0.17%	0.22%	0.38%
5	0.36%	0.64%	1.00%
6	1.00%	1.55%	2.55%
7	1.91%	2.55%	4.46%
8	2.29%	2.89%	5.18%
9	2.71%	3.18%	5.89%
10	3.15%	3.47%	6.63%
11	3.43%	3.70%	7.13%
12	3.64%	3.81%	7.45%
13	3.67%	3.80%	7.47%
14	3.74%	3.76%	7.50%
15	3.84%	3.71%	7.55%
16	3.78%	3.74%	7.52%
17	3.79%	3.53%	7.32%
18	3.03%	3.03%	6.06%
19	2.34%	2.39%	4.73%
20	1.86%	1.80%	3.66%
21	1.46%	1.32%	2.77%
22	0.98%	0.89%	1.87%
23	0.60%	0.55%	1.15%


Month of Year	Fraction
January	0.99
February	1.04
March	1.07
April	1.05
May	1.01
June	0.99
July	0.97
August	0.96
September	0.96
October	0.99
November	0.96
December	1.01

Directional Factor		
AM	0.61	SB
PM	0.51	NB


Day of Week	Fraction
Sunday	0.75
Monday	1.03
Tuesday	1.06
Wednesday	1.09
Thursday	1.06
Friday	1.11
Saturday	0.92

Design Hour Volume		
#	Volume	Factor
5	4107	0.091
10	4049	0.090
20	4024	0.089
30	4001	0.089
50	3965	0.088
100	3905	0.087
150	3870	0.086
200	3844	0.085

Hour of Day



Month of Year



Updated 3/31/22			Daily Traffic Volume (AADT)									
STREET	LOCATION	Station #	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021
PALM BEACH BLVD (SR 80)	W OF SR 31	<u>5</u>	26300	26400	27600	30100	32900	33700	35200	36700	34000	39200
PALM BEACH BLVD (SR 80)	W OF BUCKINGHAM RD	<u>118</u>									26500	34700
PALOMINO RD	N OF DANIELS	501			6700		8200		8900		8600	
PAUL J DOHERTY PKWY	S OF DANIELS PKWY	51	2300	1600	1800							
PINE ISLAND RD	@ MATLACHA PASS	<u>3</u>	10200	10600	10800	11400	11500	11500	11600	11800	11300	
PINE ISLAND RD (SR 78)	E OF PONDELLA RD	<u>49</u>	22800	23100	25000	26800	28000	29100	29900	29700	27400	30000
PINE ISLAND RD (SR 78)	EAST OF MERCHANTS CROSSING	108				26100	28500	30400	30100	29300	28300	29600
PINE ISLAND RD (SR 78)	E OF SW 19TH AVE	<u>57</u>				13300	13700	14400	14200	13400		18600
PINE ISLAND RD (SR 78)	W OF NICHOLAS BLVD	<u>113</u>									30300	36900
PINE RIDGE RD	N OF SUMMERLIN RD	368		5000		5600		5600				
PINE RIDGE RD	S OF McGREGOR BLVD	367	5700	5600	4600	5500	5600	5200	5300	5800	5500	
PLANTATION RD	S OF COLONIAL BLVD	328		11500		11000	14300	13100	12700	14900	8400	12100
PLANTATION RD	N OF DANIELS PKWY	370			12400		14200		11900		12200	
PLANTATION RD	N OF SIX MILE CYPRESS	521			5500		6400		5100		4700	
PONDELLA RD	E OF PINE ISLAND RD	373				12000		14900				18200
PONDELLA RD	E OF BETMAR BLVD	<u>34</u>	17700	18000	19000	20000	21000	21300	21600	22000	20800	23600
PONDELLA RD	W OF BUSINESS 41	374		17100	17100		19800					24500
RAY AVE	N OF MEADOW RD	533								4900		
RIVER RANCH RD	S OF CORKSCREW RD	466										2200
SAN CARLOS BLVD	S OF PRESCOTT ST	<u>8</u>	22200	22500	22800	22400	22400	22800	22000	22100	22700	24000

Updated 3/31/22			Daily Traffic Volume (AADT)									
STREET	LOCATION	Station #	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021
GLADIOLUS DR	E OF SAN CARLOS BLVD	284		7600		13100		13100		11000		11400
GLADIOLUS DR	E OF A&W BULB RD	<u>39</u>	19200	19800	20500	21900	22600	23000	22500	23200	19800	21900
GLADIOLUS DR	W OF US 41	<u>46</u>	40800	37600	38900	40600	42000	42700	41500	43200	39000	44900
GRIFFIN DR	S OF SR 82	534								8000		
GUNNERY RD	N OF IMMOKALEE RD	290	20200	17600	18300	19100	21500	20400			26300	25800
GUNNERY RD	N OF LEE BLVD (CR 884)	289	15800	13600	13600	15100	14800	15500	15800	15700	16700	
GUNNERY RD	S OF BUCKINGHAM RD					7800						
HANCOCK BRIDGE PKWY	W OF BEAU DR	<u>17</u>	17900	18400	20600	21500	22000	22200	23700	22900	19700	21100
HANCOCK BRIDGE PKWY	E OF ORANGE GROVE BLVD	116									15900	
HANCOCK BRIDGE PKWY	W OF ORANGE GROVE BLVD	292		20900	20900	20900	23800	21300	23800	23700	21400	22700
HART RD	N OF BAYSHORE RD (SR 78)	298		6000		6500		6800				
HOMESTEAD RD	@ WESTMINSTER RD	<u>6</u>	26200	24000	24800	26200	27000	27100	27500	26100	20000	26400
HOMESTEAD RD	S OF ARTHUR RD	451	10900	10100	10400	11600	11800	11700				
HOMESTEAD RD	N OF IMMOKOLEE RD	456								1900		
IMMOKALEE RD (SR 82)	W OF COLONIAL BLVD	90				25900	28800			30700	29900	
IMMOKALEE RD (SR 82)	E OF GUNNERY RD	<u>21</u>	25200	23800	25100	26700	28000	26100		28000	27600	36500
IMPERIAL PKWY	N OF STRIKE LN	<u>63</u>	9300	9900	11000	13200	13000	14200	14800	15000	11700	13500
IMPERIAL PKWY	S OF BONITA BEACH RD	492						22200		20200		
IONA RD	W OF McGREGOR BLVD	303		6800		7100		7200		7000		
JOEL BLVD (CR 884)	E OF BELL BLVD	306	14100	12700	13400	14100	14500	14100	13600	14800	13900	

**TRAFFIC DATA FROM FDOT'S
DISTRICT ONE LOS SPREADSHEET**

Section No.	State Road No.	Local Road Name	From	From M.P.	To	To M.P.	Section Length	SIS	Existing Control Class	Functional Classification	Posted Speed	Asse Type	Facility Type	FOOT LOS Std	Count y LOS Std	Cpy LOS Std	Year 2021									
																	Arterial Class	Divided/Undivided	One/Two Way	Left Turn Bays	Right Turn Bays	Thru Lanes	Peak Hour Peak Direction			
																							Capacity	Volume	LOS	
12000040	SR 739	HANSON ST	Fowler St	1.130	Old Metro Pkwy	1.751	0.621		C3C	Principal Arterial-other	30	UA	A	D	D	E	2	U	2W	WL	WR	2	788	601	D	
12001000	US 41	FOWLER ST/US 41 SB	SR 80 (Fier St)	0.000	N End of Edison Bridge	1.029	1.029		C4	Principal Arterial-other	45	UA	A	D	D	E	1	U	1W	OL	OR	3	3,624	1,618		
12001000	US 41	N TAMAMI TRUS 41	N End of Edison Bridge	1.029	SR 78/Pine Island Rd/Bayshore Rd	2.731	1.702		C4	Principal Arterial-other	40	UA	A	D	D		1	D	2W	WL	WR	6	3,171	1,715	C	
12001000	US 41	N TAMAMI TRUS 41	SR 78/Pine Island Rd/Bayshore Rd	2.731	Littleton Rd	3.838	1.107		C3C	Principal Arterial-other	45	UA	A	D	D		1	D	2W	WL	WR	4	2,100	994		
12001000	US 41	N TAMAMI TRUS 41	Littleton Rd	3.838	US 41 SB	5.137	1.299		C3C	Principal Arterial-other	45	UA	A	D	D		1	D	2W	WL	WR	4	2,100	596	C	
12001000	US 41	N TAMAMI TRUS 41	US 41 SB	5.137	SR 45/US 41	5.257	0.120		C3C	Principal Arterial-other	45	UA	A	D	D		1	U	1W	OL	OR	1	887	486	C	
12001101	US 41	EVANS AVE/PARK AVE/US 41 NB	SR 82/MLK Blvd	0.680	N End of Edison Bridge	2.290	1.600		C4	Principal Arterial-other	45	UA	A	D	D	E	1	U	1W	OL	OR	3	3,624	1,958	C	
12004000	SR 865	SAN CARLOS BLVD	Estero Blvd	0.000	CR 869 (Summerlin Rd)	3.118	3.118		C3C	Minor Arterial	45	UA	A	D	D		1	D	2W	WL	WR	4	2,100	1,051	C	
12004000	SR 865	SAN CARLOS BLVD	CR 869 (Summerlin Rd)	3.118	CR 867/Old McGregor Blvd	4.778	1.660		C3C	Minor Arterial	45	UA	A	D	D		1	D	2W	WL	WR	2	370	722	C	
12004000	SR 865	SIX MILE CYPRESS PKWY	SR 45/US 41	9.570	SR 739 (Metro Pkwy)	10.726	1.156		C3C	Minor Arterial	50	UA	A	D	D		1	D	2W	WL	WR	4	2,100	1,941	C	
12005000	SR 894	COLONIAL BLVD	SR 45/US 41	1.171	SR 739 (Metro Pkwy)	2.450	1.319		C3C	Principal Arterial-other	45	UA	A	D	D	E	1	D	2W	WL	WR	6	3,171	2,912	C	
12005000	SR 894	COLONIAL BLVD	SR 739 (Metro Pkwy)	2.450	Winkler Ave	4.612	2.122		C3C	Principal Arterial-other	55	UA	A	D	D	E	1	D	2W	WL	WR	6	3,171	2,831	C	
12005000	SR 894	COLONIAL BLVD	Winkler Ave	4.612	I-75	5.676	1.064		C3C	Principal Arterial-other	45	UA	A	D	D	E	1	D	2W	WL	WR	6	3,171	3,599	F	
12005000	SR 894	COLONIAL BLVD	I-75	5.676	400 Ft E. of Dunaway Dr	6.460	0.784		C3C	Principal Arterial-other	45	UA	A	D	D	E	1	D	2W	WL	WR	6	3,171	3,584	F	
12010000	US 41	S TAMAMI TRAIL	Collier County Line	0.000	Terry St/Bonita Bay Blvd	2.125	2.125		C3C	Principal Arterial-other	50	UA	A	D	D	E	1	D	2W	WL	WR	6	3,171	1,913	C	
12010000	US 41	S TAMAMI TRAIL	Terry St/Bonita Bay Blvd	2.125	CR 887/Old US 41 Rd/Pelican L	4.420	2.291		C3C	Principal Arterial-other	50	UA	A	D	D	E	1	D	2W	WL	WR	6	3,171	2,246	C	
12010000	US 41	S TAMAMI TRAIL	CR 887/Old US 41 Rd/Pelican L	4.420	CR 850 (Corkscrew Rd)	7.929	3.509		C3C	Principal Arterial-other	50	UA	A	D	D	E	1	D	2W	WL	WR	6	3,171	2,342	C	
12010000	US 41	S TAMAMI TRAIL	CR 850 (Corkscrew Rd)	7.929	Estero Pkwy	9.292	1.363		C3C	Principal Arterial-other	50	UA	A	D	D		1	D	2W	WL	WR	6	3,171	2,294	C	
12010000	US 41	S TAMAMI TRAIL	Estero Pkwy	9.292	San Carlos Blvd	10.403	1.111		C3C	Principal Arterial-other	50	UA	A	D	D		1	D	2W	WL	WR	6	3,171	2,318	C	
12010000	US 41	S TAMAMI TRAIL	San Carlos Blvd	10.403	Inland Park Rd	13.807	3.404		C3C	Principal Arterial-other	50	UA	A	D	D		1	D	2W	WL	WR	6	3,171	2,576	C	
12010000	US 41	S TAMAMI TRAIL	Inland Park Rd	13.807	SR 865/CR 865 (Gladstone Dr)	15.780	1.973		C3C	Principal Arterial-other	45	UA	A	D	D		1	D	2W	WL	WR	6	3,171	3,002	C	
12010000	US 41	S TAMAMI TRAIL	SR 865/CR 865 (Gladstone Dr)	15.780	Daniels Pkwy/Cypress Lake Dr	17.051	1.271		C3C	Principal Arterial-other	45	UA	A	D	D		1	D	2W	WL	WR	6	3,171	2,509	C	
12010000	US 41	CLEVELAND AVE	Daniels Pkwy/Cypress Lake Dr	17.051	S Airport Rd	19.162	2.111		C3C	Principal Arterial-other	45	UA	A	D	D		1	D	2W	WL	WR	6	3,171	2,598	C	
12010000	US 41	CLEVELAND AVE	S Airport Rd	19.162	Winkler Ave	21.047	1.885		C3C	Principal Arterial-other	45	UA	A	D	D	E	1	D	2W	WL	WR	6	3,171	2,418	C	
12010000	US 41	CLEVELAND AVE	Winkler Ave	21.047	Hanson St	22.298	1.251		C4	Principal Arterial-other	40	UA	A	D	D	E	1	D	2W	WL	WR	6	3,171	2,082	C	
12010000	US 41	CLEVELAND AVE	Hanson St	22.298	Johnson St	23.391	1.093		C4	Principal Arterial-other	40	UA	A	D	D	E	1	D	2W	WL	OR	6	3,020	1,872	C	
12010000	US 41	CLEVELAND AVE	Johnson St	23.391	CR 78A/Pondella Rd	25.681	2.290		C3C	Principal Arterial-other	45	UA	A	D	D	E	1	D	2W	WL	WR	4	2,100	1,996	C	
12010000	US 41	CLEVELAND AVE	CR 78A/Pondella Rd	25.681	Littleton Rd	27.964	2.283		C3C	Principal Arterial-other	55	UA	A	D	D		1	D	2W	WL	WR	4	2,100	1,362	C	

12040000	US 41	FOWLER ST	SR 739(Hanson St)	2.235	SR 82(MLK J Blvd)	3.556	1.261		C4	Principal Arterial-Other	35	UA	A	D	D	E	2	U	2W	WL	WR	4	1548	1051	C
12040000	US 41	FOWLER ST	SR 82(MLK Blvd)	3.556	SR 80(Fire St)	4.000	0.444		C4	Principal Arterial-Other	35	UA	A	D	D	E	2	U	2W	WL	WR	3	3175	2.204	D
12040000	SR 739	EVANS AVE	Hanson St	8.733	SR 82(MLK J Blvd)	10.000	1.267		NO DATA	Principal Arterial-Other	40	UA	A	D	D	E	1	U	2W	WL	WR	3	3.805		F
12017000	SR 739	EVANS AVE	Hanson St	1.060	SR 82(MLK J Blvd)	2.330	1.270		C3C	Principal Arterial-Other	40	UA	A	D	D	E	1	U	2W	WL	WR	3	3.805		F
12020000	SR 80	MAIN ST	US 41(Cleveland Ave)	0.000	SR 82(Marion St)	0.168	0.168		C5	Principal Arterial-Other	30	UA	A	D	D	E	2	U	2W	WL	WR	3	1.207	387	C
12020000	SR 80	1ST ST	SR 739/US 41 Bus (Fowler St)	0.658	SR 80/Seaboard St	1.666	1.008		C3C	Principal Arterial-Other	35	UA	A	D	D	E	2	U	2W	WL	WR	2	2.054	728	C
12020000	SR 80	PALM BEACH BLVD	SR 80/Seaboard St	1.666	CR 808 (Orie Ave)	4.364	2.698		C3C	Principal Arterial-Other	45	UA	A	D	D	E	1	D	2W	WL	WR	4	2.100	1.038	C
12020000	SR 80	PALM BEACH BLVD	CR 808 (Orie Ave)	4.364	L-75	5.546	1.982		C3C	Principal Arterial-Other	45	UA	A	D	D		1	D	2W	WL	WR	6	3.171	1.243	C
12020000	SR 80	PALM BEACH BLVD	L-75	5.546	SR 311(Arcadia Rd)	8.249	2.703	SS	C3C	Principal Arterial-Other	55	UA	A	D	D		1	D	2W	WL	WR	6	3.171	1.616	C
12020000	SR 80	PALM BEACH BLVD	SR 311(Arcadia Rd)	8.249	CR 804(Buckingham Rd/Old Ogle)	10.741	2.492	SS	C3C	Principal Arterial-Other	45	UA	A	D	D		1	D	2W	WL	WR	4	2.100	2.043	D
12020000	SR 80	PALM BEACH BLVD	CR 804(Buckingham Rd/Old Ogle)	10.741	Hickory Creek Rd	13.308	2.567	SS	C2	Principal Arterial-Other	55	UA	H	D	D			D	2W	WL	WR	4	3.280	1.426	B
12020000	SR 80	PALM BEACH BLVD	Hickory Creek Rd	13.308	CR 884 (Joel Blvd)	18.227	4.918	SS	C2	Principal Arterial-Other	55	ROA	H	C	C			D	2W	WL	WR	4	2.210	1.179	B
12020000	SR 80	PALM BEACH BLVD	CR 884 (Joel Blvd)	18.227	Hendry County Line	20.340	2.113	SS	C2	Principal Arterial-Other	60	ROA	H	C	C			D	2W	WL	WR	4	2.210	1.053	B
12020102	SR 80 EE	SR 80/2ND ST/SEABOARD ST	SR 739 (Fowler St)	0.337	SR 80/Palm Beach Blvd	1.560	1.163		C4	Principal Arterial-Other	35	UA	A	D	D	E	2	U	2W	WL	OR	2	1.958	992	D
12040000	SR 867	MCGREGOR BLVD	Old McGregor Blvd	0.000	A & W Blvd Rd	1.993	1.993		C3C	Minor Arterial	45	UA	A	D	D		1	D	2W	WL	WR	4	2.100	1.465	C
12040000	SR 867	MCGREGOR BLVD	A & W Blvd Rd	1.993	College Pkwy	3.485	1.472		C3C	Minor Arterial	45	UA	A	D	D		1	D	2W	WL	WR	4	2.100	1.874	C
12040000	SR 867	MCGREGOR BLVD	College Pkwy	3.485	Winder Rd	4.896	1.431		C3R	Minor Arterial	40	UA	A	D	D		1	U	2W	WL	WR	2	924	726	C
12040000	SR 867	MCGREGOR BLVD	Winder Rd	4.896	CR 884/Colonial Blvd	6.485	1.589		C3R	Minor Arterial	40	UA	A	D	D	E	1	D	2W	WL	WR	2	970	1.039	F
12060000	SR 78	PINE ISLAND RD	CR 785/CR 884/Buena Vista Rd	5.487	Chiquita Blvd	7.514	2.047		C3C	Principal Arterial-Other	50	UA	A	D	D	E	1	D	2W	WL	WR	4	2.100	1.052	C
12060000	SR 78	PINE ISLAND RD	Chiquita Blvd	7.514	Santa Barbara Blvd	9.757	2.243		C3C	Principal Arterial-Other	50	UA	A	D	D	E	1	D	2W	WL	WR	4	2.100	1.052	C
12060000	SR 78	PINE ISLAND RD	Santa Barbara Blvd	9.757	Del Prado Blvd	12.061	2.304		C3C	Principal Arterial-Other	55	UA	A	D	D	E	1	D	2W	WL	WR	4	2.100	1.465	C
12060000	SR 78	PINE ISLAND RD	Del Prado Blvd	12.061	Hancock Creek Blvd/NE 24th Ave	13.248	1.987		C3C	Principal Arterial-Other	55	UA	A	D	D	E	1	D	2W	WL	WR	4	2.100	1.468	C
12060000	SR 78	PINE ISLAND RD	Hancock Creek Blvd/NE 24th Ave	13.248	SR 45/US 41(Cleveland Ave)	14.741	1.493		C3C	Principal Arterial-Other	55	UA	A	D	D		1	D	2W	WL	WR	4	2.100	1.821	C
12060000	SR 78	PINE ISLAND RD	SR 45/US 41(Cleveland Ave)	14.741	SR 739/US 41 Bus	15.958	1.117		C3C	Principal Arterial-Other	40	UA	A	D	D			D	2W	WL	WR	4	2.100	1.975	C
12060000	SR 78	BAYSHORE RD	SR 739/US 41 Bus	15.958	New Post Rd/Hart Rd	17.015	1.157		C3R	Principal Arterial-Other	50	UA	A	D	D		1	D	2W	WL	WR	4	2.100	1.975	C
12060000	SR 78	BAYSHORE RD	New Post Rd/Hart Rd	17.015	Cann Rd/Stacer Rd	18.235	1.270		C3R	Principal Arterial-Other	50	UA	A	D	D		1	D	2W	WL	WR	4	2.100	1.971	C
12060000	SR 78	BAYSHORE RD	Cann Rd/Stacer Rd	18.235	W of Pritchett Pkwy	21.179	2.944		C2	Principal Arterial-Other	50	UA	A	D	D		1	D	2W	WL	WR	4	2.100	1.222	C
12060000	SR 78	BAYSHORE RD	W of Pritchett Pkwy	21.179	SR 31	24.404	3.225		C3R	Minor Arterial	50	UA	A	D	D		1	U	2W	WL	WR	2	924	741	C
12070000	SR 82	DR M L KING JR BLVD	US 41/US 45	0.000	SR 739 (Fowler St)	0.845	0.845		C4	Minor Arterial	30	UA	A	D	D	E	2	D	2W	WL	WR	2	827	421	D
12070000	SR 82	DR M L KING JR BLVD	SR 739 (Fowler Ave)	0.845	Michigan Link Ave	2.966	2.321		C4	Principal Arterial-Other	30	UA	A	D	D	E	2	D	2W	WL	WR	4	1.712	1.888	F
12070000	SR 82	DR M L KING JR BLVD	Michigan Link Ave	2.966	W of Teter Rd/75 NB On Ramp	4.507	1.541		C3C	Principal Arterial-Other	50	UA	A	D	D	E	1	D	2W	WL	WR	6	3.171	2.194	C
12070000	SR 82	IMMOKALEE ROAD	W of Teter Rd/75 NB On Ramp	4.507	Buckingham Rd	6.154	1.647	SS	C3C	Principal Arterial-Other	50	UA	A	D	D	D	1	D	2W	WL	WR	6	3.171	1.906	C
12070000	SR 82	IMMOKALEE ROAD	Buckingham Rd	6.154	SR 45/US 41(Cleveland Ave)	7.906	1.752	SS	C2	Principal Arterial-Other	55	UA	A	D	D		1	D	2W	WL	WR	6	3.171	1.882	C
12070000	SR 82	IMMOKALEE ROAD	Gateway Blvd	7.906	Griffin Dr/Ray Ave S	9.314	1.408	SS	C3R	Principal Arterial-Other	55	UA	A	D	D		1	D	2W	WL	WR	6	3.171	1.362	C
12070000	SR 82	IMMOKALEE ROAD	Griffin Dr/Ray Ave S	9.314	Daniels Pkwy/Gunnery Rd S	11.123	1.809	SS	C3R	Principal Arterial-Other	60	UA	A	D	D		1	D	2W	WL	WR	6	3.171	1.790	C
12070000	SR 82	IMMOKALEE ROAD	Daniels Pkwy/Gunnery Rd S	11.123	Alabama Rd	14.709	3.586	SS	C3R	Principal Arterial-Other	60	UA	H	D	D			D	2W	WL	WR	6	4.920	1.326	B
12070000	SR 82	IMMOKALEE ROAD	Alabama Rd	14.709	Bell Blvd S	18.929	4.220	SS	C3R	Principal Arterial-Other	60	UA	H	D	D			D	2W	WL	WR	4	3.260	750	R
12070000	SR 82	IMMOKALEE ROAD	Bell Blvd S	18.929	Hendry County Line	21.551	2.622	SS	C3R	Principal Arterial-Other	60	UA	H	D	D			D	2W	WL	OR	4	3.280	707	B

TRAFFIC DATA
FDOT FLORIDA TRAFFIC ONLINE
FOR US BUSINESS 41

FLORIDA DEPARTMENT OF TRANSPORTATION
TRANSPORTATION STATISTICS OFFICE
2021 HISTORICAL AADT REPORT

COUNTY: 12 - LEE

SITE: 5043 - SR 739/US BUS41, NORTH OF PONDELLA ROAD LC397

YEAR	AADT		DIRECTION 1	DIRECTION 2	*K FACTOR	D FACTOR	T FACTOR
2021	30500 C	N	16000	S 14500	9.00	52.60	7.80
2020	25500 C	N	13500	S 12000	9.00	51.70	9.20
2019	32000 C	N	16500	S 15500	9.00	52.00	5.90
2018	31000 C	N	16000	S 15000	9.00	52.30	6.10
2017	27500 C	N	14500	S 13000	9.00	53.20	6.20
2016	31000 C	N	16000	S 15000	9.00	57.90	5.60
2015	28500 C	N	14500	S 14000	9.00	58.40	6.40
2014	29500 C	N	15000	S 14500	9.00	56.40	4.90
2013	23500 F	N	13000	S 10500	9.00	64.00	4.90
2012	23500 C	N	13000	S 10500	9.00	63.40	4.90
2011	23000 F	N	12500	S 10500	9.00	62.50	5.20
2010	23500 C	N	13000	S 10500	11.16	63.35	5.20
2009	23500 C	N	13000	S 10500	11.00	63.18	5.20
2008	23500 C	N	13000	S 10500	11.56	68.04	5.40
2007	27500 C	N	14500	S 13000	9.62	58.02	4.90
2006	33500 C	N	18000	S 15500	8.81	55.95	6.80

AADT FLAGS: C = COMPUTED; E = MANUAL ESTIMATE; F = FIRST YEAR ESTIMATE

S = SECOND YEAR ESTIMATE; T = THIRD YEAR ESTIMATE; R = FOURTH YEAR ESTIMATE

V = FIFTH YEAR ESTIMATE; 6 = SIXTH YEAR ESTIMATE; X = UNKNOWN

*K FACTOR: STARTING WITH YEAR 2011 IS STANDARDK, PRIOR YEARS ARE K30 VALUES

FLORIDA DEPARTMENT OF TRANSPORTATION
TRANSPORTATION STATISTICS OFFICE
2021 HISTORICAL AADT REPORT

COUNTY: 12 - LEE

SITE: 5027 - SR 739/US BUS41, NORTH OF POWELL DRIVE LC394

YEAR	AADT		DIRECTION 1	DIRECTION 2	*K FACTOR	D FACTOR	T FACTOR
2021	21000 C	N	11000	S 10000	9.00	52.60	11.20
2020	21500 C	N	11000	S 10500	9.00	51.70	7.00
2019	20500 C	N	10500	S 10000	9.00	52.00	7.30
2018	18800 C	N	9600	S 9200	9.00	52.30	7.50
2017	18400 C	N	9400	S 9000	9.00	53.20	9.00
2016	18900 C	N	9700	S 9200	9.00	57.90	6.30
2015	17200 C	N	8800	S 8400	9.00	58.40	6.00
2014	17300 F	N	8800	S 8500	9.00	56.40	5.50
2013	16300 C	N	8300	S 8000	9.00	64.00	5.50
2012	13900 C	N	7100	S 6800	9.00	63.40	6.10
2011	15400 F	N	7800	S 7600	9.00	62.50	4.90
2010	15800 C	N	8000	S 7800	11.16	63.35	4.90
2009	16400 C	N	8300	S 8100	11.00	63.18	6.00
2008	17100 C	N	8600	S 8500	11.56	68.04	7.10
2007	16800 C	N	8500	S 8300	9.62	58.02	5.70
2006	17800 C	N	9000	S 8800	8.81	55.95	9.80

AADT FLAGS: C = COMPUTED; E = MANUAL ESTIMATE; F = FIRST YEAR ESTIMATE

S = SECOND YEAR ESTIMATE; T = THIRD YEAR ESTIMATE; R = FOURTH YEAR ESTIMATE


V = FIFTH YEAR ESTIMATE; 6 = SIXTH YEAR ESTIMATE; X = UNKNOWN

*K FACTOR: STARTING WITH YEAR 2011 IS STANDARDK, PRIOR YEARS ARE K30 VALUES


**TRAFFIC DATA FROM FDOT'S
DISTRICT ONE LOS SPREADSHEET
FOR US BUSINESS 41**

State Road No.	Local Road Name	From	From M.P.	To	To M.P.	Section Length	SIS	Exhibit & Contact Class	Functional Classification	Posted Speed	Area Type	Facility Type	FDOT LOS	County LOS	City LOS	Year 2021											
																Arterial Class	Divided/ UnDivided	One/Two Way	Left Turn Bays	Right Turn Bays	Thru Lanes	Peak Hour Peak Direction					
																						Capacity	Volume	LOS			
SS 130	HAUSCH ST	Fowler St	1.150	Old Mine Place	1.171	0.021		C3C	Principal Arterial-Other	30	U/A	A	D	D	E	1	U	2W	1WL	1VR	1	755	82%	C			
US 41	FOWLER ST/US 41 SE	SR 40 East St	0.000	N. End of Edison Bridge	1.029	1.029		C4	Principal Arterial-Other	40	U/A	A	D	D	E	1	U	2W	1WL	1VR	2	1,214	1,013	C			
US 41	N TAYLOR TR/US 41	N. End of Edison Bridge	1.029	SR 75/Pine Island Rd/Bayshore Rd	2.731	1.702		C4	Principal Arterial-Other	40	U/A	A	D	D	E	1	D	2W	1WL	1VR	4	1,171	1,121	C			
US 41	SR 41/US 41	SR 75/Pine Island Rd/Bayshore Rd	1.731	Littleton Rd	2.838	1.107		C3C	Principal Arterial-Other	40	U/A	A	D	D	E	1	D	2W	1WL	1VR	4	1,171	1,121	C			
US 41	N TAYLOR TR/US 41	Littleton Rd	2.838	US 41 SE	2.137	0.699		C3C	Principal Arterial-Other	40	U/A	A	D	D	E	1	D	2W	1WL	1VR	4	1,171	1,121	C			
US 41	N TAYLOR TR/US 41	US 41 SE	2.137	SR 40/US 41	2.237	0.100		C3C	Principal Arterial-Other	40	U/A	A	D	D	E	1	U	2W	1WL	1VR	1	557	45%	C			
US 41	EVANS AVE/PARK AVE/US 41 NB	SR 82/MLK Blvd	0.000	N. End of Edison Bridge	2.290	1.000		C4	Principal Arterial-Other	40	U/A	A	D	D	E	1	U	1W	0L	0R	3	1,024	1,026	C			

2045 E+C NETWORK VOLUMES



2045 E+C FINANCIALLY FEASIBLE ROADWAY NETWORK LANES AND VOLUMES



**LEE COUNTY MPO 2045 COST
FEASIBLE HIGHWAY PLAN**



TRAFFIC COUNTS
BARRETT ROAD
@ WESTCREEK CIRCLE

Barrett Rd @ Westcreek Cir 11-3-22 AM

File Name: Barrett Rd @ Westcreek Cir 11-3-22 AM

Location:

Cars and Peds

Site Code:

Study Date: 11/03/2022

Time	Barrett Rd Southbound						Westbound						Barrett Rd Northbound						Westcreek Cir Eastbound						Int Total
	Peds	Right	Thru	Left	U-Turn	Appr Total	Peds	Right	Thru	Left	U-Turn	Appr Total	Peds	Right	Thru	Left	U-Turn	Appr Total	Peds	Right	Thru	Left	U-Turn	Appr Total	
07:00		2	32	0	0	34						0		0	51	2	0	53		3	0	1	0	4	91
07:15		0	30	0	0	30						0		0	48	2	0	50		2	0	2	0	4	84
07:30		0	39	0	0	39						0		0	37	1	0	38		1	0	4	0	5	82
07:45		2	51	0	0	53						0		0	41	2	0	43		3	0	2	0	5	101
Total	0	4	152	0	0	156	0	0	0	0	0	0	0	0	177	7	0	184	0	9	0	9	0	18	358
08:00		1	31	0	0	32						0		0	26	2	0	28		6	0	1	0	7	67
08:15		2	31	0	0	33						0		0	29	2	0	31		2	0	0	0	2	66
08:30		0	33	0	0	33						0		0	30	2	0	32		3	0	0	0	3	68
08:45		3	37	0	0	40						0		0	34	1	0	35		2	0	4	0	6	81
Total	0	6	132	0	0	138	0	0	0	0	0	0	0	0	119	7	0	126	0	13	0	5	0	18	282
Grand Total	0	10	284	0	0	294	0	0	0	0	0	0	0	0	296	14	0	310	0	22	0	14	0	36	640
Appr %		3.4	96.6	0	0			-2	-2	-2	-2			0	95.5	4.5	0			61.1	0	38.9	0		
Total %		1.6	44.4	0	0			0	0	0	0			0	46.3	2.2	0			3.4	0	2.2	0		
AM Pk Hr		07:00	07:00	07:00	07:00	07:00		07:00	07:00	07:00	07:00	07:00		07:00	07:00	07:00	07:00	07:00		07:00	07:00	07:00	07:00	07:00	07:00
AM Pk Vol		4	152	0	0	156		0	0	0	0	0		0	177	7	0	184		9	0	9	0	18	358
AM PHF		0.500	0.745	NaN	NaN	0.736		NaN	NaN	NaN	NaN	NaN		NaN	0.868	0.875	NaN	0.868		0.750	NaN	0.563	NaN	0.900	0.886

Barrett Rd @ Westcreek Cir 11-3-22 AM


File Name: Barrett Rd @ Westcreek Cir 11-3-22 AM

Location:

All Vehicles

Site Code:

Study Date: 11/03/2022



Barrett Rd @ Westcreek Cir 11-3-22 PM

File Name: Barrett Rd @ Westcreek Cir 11-3-22 PM

Location:

Cars and Peds

Site Code:

Study Date: 11/03/2022

Time	Barrett Rd Southbound						Westbound						Barrett Rd Northbound						Westcreek Cir Eastbound						Int Total
	Peds	Right	Thru	Left	U-Turn	Appr Total	Peds	Right	Thru	Left	U-Turn	Appr Total	Peds	Right	Thru	Left	U-Turn	Appr Total	Peds	Right	Thru	Left	U-Turn	Appr Total	
16:00		4	46	0		50						0		0	34	4		38		1	0	1		2	90
16:15		2	40	0	0	42						0		0	43	7	0	50		4	0	4	0	8	100
16:30		1	48	0	0	49						0		0	33	5	0	38		2	0	2	0	4	91
16:45		2	33	0	0	35						0		0	27	6	0	33		6	0	4	0	10	78
Total	0	9	167	0	0	176	0	0	0	0	0	0	0	0	137	22	0	159	0	13	0	11	0	24	359
17:00		3	59	0	0	62						0		0	49	4	0	53		3	0	3	0	6	121
17:15		0	44	0	0	44						0		0	28	6	0	34		6	0	1	0	7	85
17:30		0	45	0	0	45						0		0	33	7	0	40		2	0	0	0	2	87
17:45		4	42	0	0	46						0		0	46	3	0	49		1	0	1	0	2	97
Total	0	7	190	0	0	197	0	0	0	0	0	0	0	0	156	20	0	176	0	12	0	5	0	17	390
Grand Total	0	16	357	0	0	373	0	0	0	0	0	0	0	0	293	42	0	335	0	25	0	16	0	41	749
Appr %		4.3	95.7	0	0			-2	-2	-2	-2			0	87.5	12.5	0			61	0	39	0		
Total %		2.1	47.7	0	0			0	0	0	0			0	39.1	5.6	0			3.3	0	2.1	0		
PM Pk Hr		17:00	17:00	17:00	17:00	17:00		17:00	17:00	17:00	17:00	17:00		17:00	17:00	17:00	17:00	17:00		17:00	17:00	17:00	17:00	17:00	17:00
PM Pk Vol		7	190	0	0	197		0	0	0	0	0		0	156	20	0	176		12	0	5	0	17	390
PM PHF		0.438	0.805	NaN	NaN	0.794		NaN	NaN	NaN	NaN	NaN		NaN	0.796	0.714	NaN	0.830		0.500	NaN	0.417	NaN	0.607	0.806

Barrett Rd @ Westcreek Cir 11-3-22 PM

File Name: Barrett Rd @ Westcreek Cir 11-3-22 PM

Location:

All Vehicles

Site Code:

Study Date: 11/03/2022

Westcreek Cir	12	0	5	0
	Right	Thru	Left	U-Turn
				

Barrett Rd			
7	190	0	0
Right	Thru	Left	U-Turn
			

PM Peak Hour Statistics
PM Peak Hour Begins: 17:00
PM Peak Hour Volume: 390
PM Peak Hour Factor: 0.806

			
U-Turn	Left	Thru	Right
0	20	156	0
Barrett Rd			

	Right	0
	Thru	0
	Left	0
	U-Turn	0

**PEAK SEASON CORRECTION
FACTOR**

2021 PEAK SEASON FACTOR CATEGORY REPORT - REPORT TYPE: COUNTY
 CATEGORY: 1200 LEE COUNTYWIDE

WEEK	DATES	SF	MOCF: 0.96 PSCF
1	01/01/2021 - 01/02/2021	0.96	1.00
2	01/03/2021 - 01/09/2021	1.00	1.04
3	01/10/2021 - 01/16/2021	1.04	1.08
4	01/17/2021 - 01/23/2021	1.02	1.06
5	01/24/2021 - 01/30/2021	1.01	1.05
6	01/31/2021 - 02/06/2021	0.99	1.03
* 7	02/07/2021 - 02/13/2021	0.98	1.02
* 8	02/14/2021 - 02/20/2021	0.97	1.01
* 9	02/21/2021 - 02/27/2021	0.96	1.00
*10	02/28/2021 - 03/06/2021	0.95	0.99
*11	03/07/2021 - 03/13/2021	0.94	0.98
*12	03/14/2021 - 03/20/2021	0.93	0.97
*13	03/21/2021 - 03/27/2021	0.94	0.98
*14	03/28/2021 - 04/03/2021	0.95	0.99
*15	04/04/2021 - 04/10/2021	0.96	1.00
*16	04/11/2021 - 04/17/2021	0.96	1.00
*17	04/18/2021 - 04/24/2021	0.97	1.01
*18	04/25/2021 - 05/01/2021	0.98	1.02
*19	05/02/2021 - 05/08/2021	0.99	1.03
20	05/09/2021 - 05/15/2021	1.00	1.04
21	05/16/2021 - 05/22/2021	1.01	1.05
22	05/23/2021 - 05/29/2021	1.02	1.06
23	05/30/2021 - 06/05/2021	1.02	1.06
24	06/06/2021 - 06/12/2021	1.03	1.07
25	06/13/2021 - 06/19/2021	1.04	1.08
26	06/20/2021 - 06/26/2021	1.06	1.10
27	06/27/2021 - 07/03/2021	1.07	1.11
28	07/04/2021 - 07/10/2021	1.08	1.13
29	07/11/2021 - 07/17/2021	1.10	1.15
30	07/18/2021 - 07/24/2021	1.09	1.14
31	07/25/2021 - 07/31/2021	1.09	1.14
32	08/01/2021 - 08/07/2021	1.09	1.14
33	08/08/2021 - 08/14/2021	1.08	1.13
34	08/15/2021 - 08/21/2021	1.08	1.13
35	08/22/2021 - 08/28/2021	1.08	1.13
36	08/29/2021 - 09/04/2021	1.07	1.11
37	09/05/2021 - 09/11/2021	1.07	1.11
38	09/12/2021 - 09/18/2021	1.06	1.10
39	09/19/2021 - 09/25/2021	1.04	1.08
40	09/26/2021 - 10/02/2021	1.03	1.07
41	10/03/2021 - 10/09/2021	1.01	1.05
42	10/10/2021 - 10/16/2021	0.99	1.03
43	10/17/2021 - 10/23/2021	0.98	1.02
44	10/24/2021 - 10/30/2021	0.98	1.02
45	10/31/2021 - 11/06/2021	0.97	1.01
46	11/07/2021 - 11/13/2021	0.97	1.01
47	11/14/2021 - 11/20/2021	0.96	1.00
48	11/21/2021 - 11/27/2021	0.96	1.00
49	11/28/2021 - 12/04/2021	0.96	1.00
50	12/05/2021 - 12/11/2021	0.96	1.00
51	12/12/2021 - 12/18/2021	0.96	1.00
52	12/19/2021 - 12/25/2021	1.00	1.04
53	12/26/2021 - 12/31/2021	1.04	1.08

* PEAK SEASON

11-MAR-2022 14:24:13

830UPD

1_1200_PKSEASON.TXT

**DEVELOPMENT OF FUTURE YEAR
BACKGROUND TURNING VOLUMES
SPREADSHEET**

Development of Future Year Background Turning Volumes

Intersection
Count Date
Build-Out Year

Barrett Road @ Site Access
November 3, 2022
2027

AM Peak Hour												
	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
RAW Turning Movement Counts	0	177	0	0	152	0	0	0	0	0	0	0
Peak Season Correction Factor	1.01	1.01	1.01	1.01	1.01	1.01	1.01	1.01	1.01	1.01	1.01	1.01
Current Peak Season Volumes	0	179	0	0	154	0	0	0	0	0	0	0
Growth Rate	0.00%	2.00%	0.00%	0.00%	2.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
Years to Build-out	5	5	5	5	5	5	5	5	5	5	5	5
2027 Background Turning Volumes	0	198	0	0	170	0	0	0	0	0	0	0
Project Turning Volumes	14					6	20		45			
2027 Background + Project	14	198	0	0	170	6	20	0	45	0	0	0

PM Peak Hour												
	NBL	NBT	NBR	SBL	SBT	SBR	EBL	EBT	EBR	WBL	WBT	WBR
RAW Turning Movement Counts	0	156	0	0	190	0	0	0	0	0	0	0
Peak Season Correction Factor	1.01	1.01	1.01	1.01	1.01	1.01	1.01	1.01	1.01	1.01	1.01	1.01
Current Peak Season Volumes	0	158	0	0	192	0	0	0	0	0	0	0
Growth Rate	0.00%	2.00%	0.00%	0.00%	2.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
Years to Build-out	5	5	5	5	5	5	5	5	5	5	5	5
2027 Background Turning Volumes	0	174	0	0	212	0	0	0	0	0	0	0
Project Turning Volumes	47					20	12		28			
2027 Background + Project	47	174	0	0	212	20	12	0	28	0	0	0

HCS SUMMARY SHEETS

HCS Two-Way Stop-Control Report


General Information

Analyst	TR Transportation
Agency/Co.	
Date Performed	11/17/2022
Analysis Year	2027
Time Analyzed	AM Pk Hr With Project
Intersection Orientation	North-South
Project Description	F2210.03

Site Information

Intersection	Barrett Rd/Site Access
Jurisdiction	Lee County
East/West Street	Site Access/Westcreek Cir
North/South Street	Barrett Rd
Peak Hour Factor	0.89
Analysis Time Period (hrs)	0.25

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		0	1	0		0	0	0	0	1	1	0	0	0	1	0
Configuration			LR							L	T					TR
Volume (veh/h)		20		45						14	198				170	6
Percent Heavy Vehicles (%)		3		3						3						
Proportion Time Blocked																
Percent Grade (%)	0															
Right Turn Channelized																
Median Type Storage	Undivided															

Critical and Follow-up Headways

Base Critical Headway (sec)		7.1		6.2						4.1						
Critical Headway (sec)		6.43		6.23						4.13						
Base Follow-Up Headway (sec)		3.5		3.3						2.2						
Follow-Up Headway (sec)		3.53		3.33						2.23						

Delay, Queue Length, and Level of Service

Flow Rate, v (veh/h)			73							16						
Capacity, c (veh/h)			730							1369						
v/c Ratio			0.10							0.01						
95% Queue Length, Q ₉₅ (veh)			0.3							0.0						
Control Delay (s/veh)			10.5							7.7						
Level of Service (LOS)			B							A						
Approach Delay (s/veh)	10.5								0.5							
Approach LOS	B								A							

HCS Two-Way Stop-Control Report


General Information

Analyst	TR Transportation
Agency/Co.	
Date Performed	11/17/2022
Analysis Year	2027
Time Analyzed	PM Pk Hr With Project
Intersection Orientation	North-South
Project Description	F2210.03

Site Information

Intersection	Barrett Rd/Site Access
Jurisdiction	Lee County
East/West Street	Site Access/Westcreek Cir
North/South Street	Barrett Rd
Peak Hour Factor	0.81
Analysis Time Period (hrs)	0.25

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound			
Movement	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6
Number of Lanes		0	1	0		0	0	0	0	1	1	0	0	0	1	0
Configuration			LR							L	T					TR
Volume (veh/h)		12		28						47	174				212	20
Percent Heavy Vehicles (%)		3		3						3						
Proportion Time Blocked																
Percent Grade (%)	0															
Right Turn Channelized																
Median Type Storage	Undivided															

Critical and Follow-up Headways

Base Critical Headway (sec)		7.1		6.2						4.1						
Critical Headway (sec)		6.43		6.23						4.13						
Base Follow-Up Headway (sec)		3.5		3.3						2.2						
Follow-Up Headway (sec)		3.53		3.33						2.23						

Delay, Queue Length, and Level of Service

Flow Rate, v (veh/h)			49							58						
Capacity, c (veh/h)			624							1270						
v/c Ratio			0.08							0.05						
95% Queue Length, Q ₉₅ (veh)			0.3							0.1						
Control Delay (s/veh)			11.3							8.0						
Level of Service (LOS)			B							A						
Approach Delay (s/veh)	11.3								1.7							
Approach LOS	B								A							

TRIP GENERATION EQUATIONS

Multifamily Housing (Low-Rise) Not Close to Rail Transit (220)

Vehicle Trip Ends vs: Dwelling Units
On a Weekday

Setting/Location: General Urban/Suburban

Number of Studies: 22


Avg. Num. of Dwelling Units: 229

Directional Distribution: 50% entering, 50% exiting

Vehicle Trip Generation per Dwelling Unit

Average Rate	Range of Rates	Standard Deviation
6.74	2.46 - 12.50	1.79

Data Plot and Equation



Multifamily Housing (Low-Rise) Not Close to Rail Transit (220)

Vehicle Trip Ends vs: Dwelling Units

On a: Weekday,

Peak Hour of Adjacent Street Traffic,

One Hour Between 7 and 9 a.m.

Setting/Location: General Urban/Suburban

Number of Studies: 49


Avg. Num. of Dwelling Units: 249

Directional Distribution: 24% entering, 76% exiting

Vehicle Trip Generation per Dwelling Unit

Average Rate	Range of Rates	Standard Deviation
0.40	0.13 - 0.73	0.12

Data Plot and Equation



Multifamily Housing (Low-Rise) Not Close to Rail Transit (220)

Vehicle Trip Ends vs: Dwelling Units

On a: Weekday,

Peak Hour of Adjacent Street Traffic,

One Hour Between 4 and 6 p.m.

Setting/Location: General Urban/Suburban

Number of Studies: 59


Avg. Num. of Dwelling Units: 241

Directional Distribution: 63% entering, 37% exiting

Vehicle Trip Generation per Dwelling Unit

Average Rate	Range of Rates	Standard Deviation
0.51	0.08 - 1.04	0.15

Data Plot and Equation



Single-Family Detached Housing (210)

Vehicle Trip Ends vs: Dwelling Units
On a Weekday

Setting/Location: General Urban/Suburban

Number of Studies: 174


Avg. Num. of Dwelling Units: 246

Directional Distribution: 50% entering, 50% exiting

Vehicle Trip Generation per Dwelling Unit

Average Rate	Range of Rates	Standard Deviation
9.43	4.45 - 22.61	2.13

Data Plot and Equation



Single-Family Detached Housing (210)

Vehicle Trip Ends vs: Dwelling Units

On a: Weekday,

Peak Hour of Adjacent Street Traffic,

One Hour Between 7 and 9 a.m.

Setting/Location: General Urban/Suburban

Number of Studies: 192


Avg. Num. of Dwelling Units: 226

Directional Distribution: 26% entering, 74% exiting

Vehicle Trip Generation per Dwelling Unit

Average Rate	Range of Rates	Standard Deviation
0.70	0.27 - 2.27	0.24

Data Plot and Equation



Single-Family Detached Housing (210)

Vehicle Trip Ends vs: Dwelling Units

On a: Weekday,

Peak Hour of Adjacent Street Traffic,

One Hour Between 4 and 6 p.m.

Setting/Location: General Urban/Suburban

Number of Studies: 208


Avg. Num. of Dwelling Units: 248

Directional Distribution: 63% entering, 37% exiting

Vehicle Trip Generation per Dwelling Unit

Average Rate	Range of Rates	Standard Deviation
0.94	0.35 - 2.98	0.31

Data Plot and Equation



**2045 E+C NETWORK VOLUMES
FOR US BUSINESS 41**

Pine Island Rd

20198
3

20084
3

33613
BAYSHORE RD
BAYSHORE RD
32422
3

26643
TAMIAMI TR
TAMIAMI TR
27899
3

1
319
MARIANA
MARIANA
321
1

1
937
EVERGREEN
EVERGREEN
503
1

28179
3

27282
3

22878
3
25523
3

Pondella Rd

39183
TAMIAMI TR
TAMIAMI TR
38976
3

BARRETT PARK SURFACE WATER LEVEL OF SERVICE ANALYSIS:

I. Existing Facilities

The subject property consists of 20.14 acres, and exists as a single-family residential development located along the south side of a tributary of Hancock Creek. The general drainage pattern for the area is from west to east to the confluence of Yellow Fever Creek and Hancock Creek.

Existing stormwater facilities serving the residential development include two (2) dry detention areas constructed along the north property line and in the southeast corner of the development for water quality treatment and attenuation. These facilities were permitted through the South Florida Water Management District (SFWMD) (#36-01760-S) in September, 1990.

Surface water from the property discharges through two control structures, one from each detention basin. Discharges through the control structure are conveyed by the aforementioned tributary and an existing wetland to Hancock Creek.


II. Proposed Facilities

Stormwater run-off from the proposed multi-family development will be directed to interconnected detention basins for water quality treatment and attenuation prior to discharging into the Hancock Creek tributary and the existing wetland preserve on east side of the property. The detention basins will be designed to limit discharge rates from the development to a 25-Year, 3-day storm peak discharge rate of 64 cubic-feet-per-square-mile (CSM), which is the required Lee County Level of Service standard for Hancock Creek. The control elevation for the water management facilities will be established to be consistent with the control elevation of the previously permitted system of the existing development.

National Flood Hazard Layer FIRMette



81°55'7"W 26°40'38"N



Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT

SPECIAL FLOOD HAZARD AREAS		Without Base Flood Elevation (BFE) Zone A, V, A99
		With BFE or Depth Zone AE, AO, AH, VE, AR
		Regulatory Floodway
OTHER AREAS OF FLOOD HAZARD		0.2% Annual Chance Flood Hazard, Areas of 1% annual chance flood with average depth less than one foot or with drainage areas of less than one square mile Zone X
		Future Conditions 1% Annual Chance Flood Hazard Zone X
		Area with Reduced Flood Risk due to Levee. See Notes, Zone X
		Area with Flood Risk due to Levee Zone D
OTHER AREAS		NO SCREEN Area of Minimal Flood Hazard Zone X
		Effective LOMRs
		Area of Undetermined Flood Hazard Zone O
GENERAL STRUCTURES		Channel, Culvert, or Storm Sewer
		Levee, Dike, or Floodwall
OTHER FEATURES		Cross Sections with 1% Annual Chance Water Surface Elevation
		Coastal Transect
		Base Flood Elevation Line (BFE)
		Limit of Study
		Jurisdiction Boundary
		Coastal Transect Baseline
MAP PANELS		Digital Data Available
		No Digital Data Available
		Unmapped

The pin displayed on the map is an approximate point selected by the user and does not represent an authoritative property location.

This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap accuracy standards

The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on 1/16/2023 at 10:00 AM and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.

This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.

Basemap: USGS National Map: Orthoimagery: Data refreshed October, 2020



Planning Justification Exhibits - M16 and M19

Location and Property Description

The subject property is located along the west side of Barrett Road approximately ½ mile south of Pine Island Road and approximately ¼ mile north of Pondella Road in North Fort Myers. The property is 20.14 acres in area located in the Sub-Outlying Suburban future land use category but is currently developed with more units than allowed within that future land use category. The current use of the property is for affordable housing. The proposed application will allow for a greater density to accommodate the County's growing needs for affordable units in a strategic location, close to urban infrastructure, transit service and within proximity to one of the County's central employment districts - downtown Fort Myers. The requested future land use map amendment is to change the land use category to Urban Community to allow for a multi-family redevelopment of the subject property.

Surrounding Uses/Compatibility

The property is located in an area of existing development on all sides. To the north of the subject property are a mix of scattered single-family units with two higher density multi-family projects south of Pine Island Road on the east side of Barrett Road within the City of Cape Coral limits. To the west of the subject property is a mix of single and multi-family uses, both within the City of Cape Coral limits and unincorporated Lee County. The Lee County Housing Authority has a single-family affordable housing development approximately 500 feet to the west off of McNeill Road. To the south, along Barrett Road are a mixture of single and multi-family developments on the east and west sides of Barrett Road, north of Pondella Road. To the east of the subject property, across Barrett Road, is a mix of single family and vacant properties.

Existing and Future Conditions Analysis

In accordance with Policy 95.1.3 below is an analysis on public facilities based on the existing development of the subject property as the baseline for the analysis. In addition, attached are analyses of the impacts on sanitary sewer, potable water and surface water by Andrew Fitzgerald, PE, DeLisi Fitzgerald and a Transportation Impact Study by TR Transportation. Letters of service availability for each County service provider are attached to this application as Exhibit M17.

The subject property is currently in the Outlying Suburban future land use category allowing for 42 residential units. However, the subject property is already developed with 50 single family units built and occupied on the property. The proposed amendment would allow for the development of 200 multi-family residential units. Therefore, the following analysis is based on a comparison between the 50 units that are in existence today with the proposed 200 units that are part of the proposed application.

Parks

The level of service for Parks is established in Policy 95.1.3.6 as follows:

NON-REGULATORY STANDARDS

6. Parks and Recreation Facilities: Minimum Level of Service:

(a) Regional Parks - 6 acres of developed regional park land open for public use per 1000 total seasonal county population.

(b) Community Parks - 0.8 acres of developed standard community parks open for public use per 1000 permanent population, unincorporated county only.

The proposed amendment would allow an increase of 150 residential units from what is existing to the proposed density. The addition of 150 units proposed would create the demand for an additional 1.8 acres of regional park, assuming 2 people per unit. In accordance with Lee County's 2022 Concurrency Report, available capacity exists to meet the increase in demand (Page 37).

The inventory indicates a total of 7,066 acres of existing regional parks operated by county, local, state, and federal governments. The capacity required to meet The Lee Plan non-regulatory LOS standard of 6 acres per 1,000 total seasonal county population (as illustrated in Table 3) is equal to 923,000 [seasonal county population] X (6 acres/1,000 population) = 5,538 acres.

The addition of 150 units proposed would create the demand for an additional .24 acres of Community Park, assuming 2 people per unit. In accordance with Lee County's 2022 Concurrency Report, available capacity exists to meet the increase in demand (Page 40). The current demand to meet the County's level of service is 307 acres. The County currently has 762 acres existing.

Lee County Schools

A letter from the Lee County School District has been requested and is forthcoming. The Lee County School Board projects student generation by dwelling unit. According to the School Board, the school children generation rate for single family homes is .297 students per unit and .116 students per unit for multi-family dwellings. This student

generation rate is further broken down by grade level. Assuming a current built density of 50 single family units, the following is what the current level of development generates based on school level.

Student Generation Rates - Existing Development		
	Rate	Projected Students
Elementary	.149	7.5
Middle	.071	3.6
High	.077	3.9
Total	.297	14

Student Generation Rates - Proposed Development		
	Rate	Projected Students
Elementary	.058	11.6
Middle	.028	5.6
High	.03	6.0
Total	.116	23

The proposed amendment would therefore produce an increase in 9 students. In accordance with the attached letter from the Lee County School Board, capacity exists within each school level to accommodate the increase in units.

Environmental Impacts

The proposed amendment will have no impact on environmentally sensitive resources in Lee County as demonstrated in Exhibit M12 of this application. The subject property has already been developed. The proposed redevelopment of the site will not impact the existing wetland on the east side of the property. The proposed development will need to comply with Lee County open space and indigenous preservation requirements.



THE SCHOOL DISTRICT OF LEE COUNTY

Jacqueline Heredia

District Planning Specialist

2855 Colonial Boulevard, Fort Myers, FL 33966 | O: 239.335.1494

December 6, 2022

Daniel DeLisi

RE: Barrett Road in North Fort Myers,

Dear Daniel DeLisi:

This letter is in response to your request for concurrency review dated November 21, 2022 for the subject property in Barrett Road in North Fort Myers, in regard to educational impact. This project is located in West choice Zone.

This development is a request for 200 Multi-Family housing units. With regard to the inter-local agreement for school concurrency the generation rates are created from the type of dwelling unit and further broken down by grade level.

For multi-family homes, the generation rate is .116 and further broken down by grade level into the following, .149 for elementary, .0071 for middle and .077 for high. A total of 23 school-aged children would be generated and utilized for the purpose of determining sufficient capacity to serve the development.

The Concurrency Analysis attached, displays the impact of this development. Capacity is an issue within the Concurrency Service Area (CSA) at the elementary school level, however, capacity is available in the adjacent CSA.

Thank you and if I may be of further assistance, please contact me at 239-335-1494

Sincerely,

Jacqueline Heredia, District Planning Specialist

LEE COUNTY SCHOOL DISTRICT'S SCHOOL CONCURRENCY ANALYSIS

REVIEWING AUTHORITY Lee County School District
NAME/CASE NUMBER Barrett Road in North Fort Myers,
OWNER/AGENT Delisi
ITEM DESCRIPTION

LOCATION 04-44-24-06-00000.0010
ACRES 21.14
CURRENT FLU
CURRENT ZONING

PROPOSED DWELLING UNITS BY TYPE

Single Family	Multi Family	Mobile Home
0	200	0

STUDENT GENERATION

Student Generation Rates			
SF	MF	MH	Projected Students
0.149	0.058		11.60
0.071	0.028		5.60
0.077	0.03		6.00

Source: Lee County School District, September 8, 2018 letter

CSA SCHOOL NAME 2022/23

	CSA Capacity (1)	CSA Projected Enrollment (2)	CSA Available Capacity	Projected Impact of Project	Available Capacity W/Impact	LOS is 100% Perm FISH Capacity	Adjacent CSA Available Capacity w/Impact
West CSA, Elementary	14,234	14,026	208	12	196	99%	
West CSA, Middle	7,293	6,912	381	6	375	95%	
West CSA, High	9,536	8,492	1,044	6	1038	89%	

(1) Permanent Capacity as defined in the Interlocal Agreement and adopted in the five (5) years of the School District's Five Year Plan finding of capacity)

School Concurrency Manual

Prepared by: Jacqueline Heredia, Planning Specialist



Board of County Commissioners

Kevin Ruane
District One

Cecil L. Pendergrass
District Two

Ray Sandelli
District Three

Brian Hamman
District Four

Mike Greenwell
District Five

Roger Desjarlais
County Manager

Richard Wm. Wesch
County Attorney

Donna Marie Collins
County Hearing
Examiner

November 28, 2022

Daniel DeLisi, AICP
DeLisi, Inc.
15598 Bent Creek Rd.
Wellington, FL 33414

Re: Letter of Service Availability – Westcreek Cir.

Mr. DeLisi,

I am in receipt of your letter requesting a Letter of Service Availability for a community located on Westcreek Cir in North Fort Myers. The property is denoted by STRAP 04-44-24-06-00000.0010. The project is proposed to include 200 multi-family residential units.

Lee County Emergency Medical Services is the primary EMS transport agency responsible for coverage at the location you have provided. Because we currently serve this area and have a sufficient response data sample, we evaluated response times in this vicinity to simulate the anticipated demand and response.

The primary ambulance for this location is Medic 7, located 2.2 miles east. There are two other locations within 5 miles of the existing development.

It is our opinion that the service availability for the proposed development of this property is adequate at this time. Should the plans change, a new analysis of this impact would be required.

Sincerely,

A handwritten signature in blue ink, appearing to read "Benjamin Abes", is written over a circular stamp.

Benjamin Abes
Director, Public Safety



Daniel DeLisi, AICP
DeLisi, Inc.

Re: Pine Echo II - STRAP #: 04-44-24-06-00000.0010
14170 Warner Circle
N. Ft. Myers, FL 33903

The property is 21.14 acres in size and is currently in the Sub-Outlying Suburban Land Use Category which allows for up to 2 dwelling units per acre. Currently, the property is already developed with 50 single family units. Your client is proposing a plan amendment to change the property to Urban Community so as to allow for up to 200 multi-family residential units.

If the amendment is approved, the North Fort Myers Fire District will be able to provide fire suppression and emergency medical services to the above proposed development, as well as fire prevention, and public education service. If you require additional information, please do not hesitate to contact my office at (239) 731-1931.

Respectfully,

Rick Jones
Fire Marshal

Carmine Marceno
Sheriff



"Proud to Serve"

State of Florida
County of Lee

November 22, 2022

Daniel DeLisi
DeLisi, Inc.
520 27th St.
West Palm Beach, FL 33407

Mr. DeLisi,

The Lee County Sheriff's Office has reviewed your Comprehensive Plan Amendment request for a 21.14-acre property on Barrett Road approximately ¼ mile north of Pondella Road and ½ mile south of Pine Island Road with the following STRAP #: 04-44-24-06-00000.0010.

The proposed amendment would change the current land designation from the Sub-Outlying Suburban Land Use Category to Urban Community and allow for up to 200 multi-family residential units currently planned for the site. This Agency evaluated your rezoning request solely on its ability to provide law enforcement service to the proposed development. Based on that criterion, we have no objections as it would not affect our ability to provide law enforcement services to the project and surrounding area.

Law enforcement services will be provided from our North District offices in North Fort Myers. As this development builds out, we will factor its impact into our annual manpower review and make adjustments accordingly. At the time of application for a Development Order or building permit, we request that the applicant provide a Crime Prevention Through Environmental Design (CPTED) report done by the applicant and given to the Lee County Sheriff's Office for review and comment. Please contact Community Response Unit Crime Prevention Practitioner Beth Schell at (239) 477-1677 with any questions regarding the CPTED study.

Respectfully,

A handwritten signature in blue ink, appearing to read "Chris Reeves", with a date "9/10/24" written to the right.

Chris Reeves
Major, Patrol Bureau



"The Lee County Sheriff's Office is an Equal Opportunity Employer"
14750 Six Mile Cypress Parkway • Fort Myers, Florida 33912-4406 • (239) 477-1000



Board of County Commissioners

Kevin Ruane
District One

Cecil L Pendergrass
District Two

Ray Sandelli
District Three

Brian Hamman
District Four

Mike Greenwell
District Five

Roger Desjarlais
County Manager

Richard Wm. Wesch
County Attorney

Donna Marie Collins
County Hearing
Examiner

November 22, 2022

Delisi, Inc.
Attn: Mr. Daniel DeLisi, Owner
520 27th St
West Palm Beach, FL 33407

RE: Letter of Availability Lee County Solid Waste Barrett Road Strap # 04-44-24-06-00000.0010

Dear Mr. DeLisi:

The Lee County Solid Waste Department is capable of providing solid waste collection service for the proposed comprehensive plan amendment for up to 200 multi-family residential units located along Barrett Road in North Fort Myers through the franchised hauling contractors. Disposal of the solid waste from this development will be accomplished at the Lee County Resource Recovery Facility and the Lee-Hendry Regional Landfill. Plans have been made, allowing for growth, to maintain long-term disposal capacity at these facilities.

Please review Lee County Land Development Code, Chapter 10, Section 261, with requirements for on-site space for placement and servicing of solid waste containers. Please note that the property owner will be responsible for all future applicable solid waste assessments and fees.

If you have any questions, please call me at (239) 533-8007.

Sincerely,

Justin Lighthall

Justin Lighthall
Manager, Public Utilities
Lee County Solid Waste Department

Kevin Ruane
District One

January 19, 2023

Cecil L. Pendergrass
District Two

Ray Sandelli
District Three

Daniel DeLisi
DeLisi, Inc.

Brian Hamman
District Four

Barrett Road North Fort Myers
Request for Letter of Service Availability

District Five

Roger Desjarlais
County Manager

Mr. DeLisi,

Richard Wesch
County Attorney

LeeTran has reviewed your request for service availability in regard to a proposed Comprehensive Plan Amendment. After reviewing the site and comparing the location with our existing and planned route locations according to the 2020 Transit Development Plan (TDP), the following has been determined:

Donna Marie Collins
County Hearing Examiner

- Subject area is not within one-quarter mile of a fixed-route corridor
- Closest bus stop is not within one-quarter mile of a bus stop
- The 2020 TDP does not identify the need for enhanced or additional transit services in the area

The proposed future development does not currently meet the applicability outlined in Sec. 10-442 and Sec. 10-443. The developer will not be required to connect to and improve transit facilities because planning action does not trigger the relevant Lee County Land Development Code.

If transit services have been modified within one-quarter mile of the subject parcels at the time of a DO or LDO type D submittal, necessary improvements will be determined at that time.

If you have any questions or require further information, please do not hesitate to contact me at (239) 533-0340 or cmarinodiaz@leegov.com.

Sincerely,

Clarissa Marino Diaz

Clarissa Marino Diaz, Transit Service Planner

Lee County Transit

STRATEGIC REGIONAL POLICY PLAN ANALYSES AND STATE POLICY PLAN Exhibit M-18

Strategic Regional Policy Plan

The proposed Plan Amendment implements the Affordable Housing Element of the Strategic Regional Policy Plan. Specifically, the proposed amendment implements the following Goals, Strategies and Actions.

Goal 1: Supply a variety of housing types in various price ranges to ensure that all residents have access to decent and affordable housing.

Strategy: Increase the supply of affordable housing through public and private efforts.

Strategy: Reduce opposition to affordable housing.

Actions:

- 1. Promote the development of "quality" affordable housing projects.*
- 4. Promote the mix of affordable and non-affordable housing to create integrated communities.*

Strategy: Develop livable, integrated communities that offer residents a high quality of life.

Actions:

- 1. Encourage programs that promote infill development in urban areas to maximize the efficient use of existing infrastructure.*
- 5. Promote the mix of affordable and non-affordable housing to create integrated communities.*

State Policy Plan

The proposed Plan amendment also implements the following Goal from the State Policy Plan:

(4) *HOUSING.* –

(a) Goal. – The public and private sectors shall increase the affordability and availability of housing for low-income and moderate-income persons, including citizens in rural areas, while at the same time encouraging self-sufficiency of the individual and assuring environmental and structural quality and cost-effective operations.

3. Increase the supply of safe, affordable, and sanitary housing for low-income and moderate-income persons and elderly persons by alleviating housing shortages, recycling older houses and redeveloping residential neighborhoods, identifying housing needs, providing incentives to the private sector to build affordable housing, encouraging public-private partnerships to maximize the creation of affordable housing, and encouraging research into low-cost housing construction techniques, considering life-cycle operating costs.