

Exhibit A

DESCRIPTION

A PARCEL OF LAND BEING THE LANDS DESCRIBED IN INSTRUMENT NUMBER 2018000171817, OF THE PUBLIC RECORDS OF LEE COUNTY, FLORIDA AND A PORTION OF LANDS DESCRIBED IN INSTRUMENT NUMBER 2015000242014, OF THE PUBLIC RECORDS OF LEE COUNTY, FLORIDA, BEING FURTHER DESCRIBED AS FOLLOWS:

BEGINNING AT THE EASTERLY MOST CORNER OF LANDS DESCRIBED IN INSTRUMENT NUMBER 2018000171817, OF THE PUBLIC RECORDS OF LEE COUNTY, FLORIDA; THENCE ALONG THE SOUTH LINE OF SAID LANDS AND THE EXTENSION THEREOF SOUTH 58°08'20" WEST, A DISTANCE OF 279.49 FEET; THENCE NORTH 31°51'40" WEST, A DISTANCE OF 287.65 FEET TO AN INTERSECTION WITH THE SOUTHEAST RIGHT-OF-WAY OF ISLAND PARK RD; THENCE ALONG SAID SOUTHEAST RIGHT-OF-WAY NORTH 58°22'42" EAST, A DISTANCE OF 255.64 FEET TO A POINT ON A NON TANGENTIAL CURVE TO THE RIGHT; THENCE CONTINUE ALONG SAID RIGHT-OF-WAY EASTERLY 39.27 FEET ALONG THE ARC OF SAID CURVE, HAVING A RADIUS OF 25.00 FEET, A CENTRAL ANGLE OF 90°00'22", (CHORD BEARING SOUTH 76°37'07" EAST, A DISTANCE OF 35.36 FEET) TO AN INTERSECTION WITH THE SOUTHWEST RIGHT-OF-WAY OF U.S. 41 (TAMIAMI TRAIL); THENCE ALONG SAID SOUTHWEST RIGHT-OF-WAY SOUTH 31°37'18" EAST, A DISTANCE OF 236.62 FEET TO A POINT ON A NON TANGENTIAL CURVE TO THE LEFT; THENCE CONTINUE ALONG SAID RIGHT-OF-WAY SOUTHEASTERLY 24.85 FEET ALONG THE ARC OF SAID CURVE, HAVING A RADIUS OF 5,797.58 FEET, A CENTRAL ANGLE OF 00°14'44", (CHORD BEARING SOUTH 31°44'18" EAST, A DISTANCE OF 24.85 FEET) TO THE POINT OF BEGINNING.

CONTAINING 1.84 ACRES, MORE OR LESS.

NOTES:

1. BEARINGS SHOWN HEREON ARE BASED ON THE STATE PLANE COORDINATE SYSTEM ESTABLISHED BY THE NATIONAL GEODETIC SURVEY FOR FLORIDA WEST ZONE, 1983 DATUM WITH 1990 ADJUSTMENT OBTAINED UTILIZING RTK GPS OBSERVATIONS ON THE FDOT NETWORK AND REFER TO THE SOUTHEAST RIGHT-OF-WAY LINE OF ISLAND PARK RD, LEE COUNTY, FLORIDA AS BEING N 58°22'42" E.
2. DIMENSIONS SHOWN HEREON ARE IN U.S. SURVEY FEET AND DECIMALS THEREOF.
3. THIS SKETCH AND DESCRIPTION IS NOT VALID WITHOUT THE ORIGINAL SIGNATURE AND SEAL OR THE DIGITAL SIGNATURE AND DIGITAL SEAL OF A LICENSED FLORIDA SURVEYOR AND MAPPER. NO ADDITIONS OR DELETIONS TO THIS SKETCH AND DESCRIPTION ARE PERMITTED WITHOUT THE EXPRESSED WRITTEN CONSENT OF THE SIGNING PARTY.

REVIEWED
ADD2022-00103
Rick Burris, Principal
Planner
Lee County DCD/Planning
7/28/2022

*NOT VALID WITHOUT
 SHEET 2 OF 2*

DRAWN BY:	AH
CHECKED BY:	TJD
JOB CODE:	CC71141IP
SCALE:	N/A
DATE:	2 JUNE 2022
FILE:	21-126-SL
SHEET:	1 of 2

* NOT A SURVEY *

SKETCH AND DESCRIPTION

A PARCEL OF LAND


LYING IN
 SECTION 1, TOWNSHIP 46 SOUTH, RANGE 24 EAST
 LEE COUNTY, FLORIDA




GradyMinor

Q. Grady Minor and Associates, P.A.
 3800 Via Del Rey
 Bonita Springs, Florida 34134

Civil Engineers • Land Surveyors • Planners • Landscape Architects
 Cert. of Auth. EB 0005151 Cert. of Auth. LB 0005151 Business LC 26000266
 Bonita Springs: 239.947.1144 www.GradyMinor.com Fort Myers: 239.690.4380



ISLAND PARK RD




CURVE TABLE					
CURVE #	RADIUS	LENGTH	DELTA	CHORD BEARING	CHORD LENGTH
C1	25.00'	39.27'	90°00'22"	S 76°37'07" E	35.36'
C2	5797.58'	24.85'	0°14'44"	S 31°44'18" E	24.85'


REVIEWED
ADD2022-00103
Rick Burris, Principal
Planner
Lee County DCD/Planning
7/28/2022

LEGEND

POB POINT OF BEGINNING
 IN INSTRUMENT NUMBER



THIS PLAN MAY HAVE BEEN ENLARGED OR
 REDUCED FROM INTENDED DISPLAY SCALE FOR
 REPRODUCTION REASONS



*** NOT A SURVEY ***

***NOT VALID WITHOUT
 SHEET 1 OF 2***



GradyMinor

Q. Grady Minor and Associates, P.A.
 3800 Via Del Rey
 Bonita Springs, Florida 34134

Civil Engineers • Land Surveyors • Planners • Landscape Architects
 Cert. of Auth. EB 0005151 Cert. of Auth. LB 0005151 Business LC 26000266
 Bonita Springs: 239.947.1144 www.GradyMinor.com Fort Myers: 239.690.4380

SKETCH AND DESCRIPTION

A PARCEL OF LAND

 LYING IN
 SECTION 1, TOWNSHIP 46 SOUTH, RANGE 24 EAST
 LEE COUNTY, FLORIDA

DRAWN BY: AH
 CHECKED BY: TJD
 JOB CODE: CC71141IP
 SCALE: 1" = 60'
 DATE: 2 JUNE 2022
 FILE: 21-126-SL
 SHEET: 2 of 2