ADD2024-00090 Lee County ePlan





LEGEND

- (A) LEASE LINE
- (B) ACCESSIBLE PARKING SPACE (TYP. OF 4)
- (C) ACCESSIBLE PARKING AND PENALTY SIGN (TYP. OF 4)(SEE DETAIL SHEET C7.1)
- (D) 9" CONCRETE BOLLARD SIGN BASE (SEE DETAIL SHEET C7.1)
- (E) THICKENED CONCRETE PAD (SEE DETAIL SHEET C7.1)
- (F) CONCRETE SIDEWALK
- (G) LOADING ZONE (DELIVERIES AND GARBAGE TRUCK PICKUPS WILL BE MADE WHEN RESTAURANT IS NOT OPEN FOR BUSINESS
- (H) DUMPSTER AREA (REFER TO ARCHITECTURAL PLANS)
- (I) FIRE HYDRANT
- (J) FIRE DEPARTMENT CONNECTION
- (K) 6"X30"SWALE PER FDOT INDEX 515-001
- (L) ACCESSIBLE RAMPS (SEE DETAIL SHEET C7.1)
- (M) EXISTING SIDEWALK
- (N) EX. LIGHT POLE (TYP.)
- (O) DISCONNECT PAD (REFER TO ARCH AND ELEC PLANS FOR DETAILS)
- (P) OVERALL PROPERTY LINE
- (Q) 18" SOLID WHITE LINE SPACED 18" AT 45°
- (R) CANTILEVER MONUMENT SIGN
- (S) RELOCATED LIGHT POLE
- (T) TRANSFORMER WITH BOLLARD PROTECTION

SIGN LEGEND

SYMBOL LEGEND

- ACCESSIBLE PARKING SPACE
- (9) PARKING STALL COUNT
- CONCRETE SIDEWALK
- (E) THICKENED CONCRETE
- LEASE LINE
- T TRANSFORMER PAD

NOTE:

1. SEE SHEET C8.1 FOR CURBING AND PAVING INFORMATION.
2. SEE SHEET C7.1 FOR ACCESSIBILITY AND RAMP DETAILS.
3. ALL TRAFFIC CONTROL DEVICES SHALL BE INSTALLED IN COMPLIANCE WITH THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES AND THE FLORIDA DEPARTMENT OF TRANSPORTATION STANDARDS.
4. THIS PLAN IS CONSISTENT WITH APPLICABLE LEE PLAN STANDARDS AND PROVISIONS.

SITE DATA

PROJECT DESCRIPTION	CONSTRUCTION OF CAPITAL GRILLE RESTAURANT
PARCEL ID	24-45-24-06-00005.1000
LOCATION	SECTION 24, TOWNSHIP 45S, RANGE 24E
ADDRESS	9250 BELL TOWER SHOP AVE FORT MYERS, FL 33907
ZONING DISTRICT	CI (CENTRE BELL TOWER SHOPS)
LAND USE	COMMERCIAL
FLOOD ZONE	ZONE X, AS SHOWN ON FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAP COMMUNITY PANEL NUMBER 12071C0529G, EFFECTIVE DATE DECEMBER 7, 2018. NO BASE FLOOD ELEVATION.

	REQUIRED	PROVIDED
MAX. BUILDING HEIGHT	35'	31'-0" (1 STORY)
LEASE AREA	10,156 S.F. (0.43 AC.)	
FLOOR AREA RATIO	10,156/10,156 = 0.54	

SITE COVERAGE	PROVIDED	
SITE AREA	10,156 S.F. (0.43 AC)	100.0%
BUILDING AREA	10,156 S.F. (0.23 AC)	53.69%
IMPERVIOUS AREA	3,892 S.F. (0.09 AC)	20.93%
PERVIOUS AREA	4,726 S.F. (0.11 AC)	25.38%

BUILDING SETBACKS	REQUIRED	PROVIDED
REAR	25'	113.23' (FROM ROW)
SIDE	15'	60'
		67'

PARKING SUMMARY	REQUIRED	PROVIDED
STANDARD	45	40
ACCESSIBLE		4
TOTAL		44

PARKING CALCULATION:
AS SPACES/1,000 SF (10,156 SF = 46 SPACES

* PARKING AND OPEN SPACE ANALYSIS REPORT PREPARED BY GREENSITE ENGINEERING INC. ON SEPTEMBER 10, 2012 STATES THAT THERE IS AN EXCESS OF 341 PARKING SPACES IN THE OVERALL CENTER (301 STANDARD SPACES AND 29 ACCESSIBLE PARKING SPACES)

* THE 87 SPACES ARE LOCATED IN THE PARKING ROWS ADJACENT TO THE BUILDING AND SHOWN ON THIS PLAN. THE PARKING IN THE MALL IS SHARED AND THERE IS ADDITIONAL PARKING TO THE NORTH EAST AND WEST OF THE BUILDING.

THE PRESENCE OF GROUNDWATER SHOULD BE ANTICIPATED ON THIS PROJECT. CONTRACTOR'S BID SHALL INCLUDE CONSIDERATION FOR ADDRESSING THIS ISSUE.

Always call 811 two full business days before you dig to have underground utilities located and marked.

Sunshine811.com

Kimley»Horn
445 24TH STREET, SUITE 200
VERO BEACH, FL 32960
PH: (772) 794-4100

5/15/2023

THE CAPITAL GRILLE

Issue Date:	07/29/2022
REVISION INFORMATION	
1 DO COMMENTS	2/8/23
2 DO COMMENTS	4/17/23
Restaurant #:	8073

THE CAPITAL GRILLE
BELL TOWER SHOPPING MALL
PROTOTYPE CUSTOM
LEE COUNTY FLORIDA

DRAWING
SITE PLAN

C3.1

Drawing name: K:\WEB_LOC\LG4796 – Darden\126_CG FL Myers\CAD\PlanSheets\C08-C3.1 SITE PLAN.dwg C08-C3.1 SITE PLAN May 15, 2023 2:37pm by Liz Meeks
This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



PROJECT NORTH

SITE PLAN
1" = 10'-0"

GENERAL SITE PLAN NOTES
1. REFER TO CIVIL DRAWINGS FOR MORE INFORMATION.
2. REFER TO A2.0 FOR EGRESS PLAN AND CODE ANALYSIS.

KEYED ARCHITECTURAL SITE PLAN NOTES
SP# DENOTES ARCHITECTURAL SITE PLAN NOTE
1. PROPERTY LINE.
2. LINE OF CANOPY ABOVE.
3. PARKING SPACE.
4. ACCESSIBLE PARKING SPACE.
5. ACCESSIBLE VAN PARKING SPACE.
6. ACCESSIBLE PATH OF TRAVEL.
7. BLACK DOUBLE SHREDDED HARDWOOD MULCH, AMERICAN RIVER BLACK, AROUND PERIMETER OF BUILDING. REFER TO LANDSCAPE DRAWINGS.
8. BOLLARD.
9. GAS METER. REFER TO MEP DRAWINGS.
10. WATER METER & BFP. REFER TO MEP DRAWINGS.
11. TRANSFORMER WITH CONCRETE PAD. COORDINATE WITH ENERGY COMPANY TRANSFORMER REQUIREMENTS.
12. DISCONNECT WITH CONCRETE PAD. REFER TO MEP DRAWINGS.
13. FIRE DEPARTMENT CONNECTION. COORDINATE FINAL LOCATION WITH FIRE MARSHAL AND GENERAL CONTRACTOR WITHIN 100' OF THE FDC.
14. MONUMENT SIGNAGE. REFER TO CIVIL & MEP DRAWINGS.

JKRP
ARCHITECTS
100 EAST PENN SQUARE
SUITE 1080
PHILADELPHIA, PA 19107
215.928.9331
JKRPARCHITECTS.COM

DARDEN

THE CAPITAL GRILLE

SUBMISSION INFORMATION	
ISSUED FOR PERMITS	2022.08.25
B - ADDENDUM B	2022.11.28
C - ADDENDUM C	2023.03.06
1 - BULLETIN 1	2023.05.08

RESTAURANT #: 8073

THE CAPITAL GRILLE
FORT MYERS, FL
04-22-004
5070 BELL TOWER SHOP AVE
FORT MYERS, FL 33907

DRAWING:
ARCHITECTURAL SITE PLAN

SP1.1

ADD2024-00090 Lee County ePlan