

DATE: December 20, 2024

AFFIDAVIT OF PUBLICATION

Tracy Toussaint
Lcbc-Dept Of Comm Development-D
1500 MONROE ST
Fort Myers FL 33901

STATE OF WISCONSIN, COUNTY OF BROWN

Before the undersigned authority personally appeared, who on oath says that he or she is the Legal Advertising Representative of the News-Press, a daily newspaper published at Fort Myers in Lee County, Florida; that the attached copy of advertisement, being a Legal Ad in the matter of Public Notices, was published on the publicly accessible website of Lee County, Florida, or in a newspaper by print in the issues of, on:

12/05/2024

Affiant further says that the website or newspaper complies with all legal requirements for publication in chapter 50, Florida Statutes.

Subscribed and sworn to before me, by the legal clerk, who is personally known to me, on 12/05/2024

D. Fokwa
Legal Clerk
Nicole Jacobs
Notary, State of WI, County of Brown

8-21-26

My commission expires

Publication Cost:	\$265.64	
Tax Amount:	\$0.00	
Payment Cost:	\$265.64	
Order No:	10800677	# of Copies:
Customer No:	1124450	1
PO #:	#900697	

THIS IS NOT AN INVOICE!

Please do not use this form for payment remittance.

NICOLE JACOBS
Notary Public
State of Wisconsin

NOTICE OF PUBLIC HEARING

The Hearing Examiner of Lee County will hold public hearings on Thursday, December 19, 2024, in the Hearing Examiner Meeting Room, 1500 Monroe St., Ft. Myers, FL. An interested individual may appear in person, through counsel, or an authorized agent and provide testimony, legal argument or other evidence at the hearing.

If you do not appear before the Hearing Examiner or otherwise become a participant for that case in which you wish to testify, the law does not permit you to address the Board of County Commissioners. Any document that a participant of record intends to submit to the BoCC during the Board Zoning Hearing must be submitted as an exhibit as part of the record in the hearing before the Hearing Examiner. If the document is not submitted and is not relevant new evidence that was not known or could not have been reasonably discovered by the participant at the time of the hearing before the Hearing Examiner, then the document may not be submitted to the Board.

After the Hearing Examiner has made a written recommendation, the case will be scheduled for a public hearing before the Board of County Commissioners who will review the recommendation and make a final decision.

Copies of staff report(s) are available two weeks prior to the hearing. The file can be reviewed at the Zoning Section, 1500 Monroe St., Fort Myers, FL. Call 239 533 8585 for additional information.

Lee County will not discriminate against individuals with disabilities. To request an accommodation, contact Raphaela Morales-Peroba, 239-533-8782, Florida Relay Service 711, or ADArequests@leegov.com, at least 5 business days in advance.

The following case(s) will be heard (Lee County Land Development Code is abbreviated below as LDC): DCI2024 00027. Cypress Manor RPD. 9:00 am. Request to rezone 28.03± acres from Agricultural (AG 2) to Residential Planned Development (RPD) to allow a 168 multi family or townhouse unit development.

Located At 18831 State Road 82., Lehigh Acres Planning Community, Lee County, FL.

DCI2023-00015/Pine Island Road CPD. Remand Hearing. 1:00pm. Request to rezone 9.7± acres from Agricultural (AG-2) and Commercial (C-1 and C-1A) to Commercial Planned Development (CPD) to allow a maximum of 121,800 square feet of commercial uses including a convenience food and beverage store with sixteen fueling positions. Located At SW corner of Pine Island Road and Cleveland Avenue, North Fort Myers Planning Community, Lee County, FL.
December 5, 2024 10800677

Summary of Hearing Examiner Recommendation

PINE ISLAND ROAD CPD

The request seeks to develop the southwest corner of the US 41 and Pine Island Road intersection with a range of intense commercial uses and a storage facility.





The Master Concept Plan and conditions of approval ensure protection of nearby residents. This is accomplished through site design that orients intense uses toward arterial roadways, enhances right of way buffers along Herron Road, and imposes limitations on hours of operation.

Detailed recommendation follows

DCI2023-00015

Future Land Use

-  Subject Property
-  Intensive Development
-  Central Urban
-  Sub-Outlying Suburban
-  City Limits







DCI2023-00015

Aerial

 Subject Property

 City Limits







DCI2023-00015

Mixed Use Overlay

 Subject Property

 Mixed Use Overlay

 City Limits



OFFICE OF THE HEARING EXAMINER, LEE COUNTY, FLORIDA

HEARING EXAMINER RECOMMENDATION

REZONING: DCI2023-00015

Regarding: PINE ISLAND ROAD CPD

Location: Southwest corner of US 41 and Pine Island Road
North Fort Myers Planning Community
(District 4)

Hearing Date: August 14, 2024

Record Closed: September 23, 2024

I. Request

Rezone 9.7 acres from Commercial (C-1 and C-1A) and Agricultural (AG-2) to Commercial Planned Development (CPD), to allow 121,800 square feet of commercial uses with maximum heights of 45 feet. The request seeks alternative development scenarios as follows:

Option A:

- Up to 100,000 sq. ft. mini or public warehouse,
- 4,000 sq. ft. carwash,
- 2,500 sq. ft. auto repair services,
- 5,000 sq. ft. fast food restaurant,
- 7,800 sq. ft. commercial retail uses.

Option B:

- Up to 100,000 sq. ft. mini or public warehouse,
- 4,000 sq. ft. carwash,
- 2,500 sq. ft. auto repair services,
- 7,500 sq. ft. convenience food and beverage store with 16 fuel pumps.

The property legal description is set forth in Exhibit A.

II. Hearing Examiner Recommendation

Approve, subject to conditions and deviations set forth in Exhibit B.

III. Discussion

The Hearing Examiner serves in an advisory capacity to the Board of County Commissioners (Board) on applications to rezone property to the planned development zoning district.¹ In furtherance of this duty, the Hearing Examiner accepted testimony and evidence on an application to rezone property in North Fort Myers to the CPD district. Staff recommended approval with conditions.

In preparing a recommendation to the Board, the Hearing Examiner must apply the Lee County Comprehensive Plan (Lee Plan), Land Development Code (LDC), and other County regulations to facts adduced at hearing. The record must contain substantial competent evidence to support the recommendation.

Discussion supporting the Hearing Examiner's recommendation of approval with conditions follows below.²

Request

Applicant requests to rezone 9.7 acres from C-1 and C-1A and AG-2 to CPD. The proposed CPD includes two potential development scenarios:

Option A:

- Up to 100,000 sq. ft. mini or public warehouse,
- 4,000 sq. ft. carwash,
- 2,500 sq. ft. auto repair services,
- 5,000 sq. ft. fast food restaurant,
- 7,800 sq. ft. commercial retail uses.

Option B:

- Up to 100,000 sq. ft. mini or public warehouse,
- 4,000 sq. ft. carwash,
- 2,500 sq. ft. auto repair services,
- 7,500 sq. ft. convenience food and beverage store with 16 fuel pumps.

The request includes two deviations from LDC standards. Maximum building heights will be 45 feet.

The Master Concept Plan (MCP) clusters buildings internal to the site and provides enhanced buffering along Herron Road. Both development options feature driveways on US 41, Pine Island Road, and Herron Road. The Herron Road

¹ LDC §34-145(d)(4) a.

² Hearing Examiner codified conditions and deviations from prior approvals.

Access drive is located 125 feet from Pine Island Road to minimize impacts to the neighborhood.

Character of Area

The property is in the North Fort Myers Planning District and subject to a community plan. The site is located at the intersection of US 41/North Cleveland Avenue and Pine Island Road.

US 41/North Cleveland Avenue is a "Commercial Corridor" under the North Fort Myers Community Plan.³ The corridor is developed with large retail centers and midsize commercial businesses. Multifamily development is underway north of Merchant's Crossing.⁴ There is an auto repair business on the corner of Pineapple Lane and US 41/North Cleveland Avenue. Herron Road is developed with single family homes and a church.

History

The 9.7 acre site is comprised of 11 separate parcels. Three parcels abutting US 41/North Cleveland Avenue are zoned C-1. These parcels lie within the Mixed Use Overlay. One parcel along Pine Island Road is zoned C-1A and the remaining seven parcels are zoned for agriculture.⁵

The commercially zoned parcels were formerly developed with a car wash. Three of the seven agriculturally zoned parcels hosted three single family dwellings. All improvements have been removed and the property is now vacant.

Lee Plan

Planned developments must be consistent with the Lee Plan.⁶

The Lee Plan designates the property within the Intensive Development and Sub-Outlying Suburban future land use categories.

The Intensive Development Future Land Use category is the most intense under the Lee Plan. Intensive Development areas are located along major arterial roads with access to a wide array of services.⁷ These areas are considered suited for intense development.⁸

³ LDC §§33-1537, 33-1566(a).

⁴ Commercial uses in the immediate area include regional shopping centers, convenience stores with fuel pumps, and pharmacies.

⁵ Staff Report page 2.

⁶ LDC §34-411(a).

⁷ The property is in an area of the County characterized by intense development patterns.

⁸ See Lee Plan Table 1(b).

Sub-Outlying Suburban lands feature low density residential land uses. These areas generally do not have the infrastructure needed to support intense development. This Sub-Outlying Suburban category are typically found in areas where intense development is not anticipated or where there is a desire to retain a low-density community character.⁹ The Sub-Outlying Suburban classification of a portion of the site appears to be a vestige from development patterns predating the urbanization of the US 41 and Pine Island Road corridors. Properties along Herron Road are sandwiched between the City of Cape Coral and the intense development along Pine Island Road and US 41.

The juxtaposition of the two diametrically different land use categories requires careful attention to site design and buffering.

The property's current zoning designation is C-1, C-1A, and AG-2. The purpose of the C-1 and C-1A districts is to regulate continuance of commercial and select residential land uses.¹⁰ The purpose of agricultural districts is to provide for agricultural operations with ancillary residential use.¹¹ The Lee Plan discourages new agricultural uses in future urban areas with public services and infrastructure available to serve development.¹² The requested planned development district authorizes development of land uses better suited to property in an urban area.¹³

Development in North Fort Myers is subject to a Community Plan adopted as part of the Lee Plan as well as specific use and site design criteria in the LDC.¹⁴ The Community Plan emphasizes protecting North Fort Myers' character, economic vitality, and quality of life.¹⁵ The proposed CPD will serve residents in surrounding areas and the traveling public.

The Economic Element of the Lee Plan encourages expansion of the County's economic base.¹⁶ The proposed mix of land uses contributes to a positive business climate creating additional employment opportunities.¹⁷

A portion of the site is located within a Mixed Use Overlay.¹⁸ The Mixed Use Overlay is desirable for mixed use development due to its proximity to public transit, shopping, and employment centers.

⁹ Lee Plan Policy 1.1.11.

¹⁰ LDC §34-841.

¹¹ LDC §34-651.

¹² Lee Plan Goal 9, Objective 9.2.

¹³ Lee Plan Goal 6, Objective 9.2, Policies 6.1.4, 6.1.7, 9.2.1.

¹⁴ Lee Plan Goal 30 adopted by Lee County Ordinance No. 09-11 on February 25, 2009. Community specific LDC regulations adopted by Lee County Ordinance No. 12-01 on January 10, 2012.

¹⁵ See Lee Plan Goal 30.

¹⁶ Lee Plan Goal 158 Objective 158.2.

¹⁷ Lee Plan Goal 158, Objective 158.3.

¹⁸ Lee Plan Map 1-C: Mixed Use Overlay.

Lee Tran routes 140 and 595 travel along US 41 and Pine Island Road with transit stops proximate to the project.¹⁹ There are sidewalks and shared use paths on Pine Island Road and US 41.²⁰

Compatibility

Compatibility between land uses exists when land uses do not unduly impact one another. Planned development zoning is a useful tool when integrating new development with surrounding land uses.²¹ The planned development zoning district allows flexibility in site design to address potential incompatibilities with residential development on Herron Road.

The property's location at the intersection of two heavily traveled arterial roadways makes the site suitable for intense land uses.²² The Mixed Use Overlay designation on a portion of the site encourages compact urban development forms.²³ The property qualifies as "infill" contributing to contiguous development patterns.²⁴

Zoning the property to a commercial district will permit development of uses designed to serve nearby residential land uses and traveling public.²⁵ The proposed CPD is consistent with development patterns along the US41/North Cleveland Avenue commercial corridor.²⁶ The site will serve as a transition between the US41 corridor and less intense uses to the west. The Herron Road right of way separates residential land uses from proposed commercial uses and more intense development and traffic along US 41.²⁷

The North Fort Myers Community Plan encourages streetscape and landscape improvements along North Cleveland Avenue.²⁸ While property in a Mixed Use Overlay generally benefits from scaled back open space and landscape requirements,²⁹ the LDC imposes enhanced landscape requirements for some uses regardless of location.³⁰ These enhanced standards will apply to convenience stores with fuel pumps as well as fast food restaurants.

¹⁹ Lee Plan Policy 39.1.3.

²⁰ Lee Plan Policies 39.6.4, 43.1.1, Lee Plan Map 3-D: Lee County Walkways & Bikeways.

²¹ LDC §34-612(2).

²² LDC §34-413

²³ Lee Plan Map 1-C, Goal 11, Objectives 2.1, 2.2, 11.1, Policies 2.2.1, 2.2.2, 6.1.4; LDC §34-413.

²⁴ Lee Plan Goal 6, Objective 2.2, Policy 6.1.7.

²⁵ Lee Plan Goal 30.

²⁶ Lee Plan Policies 1.1.2, 6.1.7, 11.2.5.

²⁷ The sub-outlying Suburban future land use designation on Herron Road is a vestige of prior development patterns. The site borders an enclave of single family development bounded by the City of Cape Coral and the Intensive Development category.

²⁸ Lee Plan Policy 30.3.1.

²⁹ LDC §10-425.

³⁰ LDC §§10-424, 10-425; see also LDC §10-425.

Lighting on the property is regulated by LDC outdoor lighting standards.³¹ Developer must comply with illumination restrictions, shielding and orientation of lighting fixtures. In addition, as a commercial structure, the warehouse facility will be subject to LDC design standards for commercial buildings.³²

The MCP and recommended conditions will shield residents of Herron Road from project impacts. Conditions include placement of the carwash and dumpsters internal to the project, relocation of Herron Road driveway access to within 125 feet of Pine Island Road, enhanced buffering along Herron Road, and limitations on carwash hours of operation. Recommended conditions and site design reflected in the MCP ensures limited impact to area residents.

There was no testimony on the record as to whether the warehouse facility will be monitored by security cameras, or if there are plans to provide onsite security personnel.³³ Notwithstanding proximity to residences, no restrictions were proposed on hours of operation. The Hearing Examiner recommends hours of operation for warehouse uses from 6 am to 10 pm daily. If applicant intends to operate 24 hours a day, the Hearing Examiner recommends a condition requiring onsite security personnel between the hours of 10 pm and 6 am.

LDC

Rezoning requests must comply with County regulations or seek deviations.

Once rezoned, permitted uses must be consistent with the design standards for the North Fort Myers Commercial Corridor.³⁴ Commercial projects in North Fort Myers are required to provide publicly accessible open space.³⁵ Future buildings must comply with North Fort Myers Urban Design Guidelines for commercial land uses.³⁶ The Community Plan also encourages streetscape and landscape improvements along US 41/North Cleveland Avenue.³⁷ Site development must comply with these regulations or seek variances.

A "deviation" is a departure from a land development regulation.³⁸ Applicants must demonstrate deviations enhance the planned development and will not cause a

³¹ LDC §34-625.

³² The purpose of the commercial building design standards is to maintain and complement the street scape by requiring buildings to be designed with architectural features and patterns that provide visual interest consistent with the community's identity and local character. LDC §10-620 *et seq.*

³³ Requested uses did not include a caretaker's residence.

³⁴ North Fort Myers is subject to a community plan set forth in Lee Plan Goal 30 as well as supplemental development regulations in LDC §33-1531 *et seq.*, including standards governing architecture, signs, landscaping, and site design. LDC §§33-1571, 33-1596. Land uses must be consistent with the commercial corridor use regulations.

³⁵ LDC §33-1572.

³⁶ LDC §33-1575 *et seq.*

³⁷ Lee Plan Policy 30.3.1.

³⁸ LDC §34-2.

detriment to the public.³⁹ The CPD includes two deviations; one relating to parking and the other to internal road buffering.⁴⁰ Applicant submitted a parking study of seven warehouse facilities in Lee County and Fort Myers demonstrating parking demand is lower than LDC standards. County staff accepted the study in support of the requested parking deviation.

Staff recommended approval of both deviations, and the Hearing Examiner agrees with this recommendation.⁴¹

The North Fort Myers Community Planning & Design Review Panel reviewed the request prior to hearing and expressed no objection to the proposed zoning.⁴² The property will be subject to further community review at the development order stage.⁴³

Development will be subject to road, fire, and emergency medical services impact fees.⁴⁴

Environmental/Natural Resources

Rezoning requests must not adversely affect environmentally critical/sensitive areas or natural resources.

A portion of the site has been cleared and does not contain wetlands.⁴⁵ The species survey revealed no evidence of protected species.⁴⁶ The MCP depicts 2.56 acres of open space, 1.0 acre of which will be comprised of an upland indigenous preserve. Project open space includes wet and dry detention areas and landscape buffers.

Developer must install enhanced plantings along Herron Road.⁴⁷ The 30 foot wide Type F buffer will include ten trees every 100 linear feet with a double staggered hedgerow. The hedgerow must be 48 inches high at installation and maintained at 60 inches to ensure a lush landscape buffer along the Herron Road right of way. The buffer will ameliorate potential impacts to residents on Herron Road.

³⁹ LDC §34-373(a)(9).

⁴⁰ LDC §§34-2013(b)(3), 34-2020(b).

⁴¹ The Hearing Examiner may recommend approval, approval with modifications or denial of deviations based on findings that a deviation (1) enhances the planned development and, (2) preserves/promotes public health, safety, and welfare. LDC §34-377(a)(4).

⁴² Advertised meeting held on February 6, 2024, before the North Fort Myers Community Planning Panel. LDC §33-1532(a). See Staff Report Attachment F.

⁴³ LDC §33-1532.

⁴⁴ Lee Plan Policies 38.1.1, 38.1.5; LDC Chapter 2.

⁴⁵ Staff Report Attachment F: Testimony of Barrett Stejskal, BearPaws Environmental Consulting.

⁴⁶ *Id.*

⁴⁷ See Condition 6.

Buffers and landscaping within open space areas must follow Xeriscape principles and consist of native landscape to conserve water.⁴⁸

The Hearing Examiner finds the proposed CPD will not harm environmentally critical/sensitive areas or natural resources.⁴⁹ The plan of development includes removal of exotic vegetation.

Transportation

Access must be sufficient to support development intensity and expected impacts must be addressed by existing county regulations.

The property is bounded on four sides by roadways: Pine Island Road, US 41, Herron Road, and Pineapple Lane. US 41/North Cleveland Ave and Pine Island Road are state maintained arterial roadways.⁵⁰ As such, Florida Department of Transportation has permit authority over driveway access and location. Herron Road and Pineapple Lane are County maintained local roads.

Three access drives will serve the site: A right in only access from Pine Island Road, a right-in/right-out access to US 41, and a full access from Herron Road.⁵¹ The Herron Road access drive is located 125 feet from Pine Island Road to limit project related traffic in the adjacent residential neighborhood.⁵²

The Traffic Impact Statement (TIS) calculated project impacts on the county road network.⁵³ The TIS reflects the convenience store/gas station use attracts a significant amount of traffic from vehicles already traveling adjoining roadways.⁵⁴ This "pass by" traffic reduces impacts to the road network.

The TIS concludes most roadways will not be significantly impacted by the project at buildout. The exception is Pine Island Road west of US 41, which will operate below adopted levels of service at buildout.⁵⁵ However, the condition exists in 2027 with *and without* the proposed development.⁵⁶ The County does not require special mitigation to address existing transportation deficiencies. As a result, project traffic

⁴⁸ Lee Plan Objective 126.2, Policy 126.2.1, LDC §10-421.

⁴⁹ Lee Plan 125.1.2.

⁵⁰ Lee County Administrative Code 11-1.

⁵¹ MCP. The MCP depicts no access to Pineapple Lane.

⁵² The developer must upgrade Herron Road to the project access to meet County road standards.

⁵³ TIS attached to Applicant's 48 hour memorandum prepared by TR Transportation Consultants, Inc. revised February 16, 2024.

⁵⁴ *Id.* Consistent with FDOT studies in Florida, pass-by rates for gas station use is 77%. Proposed retail uses will also experience pass-by trip reductions. Significant impact is defined as the project trips impacting a roadway link greater than 140% of the adopted Level of Service "C" service volumes.

⁵⁵ TIS attached to Applicant's 48 hour memorandum prepared by TR Transportation Consultants, Inc. revised February 16, 2024. Significant impact is defined as the project trips impacting a roadway link greater than 140% of the adopted Level of Service "C" service volumes.

⁵⁶ The County will not require special mitigation to address level of service issues when there are existing transportation deficiencies not caused by a project.

generated by the proposed rezoning does not warrant roadway capacity improvements.⁵⁷

Further analysis of transportation impacts, including site-related turn lane improvements, will occur during development order permitting.⁵⁸

Transit

Lee Tran Route 140 runs along US 41.⁵⁹ Project design must comply with LDC requirements to facilitate transit access.⁶⁰

Greenways Master Plan

The property is on the Pine-Island Hendry Trail, which runs along Pine Island Road.⁶¹

Public Services

Public services include facilities, capital improvements, and infrastructure necessary to support development at urban levels of intensity.⁶² The Lee Plan requires evaluation of available public services during the rezoning process.⁶³

Public services and infrastructure are in place to serve the property.⁶⁴ The site is surrounded by paved roadways. There is public water and sanitary sewer

⁵⁷ TIS attached to Applicant's 48 hour memorandum prepared by TR Transportation Consultants, Inc. revised February 16, 2024.

⁵⁸ Site related road improvements include capital improvements and right-of-way dedications for direct access to the development. Direct access improvements may include: (1) site access and roads; (2) Median cuts; (3) Turn and deceleration/acceleration lanes; (4) Traffic control measures; (5) Access/frontage roads providing frontage for newly created lots; (6) Roads or intersection improvements whose primary purpose is to provide access to the development; (7) Improvements to bicycle and pedestrian facilities along parcel frontage of public streets; (8) Improvements to transit facilities within one-quarter mile of parcel frontage measured along principal perimeter streets.

LDC §§10-1, 10-7(b), 10-286, 10-288, 10-441.

⁵⁹ Lee Plan Map 3-C: 2045 Financially Feasible Transit Network. An improved transit stop is located on US 41 along the site frontage. See Lee Plan Policies 43.1.1, 158.3.1.

⁶⁰ LDC §10-442(b) requires projects proposing 30,000 square feet or greater commercial floor area must provide a paved walkway to the nearest bus stop and install a bicycle storage rack, signage, and a landing pad within the road right of way or dedicated easement.

⁶¹ Lee Plan Map 4-E Greenways Master Plan.

⁶² Public services include public water and sewer, paved streets, parks, and recreation facilities, urban levels of police, fire and emergency services, surface water management, schools, employment, industrial and commercial centers, institutional, public, or administrative facilities, and community facilities.

⁶³ Lee Plan Policy 2.2.1.

⁶⁴ Lee Plan Glossary definition of Public Services, Goal 4, Policies 1.1.2, 2.2.1, Standards 4.1.1, 4.1.2.

infrastructure to serve the property.⁶⁵ Fire, EMS, and law enforcement services are available from nearby stations.⁶⁶

The property has access to two major arterials: Pine Island Road and US 41. Pine Island Road offers connections to I-75, Del Prado Boulevard, and Business US 41. Lee Tran services the US 41 and Pine Island Road corridors.⁶⁷ Applicant may be required to provide convenient access to the nearest bus stop.⁶⁸ A shared use path for cyclists and pedestrians is located on Pine Island Road and US 41.⁶⁹

Conditions

The County must administer the zoning process so proposed land uses minimize adverse impacts on adjacent property and protect County resources.⁷⁰ Conditions must be plausibly related to the project's anticipated impacts, and pertinent to mitigating impacts to the public.⁷¹

The CPD is subject to conditions addressing impacts reasonably anticipated from development.⁷² Notable conditions include restoration of indigenous upland vegetation, restrictions on hours of operation, and signs to discourage truck traffic on Herron Road.⁷³

The Hearing Examiner has the authority to recommend additional conditions in the context of a proposed planned development.⁷⁴ In furtherance of this authority, the Hearing Examiner recommends conditions to ensure compatibility with nearby residents on Herron Road. These conditions include limiting the hours of operation of the carwash and warehouse facility.

Hearing Examiner revised conditions/deviations for clarity, compliance with state law and to remove LDC references applicable to development by Condition 1.

⁶⁵ Lee County Utilities and FGUA have public water and sanitary sewer infrastructure in proximity to the property. Lee Plan Standards 4.1.1, 4.1.2; Staff Report.

⁶⁶ North Fort Myers Fire Control & Rescue Service District has stations on Barrett Road and Trail Dairy Circle. Lee County EMS Medic 7 and Lee County Sheriff North District Office are located on Pondella Road.

⁶⁷ Lee Plan Objective 11.2, Policy 30.3.3; Lee Tran Route 140.

⁶⁸ Developer must ensure access to public transportation if available. Lee Plan Objective 11.2, Policy 30.3.3, Map 3-C, LDC §33-1574 identifies design techniques that facilitate public access to transit.

⁶⁹ Lee Plan Map 3-D: Lee County Walkways & Bikeways.

⁷⁰ Lee Plan Policies 5.1.5, 135.9.6; LDC §§34-145(d)(4) a.2.(b), 34-377(a)(3), 34-411, and 34-932(c).

⁷¹ LDC §34-932(b).

⁷² LDC §§34-83(b)(4) a.3, 34-377(a)(2)c; Lee Plan Objective 77.3, Policies 5.1.5, 6.1.4, 77.3.1, 135.9.6.

⁷³ The Hearing Examiner further restricted the carwash hours of operation in deference to resident's concerns regarding noise.

⁷⁴ LDC 34-145(d)(1)c. and (d)(6)a.

Public

Two members of the public attended the hearing who were residents of Herron Road. They expressed concerns regarding the intrusion of commercial traffic into their residential neighborhood and attendant noise. Hearing Examiner's prehearing site visit brought the public's concerns into sharp focus.⁷⁵

In response to resident concerns, Applicant revised the MCP relocating the Herron Road driveway closer to Pine Island Road. The revised MCP repositions intense uses proximate to US 41 and Pine Island Road. Applicant volunteered conditions limiting the hours of operation of the car wash and requiring the placement of signs discouraging commercial trucks from using Herron Road as a means of ingress or egress from the site. The Hearing Examiner further limited carwash hours of operation. In addition, the Hearing Examiner imposed limits warehouse hours of operation.⁷⁶

Conclusion

The Hearing Examiner recommends approval of the requested Pine Island Road CPD, subject to conditions in Exhibit B.

The Hearing Examiner finds the Pine Island Road CPD meets LDC criteria and, as conditioned, is compatible with surrounding development.⁷⁷

IV. Findings and Conclusions

Based on the testimony and exhibits presented in the record, the Hearing Examiner finds:

- A. The requested CPD is consistent with the Lee Plan. Lee Plan Goals 2, 4, 6, 11, 30, 60, 61, 77, 95, 125, 158, 159; Objectives 2.1, 4.1, 6.1, 11.1, 11.2, 30.2, 77.2, 77.3, 126.2, and Policies 1.1.2, 1.1.11, 1.6.5, 2.2.1, 6.1.1, 6.1.3, 6.1.4, 6.1.5, 6.1.6, 6.1.7, 30.2.5, 39.1.3, 135.9.6, Lee Plan Maps 1-A, 1-B, 1-C, 2-A, 3-C, 3-D, 4-A, 4-B, 4-E, Table 1(b).
- B. As conditioned, the Pine Island Road CPD:
 - 1. Is consistent with the LDC or qualifies for deviations. LDC Chapters 2, 10, 33, and 34.
 - 2. Is compatible with existing or planned uses in the surrounding area. Lee Plan Goals 2, 6, 30, Objectives 2.1, 2.2, 11.2, and Policies 1.1.2,

⁷⁵ The Hearing Examiner makes a site visit on each case. Lee County Administrative Code 2-6 §3.1.

⁷⁶ Mini-warehouse and public warehouse uses.

⁷⁷ Lee Plan Policy 6.1.4.

- 1.1.11, 5.1.5, 6.1.4, 11.2.1, 30.3.1, 39.1.3, 135.9.5, 135.9.6; LDC §§34-411, 34-413.
3. Provides sufficient road access to support proposed development intensity. Lee Plan Objective 39.1, Policies 6.1.4, 6.1.5, 30.3.3, 38.1.1, 39.1.1, 39.2.2.
 4. Expected impacts on transportation facilities will be addressed by County regulations and conditions of approval. Lee Plan Objective 39.1, Policies 6.1.5, 38.1.1, 38.1.5, 39.1.3, 39.2.1; LDC §§2-261 *et seq.*, 34-411(d) and (e).
 5. Will not adversely affect environmentally sensitive areas or natural resources. Lee Plan Goals 60, 77, 125, Objectives 77.3, 126.2, Policies 6.1.6, 60.1.1, 61.3.6, 77.3.1, 77.3.3, 125.1.2, 125.1.3, 126.2.1, and Standard 4.1.4; and
 6. Public services and infrastructure will be available to serve the development. Goals 2, 4, 6, 11, 95, Objectives 2.1, 2.2, 4.1, 6.1, 158.3, Policies 2.2.1, 4.1.1, 4.1.2, 6.1.4, 11.2.1, 39.2.1, 65.2.1, 158.3.1, 160.1.1, Standards 4.1.1, 4.1.2.
- C. The proposed uses are appropriate at the location. Lee Plan Goals 2, 6, 11, 30; Objectives 2.1, 2.2, 11.2, Policies 2.1.1, 2.1.2, 6.1.7, 6.1.8, 11.2.5, 39.1.3, 135.9.6, Lee Plan Table 1(b)
- D. The County regulations and recommended conditions provide sufficient safeguards to protect the public interest and relate to impacts expected from the proposed development. Lee Plan Goals 30, 125, Objectives 77.2, 77.3, 126.2, Policies 5.1.5, 6.1.4, 30.3.1, 53.1.5, 56.1.4, 77.3.1, 126.2.1, 135.9.6; LDC §§34-377(a)(3), 34-411 and 34-932(c).
- E. Deviations recommended for approval enhance the planned development and preserve public health, safety, and welfare. LDC §§34-373(a)(9), 34-377(a)(4).
- F. Will be served by urban services and infrastructure. Lee Plan Goal 2, Objectives 2.1, 2.2, Policy 2.2.1, 4.1.1, 4.1.2.

Date of Recommendation: September 25, 2024.


Donna Marie Collins
Chief Hearing Examiner

Lee County Hearing Examiner
1500 Monroe Street, Suite 218
Post Office Box 398
Fort Myers, FL 33902-0398

Exhibits to Hearing Examiner's Recommendation

Exhibit A Legal Description and Vicinity Map
Exhibit B Recommended Conditions and Deviations
Exhibit C Exhibits Presented at Hearing
Exhibit D Hearing Participants
Exhibit E Information

Exhibit A

LEGAL DESCRIPTION AND VICINITY MAP

Exhibit A



Professional Engineers, Planners & Land Surveyors

DESCRIPTION
OF
A TRACT OR PARCEL OF LAND LYING IN
SECTION 3, TOWNSHIP 44 SOUTH, RANGE 24 EAST
LEE COUNTY, FLORIDA

A TRACT OR PARCEL OF LAND SITUATED IN THE STATE OF FLORIDA, COUNTY OF LEE, LYING IN SECTION 3, TOWNSHIP 44 SOUTH, RANGE 24 EAST, BEING A PORTION OF LOT 8, LITTLE GROVES UNIT "B", AS RECORDED IN PLAT BOOK 9, PAGE 11, ALL OF LOT 4, MARIANA PARK ADDITION NO. 1, AS RECORDED IN PLAT BOOK 10, PAGE 36, ALL OF LOTS 8, 9, 10, 11, 12, AND PORTIONS OF LOTS 13 AND 14, MARIANA PARK 3RD ADDITION, AS RECORDED IN PLAT BOOK 12, PAGE 61, ALL OF THE PUBLIC RECORDS OF LEE COUNTY, FLORIDA, AND BEING FURTHER BOUNDED AND DESCRIBED AS FOLLOWS:

BEGINNING AT THE SOUTHWEST CORNER OF PARCEL 102, AS DESCRIBED IN OFFICIAL RECORDS BOOK 2614, PAGES 3177 THROUGH 3197, OF SAID PUBLIC RECORDS; THENCE S 89°54'05" E ALONG THE SOUTH LINE OF SAID PARCEL AND THE SOUTH RIGHT-OF-WAY LINE OF NE PINE ISLAND ROAD (STATE ROAD 78 – WIDTH VARIES) FOR 472.90 FEET; THENCE S 44°54'04" E ALONG SAID SOUTH LINE AND SAID RIGHT-OF-WAY LINE FOR 33.81 FEET TO AN INTERSECTION WITH THE WEST RIGHT-OF-WAY LINE OF N. CLEVELAND AVENUE (U.S. 41 / STATE ROAD 45 – 200 FEET WIDE) AND THE BEGINNING OF A NON-TANGENT CURVE TO THE LEFT HAVING A RADIUS OF 2,964.79 FEET, TO WHICH POINT A RADIAL LINE BEARS S 81°47'47" W; THENCE SOUTHERLY ALONG SAID WEST RIGHT-OF-WAY LINE AND SAID CURVE THROUGH A CENTRAL ANGLE OF 10°40'37" FOR 552.48 FEET TO AN INTERSECTION WITH THE NORTH LINE OF SAID MARIANA PARK ADDITION NO. 1; THENCE N 89°56'16" W ALONG SAID NORTH LINE FOR 181.44 FEET TO AN INTERSECTION WITH THE WEST LINE OF LOT 3 OF SAID MARIANA PARK ADDITION NO. 1; THENCE S 00°17'45" E ALONG SAID WEST LINE FOR 343.97 FEET TO AN INTERSECTION WITH THE NORTH RIGHT-OF-WAY LINE OF PINEAPPLE LANE (50 FEET WIDE); THENCE N 89°56'16" W ALONG SAID NORTH RIGHT-OF-WAY LINE FOR 339.37 FEET TO THE BEGINNING OF A CURVE TO THE RIGHT HAVING A RADIUS OF 25.00 FEET; THENCE NORTHWESTERLY ALONG SAID NORTH RIGHT-OF-WAY LINE AND SAID CURVE THROUGH A CENTRAL ANGLE OF 84°37'20" FOR 36.92 FEET TO AN INTERSECTION WITH THE EAST RIGHT-OF-WAY LINE OF HERRON ROAD (50 FEET WIDE); THENCE N 05°18'56" W ALONG SAID EAST RIGHT-OF-WAY LINE FOR 885.63 FEET TO THE POINT OF BEGINNING.

SUBJECT PARCEL CONTAINS: 9.71 ACRES, MORE OR LESS.

BEARINGS AND DISTANCES ARE BASED ON THE "STATE PLANE COORDINATE SYSTEM" FLORIDA ZONE WEST NAD 83/2011 (CORS), WHEREIN THE SOUTH RIGHT-OF-WAY LINE OF N.E. PINE ISLAND ROAD (STATE ROAD 78) BEARS S 89°54'05" E. THE SCALE FACTOR IS 0.999942347.


ALL DISTANCES ARE IN FEET AND DECIMALS THEREOF.

SUBJECT TO EASEMENTS, RESTRICTIONS, RESERVATIONS AND RIGHTS-OF-WAY OF RECORD.

DESCRIPTION PREPARED: 05-30-2023.

Digitally signed by Allen M Vose III
Date: 2023.06.09 11:38:23 -04'00'

ALLEN M. VOSE III, P.S.M.
PROFESSIONAL SURVEYOR AND MAPPER
FLORIDA CERTIFICATION NO. 7191
DATE SIGNED 06-09-2023
S:\Vobs\86xx\8638\Surveying\Descriptions\8638P BNDY LGL.doc
S:\Vobs\86xx\8638\Surveying\Descriptions\8638P BNDY SKT.dwg



REVIEWED
DCI2023-00015
Rick Burris, Principal
Planner
Lee County DCD/Planning
5/7/2024

SHEET 1 OF 2
• SERVING THE STATE OF FLORIDA •


10511 Six Mile Cypress Parkway • Suite 101 • Fort Myers, Florida 33966
Phone 239-939-5490 • www.bankseng.com • Fax 239-939-2523
Engineering License No. EB 6469 • Surveying License No. LB 6690

SKETCH OF DESCRIPTION

REVIEWED
DCI2023-00015
Rick Burris, Principal
Planner
Lee County DCD/Planning
5/7/2024

OF
A TRACT OR PARCEL OF LAND LYING IN
SECTION 3, TOWNSHIP 44 SOUTH, RANGE 24 EAST
LEE COUNTY, FLORIDA

STATE ROAD 78
NE PINE ISLAND ROAD
(PUBLIC RIGHT-OF-WAY - WIDTH VARIES)



NOTES:

BEARINGS AND DISTANCES ARE BASED ON THE "STATE PLANE COORDINATE SYSTEM" FLORIDA ZONE WEST HAD 83/2011 (CORS), WHEREIN THE SOUTH RIGHT-OF-WAY LINE OF N.E. PINE ISLAND ROAD (STATE ROAD 78) BEARS S 89°54'05" E. THE SCALE FACTOR IS 0.999942347.

ALL DISTANCES ARE IN FEET AND DECIMALS THEREOF.

SUBJECT TO EASEMENTS, RESTRICTIONS, RESERVATIONS AND RIGHTS-OF-WAY OF RECORD.

CURVE TABLE

CURVE	RADIUS	DELTA	ARC	CHORD	CHORD BEARING
C1	2964.79'	10°40'37"	552.48'	551.68'	S 13°32'31" E
C2	25.00'	84°37'20"	36.92'	33.66'	N 47°37'36" W

LEGEND:

C INDICATES CENTERLINE
 P.B. INDICATES PLAT BOOK
 O.B. INDICATES DEED BOOK
 R/W INDICATES RIGHT-OF-WAY
 8 INDICATES LOT NUMBER 8
 I.N. INDICATES INSTRUMENT NUMBER
 P.I. INDICATES POINT OF INTERSECTION
 L.I. INDICATES LINE DATA: SEE LINE TABLE
 C.I. INDICATES CURVE DATA: SEE CURVE TABLE
 P.S.M. INDICATES PROFESSIONAL SURVEYOR AND MAPPER
 C.O.S. INDICATES CONTINUOUSLY OPERATING REFERENCE STATION

LINE TABLE

LINE	BEARING	DISTANCE
L1	S 44°54'04" E	33.81'


S:\JOBS\86XX\8630\SURVEYING\DESCRIPTIONS\8630P BNDY LGL.DWG
 S:\JOBS\86XX\8630\SURVEYING\DESCRIPTIONS\8630P BNDY SKT.DWG

SEE SHEET 1 OF 2 FOR COMPLETE METES AND BOUNDS LEGAL DESCRIPTION
THIS SKETCH OF DESCRIPTION IS NOT A BOUNDARY SURVEY

Digitally signed by Allen M Vose III
Date: 2023.06.09 11:38:41 -04'00'

ALLEN M. VOSE III, P.S.M.
PROFESSIONAL SURVEYOR AND MAPPER
FLORIDA CERTIFICATION NO. 7191

- DATE SIGNED: 06-09-2023
 - THIS SKETCH OF DESCRIPTION IS NOT VALID WITHOUT THE ORIGINAL SIGNATURE AND SEAL OF A FLORIDA LICENSED SURVEYOR AND MAPPER.



BANKS ENGINEERING
Professional Engineers, Planners, & Land Surveyors
Serving the State of Florida

10511 SIX MILE CYPRESS PARKWAY
FORT MYERS, FLORIDA 33908
PHONE: (239) 939-5400
FAX: (239) 939-2523
ENGINEERING LICENSE # EB 8469
SURVEY LICENSE # LB 6690
WWW.BANKSENG.COM

SKETCH OF DESCRIPTION
14993 N CLEVELAND AVE
NORTH FORT MYERS, LEE COUNTY, FLORIDA

DATE	PROJECT	DRAWING	DRAWN	CHECKED	SCALE	SHEET	OF	FILE NO. (S-T-R)
05-30-2023	8630P	BNDY SKT	AMV	AMV	1" = 150'	2	2	03-44-24

DCI2023-00015

Zoning








Exhibit B

RECOMMENDED CONDITIONS AND DEVIATIONS

As revised by the Hearing Examiner

CONDITIONS

1. Master Concept Plan (MCP). Development must be consistent with four-page MCP dated September 23, 2024, entitled "Pine Island Road CPD", prepared by Phoenix Associates of Florida, Inc. except as modified by the conditions below. (Exhibit B1)

Lee Plan and Land Development Code (LDC). Development must comply with the Lee Plan and LDC, except where deviations are approved herein. Amendments to the MCP, conditions, or deviations require further review and approval.

Approved Development Parameters. The property is approved to develop up to 121,800 square feet of commercial land uses as follows:

Option A:

- Up to 100,000 sq. ft. mini-warehouse/public warehouse,
- 4,000 sq. ft. carwash,
- 2,500 sq. ft. auto repair services,
- 5,000 sq. ft. fast food restaurant
- 7,800 sq. ft. commercial retail uses

Option B:

- Up to 100,000 sq. ft. mini-warehouse/public warehouse,
- 4,000 sq. ft. carwash,
- 2,500 sq. ft. auto repair services,
- 7,500 convenience food and beverage store with 16 fuel pumps.

2. Schedule of Permitted Uses and Property Development Regulations.

- a. Permitted Uses

Accessory uses, buildings, and structures
ATM (Automated Teller Machine)
Auto parts store (with installation services)
Automobile Repair and Service: Groups I, II
Automobile Service Station
Bank & Financial Establishments: Groups I, II
Car Wash
Clothing Store, General
Convenience Food and Beverage Store (limited to a maximum of 16 fuel pumps)

Drive-through facility for any permitted use
 Essential Service Facilities: Group I
 Excavation: Water Retention
 Food Stores: Group I
 Hardware Store
 Hobby, Toy, and Game Shops
 Laundry or Dry Cleaning: Group I
 Lawn and Garden Supply Store
 Paint, Glass, and Wallpaper
 Parking Lot (accessory)
 Personal Services: Groups I-IV (Excludes bail bonding, escort services, fortune tellers, palm readers or card readers, massage parlors, and tattoo parlors)
 Pet Shop
 Rental and Leasing Establishments: Groups I, II
 Repair Shops: Groups I, II
 Restaurant, Fast Food
 Self-Service Fuel Pumps, in conjunction with a Convenience Food and Beverage Store
 Signs
 Specialty Retail Shops: Groups I, II, & III
 Temporary Uses
 Used Merchandise Stores: Groups I (except pawn shops), II, III
 Variety Store
 Warehouse: Public
 Mini Warehouse

b. Site Development Regulations

Development Criteria	Commercial
Setbacks	
Perimeter	25 feet
Side Yard	15 feet
Rear	20 feet
Preserve	30 feet
Maximum Building Height	45 feet
Overall Minimum Lot Area and Dimensions	
Area	25,000 sq. feet
Width	150 feet
Depth	150 feet
Maximum Building Coverage	40 percent

3. Open Space
Development order plans must depict a total of 2.56 acres open space.
4. Indigenous Open Space
Development order plans must depict 1.00 acres of indigenous preserve area to include 135 percent credit (1.35 acres of indigenous open space with credits). Plans must substantially comply with the MCP.
5. Indigenous Restoration and Buffers
The first development order application must include an indigenous restoration plan. Restoration plants used to meet right-of-way buffer requirements must comply with LDC §10-416(d). Supplemental buffer landscaping must comply with LDC §10-420. An above ground temporary irrigation system must be specified on the development order plans.
6. Enhanced Buffer on Herron Road. Development order plans must depict an LDC "Type F" buffer along the eastern edge of Herron Road, north and south of the onsite native preserve.
7. Warehouse Hours of Operation. Warehouse operations are limited to the hours of 7:00 am to 10:00 pm daily. If the property owner intends to operate warehouse uses 24 hours a day, there must be security personnel onsite between the hours of 10:00 pm and 7:00 am.
8. Buffers Around Warehouse Uses
 - a. Development order submittals for mini or public warehouse must reflect an enhanced 15-foot-wide buffer along the internal accessway abutting the mini or public warehouse with landscape vegetation meeting LDC §34-1353(e)(1) specifications. Tree and shrub species must be consistent along the internal accessway to create a unified landscape plan.
 - b. Development order submittals for mini or public warehouses must include landscape plans depicting a five-foot-wide buffer along the southeast property line abutting Community Commercial zoned property.
9. Site Access
Access to US 41 and SR 78 depicted on the MCP is conceptual and subject to modification based upon final approval from Florida Department of Transportation.
10. Commercial Trucks Prohibited on Herron Road. Development order plans must depict the posting location of signs prohibiting trucks from using Herron Road for ingress to or egress from the site.
11. Dumpsters. Dumpsters are prohibited within 100 feet of the Herron Road right-of-way.

12. Carwash Hours of Operation. Carwash may be operated between the hours of 8:00 a.m. and 7:00 p.m., seven days a week.
13. State and Federal Permits
County development permits do not create rights to obtain permits from state or federal agencies and do not create liability on the part of the County if applicant fails to obtain requisite approvals or fulfill obligations imposed by state/federal agencies or if applicant undertakes actions resulting in a violation of state or federal law. Applicant must obtain applicable state/federal permits prior to commencing development.

DEVIATIONS

1. Required Parking Spaces. Deviation 1 seeks relief from LDC §34-2020(b), which requires non-residential uses, particularly mini or public warehouse, to provide a minimum of one space per 25 storage units to allow for a minimum of one space per 50 storage units, with a minimum of five spaces.

Hearing Examiner Recommendation: Approved.

2. Buffers. Deviation 2 seeks relief from LDC 34-1353(e), which requires convenience food and beverage stores, automobile service stations, fast food restaurants, and car washes to provide 15 foot wide right-of-way buffer if abutting an internal accessway to a commercial development to allow for a 10 foot wide buffer where those uses adjacent to internal rights-of-way in the locations depicted on the MCP.

Hearing Examiner Recommendation: Approved.

Exhibits to Conditions:

B1 Master Concept Plan entitled "Pine Island Road CPD", prepared by Phoenix Associates of Florida, Inc. dated September 23, 2024.

Exhibit C


EXHIBITS PRESENTED AT HEARING

STAFF EXHIBITS

1. *DCD Staff Report with attachments for DCI:* Prepared by Elizabeth Workman, Principal Planner, date received July 30, 2024 (multiple pages – 8.5"x11" & 11"x14") [black & white, color]
2. *Affidavit of Publication:* Advertisement for zoning case DCI2023-00015 Pine Island Road CPD, date of hearing August 14, 2024 (1 page – 8.5"x11")
3. *PowerPoint Presentation:* Prepared by Lee County Staff for DCI2023-00015 Pine Island Road CPD, dated August 14, 2024 (multiple pages – 8.5"x11")[color]

APPLICANT EXHIBITS

- a. *48-Hour Notice:* Email from Alexis Crespo with RVI Planning and Landscaping Architecture, to Maria Perez, C. Lasano, Josephine Medina, Brett Nevaril, Barrett Stejskal, Ted Treesh, Elizabeth Workman, and Diogo Rodrigues, with copies to Rebecca Sweigert, Tracy Toussaint, Jamie Pringing, Elizabeth Workman, Audra Ennis, Nicholas DeFilippo, Ohdet Kleinmann, Abby Henderson, Lee Werst, Warren Baucom, Mikki Rozdolski, Anthony Rodriguez, Dirk Danley, Jr., Phil Gillogly, Marcus Evans, and Jennifer Rodriguez, dated Sunday, August 11, 2024, 11:53 AM (multiple pages – 8.5"x11" & 11"x17")
1. *PowerPoint Presentation:* Prepared by RVI Planning and Landscaping Architecture for DCI2023-00015 Pine Island Road CPD, dated August 14, 2024 (multiple pages – 8.5"x11")[color]
2. *Written Submissions:* Email from Alexis Crespo with RVI Planning and Landscaping and Architecture, to Maria Perez, C. Lascano, Brett Nevaril, Diogo Rodrigues, Ted Treesh, Barrett Stejskal, and Elizabeth Workman, with copies to Rebecca Sweigert, Tracy Toussaint, Jamie Pringing, Elizabeth Workman, Audra Ennis, Nicholas DeFilippo, Ohdet Kleinmann, Abby Henderson, Lee Werst, Marcus Baucom, and Jennifer Rodriguez, dated Monday, September 23, 2024, 5:09 PM (multiple pages – 8.5"x11" and 11"x17"){post hearing submittal}




PROJECT SUMMARY	
SITE LOCATION:	SWC OF N CLEVELAND AVE & NE PINE ISLAND RD LEE COUNTY, FL 33903
PROJECT AREA:	9.71 ACRE ±
STRAP NUMBER:	034240100000008B 034240100000008A 0342401000000080 0342406000000040 0342411000000080 0342411000000090 0342411000000100 0342411000000110 0342411000000120 0342411000000130 0342411000000140
ZONING/REZONING	C-1, C-1A & AG-2 TO CPD

OPEN SPACE SUMMARY	
LAND USE	AREA
ON-SITE INDIGENOUS PRESERVE PROVIDED	1.00 ACRES
OTHER OPEN SPACE PROVIDED	1.56 ACRES
TOTAL OPEN SPACE REQUIRED	2.56 ACRES
TOTAL OPEN SPACE PROVIDED	2.56 ACRES
PUBLICLY ACCESSIBLE OPEN SPACE REQUIRED	0.35 ACRES
PUBLICLY ACCESSIBLE OPEN SPACE PROVIDED	0.35 ACRES

LEGEND	
	CPD BOUNDARY
	BUILDING
	PEDESTRIAN CROSSWALK
	VEHICULAR FLOW/INGRESS/EGRESS
	LOADING ZONE
	PAVEMENT EDGE DRIVE
	SIDEWALK
	DEVIATION TRIANGLE

INDIGENOUS PRESERVE SUMMARY	
LAND USE	AREA
ON-SITE INDIGENOUS PRESERVE REQUIRED	1.29 ACRES
ON SITE INDIGENOUS PRESERVE PROVIDED	1.35 ACRES (1.0 ACRES PROVIDED ON SITE X 135% (CREDIT))



Project Name and Address	Revision	Date
PINE ISLAND ROAD CPD SWC OF N CLEVELAND AVE & NE PINE ISLAND RD LEE COUNTY, FLORIDA 33903	01/20/24	01/20/24
	01/20/24	01/20/24
	01/20/24	01/20/24
	01/20/24	01/20/24
	01/20/24	01/20/24

INFINITY
INFINITY ENGINEERING GROUP, LLC
1208 East Kennedy Boulevard
Suite 230
Tampa, Florida 33602
[p]: 813.434.4770
[f]: 813.445.4211
www.legroup.net
FL Cert. of Auth. No. 27889

PHOENIX
ASSOCIATES OF FLORIDA
1310 LAMAR ROAD, SUITE 200, NAPLES, FLORIDA 34109
PH (239) 441-1111 FAX (239) 441-1112
PH (239) 441-1113 FAX (239) 441-1114
PH (239) 441-1115 FAX (239) 441-1116
PH (239) 441-1117 FAX (239) 441-1118
PH (239) 441-1119 FAX (239) 441-1120
PH (239) 441-1121 FAX (239) 441-1122
PH (239) 441-1123 FAX (239) 441-1124
PH (239) 441-1125 FAX (239) 441-1126
PH (239) 441-1127 FAX (239) 441-1128
PH (239) 441-1129 FAX (239) 441-1130
PH (239) 441-1131 FAX (239) 441-1132
PH (239) 441-1133 FAX (239) 441-1134
PH (239) 441-1135 FAX (239) 441-1136
PH (239) 441-1137 FAX (239) 441-1138
PH (239) 441-1139 FAX (239) 441-1140
PH (239) 441-1141 FAX (239) 441-1142
PH (239) 441-1143 FAX (239) 441-1144
PH (239) 441-1145 FAX (239) 441-1146
PH (239) 441-1147 FAX (239) 441-1148
PH (239) 441-1149 FAX (239) 441-1150
PH (239) 441-1151 FAX (239) 441-1152
PH (239) 441-1153 FAX (239) 441-1154
PH (239) 441-1155 FAX (239) 441-1156
PH (239) 441-1157 FAX (239) 441-1158
PH (239) 441-1159 FAX (239) 441-1160
PH (239) 441-1161 FAX (239) 441-1162
PH (239) 441-1163 FAX (239) 441-1164
PH (239) 441-1165 FAX (239) 441-1166
PH (239) 441-1167 FAX (239) 441-1168
PH (239) 441-1169 FAX (239) 441-1170
PH (239) 441-1171 FAX (239) 441-1172
PH (239) 441-1173 FAX (239) 441-1174
PH (239) 441-1175 FAX (239) 441-1176
PH (239) 441-1177 FAX (239) 441-1178
PH (239) 441-1179 FAX (239) 441-1180
PH (239) 441-1181 FAX (239) 441-1182
PH (239) 441-1183 FAX (239) 441-1184
PH (239) 441-1185 FAX (239) 441-1186
PH (239) 441-1187 FAX (239) 441-1188
PH (239) 441-1189 FAX (239) 441-1190
PH (239) 441-1191 FAX (239) 441-1192
PH (239) 441-1193 FAX (239) 441-1194
PH (239) 441-1195 FAX (239) 441-1196
PH (239) 441-1197 FAX (239) 441-1198
PH (239) 441-1199 FAX (239) 441-1200

NISIT SAPPARKHAO, P.E. FL REG. NO. 64085
DATE

Project Name and Address
PINE ISLAND ROAD CPD
SWC OF N CLEVELAND AVE & NE PINE ISLAND RD
LEE COUNTY, FLORIDA 33903


Sheet Title
MASTER CONCEPT PLAN

Project No.
300-21-00

Date
01-23-23

Scale
AS NOTED


Sheet
MCP11



PROJECT SUMMARY	
SITE LOCATION:	SWC OF N CLEVELAND AVE & NE PINE ISLAND RD LEE COUNTY, FL 33903
PROJECT AREA:	9.71 ACRE ±
STRAP NUMBER:	03442401000000008B 03442401000000008A 034424010000000080 034424060000000040 034424110000000080 034424110000000090 034424110000000100 034424110000000110 034424110000000120 034424110000000130 034424110000000140
ZONING/REZONING	C-1, C-1A & AG-2 TO CPD

LEGEND	
	CPD BOUNDARY
	BUILDING
	PUBLICLY ACCESSIBLE OPEN SPACE = 0.35 ACRES
	TOTAL OPEN SPACE PROVIDED = 2.56 ACRES
	NATIVE PRESERVE = 1.00 ACRE
	PEDESTRIAN CROSSWALK
	VEHICULAR FLOW INGRESS/EGRESS
	LOADING ZONE
	PAVEMENT EDGE DRIVE
	SIDEWALK
	DEVIATION TRIANGLE

OPEN SPACE SUMMARY			
<u>LAND USE</u>	<u>AREA</u>	<u>LAND USE</u>	<u>AREA</u>
REQUIRED OPEN SPACE	2.56 ACRES (0.20 X 3.49 ACRES + 0.30 X 0.22 ACRES)	REQUIRED ON-SITE PRESERVE	1.29 ACRES (0.5 x 2.56 ACRES)
PROVIDED OPEN SPACE	2.56 ACRES (INCLUDES NATIVE PRESERVE)		
REQUIRED PUBLICLY ACCESSIBLE OPEN SPACE	0.35 ACRES (0.10 X 3.49 ACRES)	PROVIDED ON-SITE PRESERVE (PER LDC SEC. 10-415(B)(3)(a) & (b)(4) CREDITS)	1.35 ACRES = (135% (CREDIT) x 1.0 ACRES PROVIDED ON-SITE)
PROVIDED PUBLICLY ACCESSIBLE OPEN SPACE (IN ADDITION TO REQUIRED OPEN SPACE)	0.35 ACRES		



No.	Revision/Issue	Date
01/2024	POST HEX REVISION	01/2024
02/2024	REVISED FOR HEX	02/2024
03/2024	REVISED BUFFERS	03/2024
04/2024	REVISED LAYOUT	04/2024
05/2024	ISSUE FOR DCI REVIEW COMMENTS	05/2024
06/2024	ISSUE FOR REVIEW	06/2024

INFINITY
 INFINITY ENGINEERING GROUP, LLC
 1208 East Kennedy Boulevard
 Suite 230
 Tampa, Florida 33602
 [p]: 813.434.4770
 [f]: 813.445.4211
 www.legroup.net
 FL Cert. of Auth. No. 27889

PHOENIX
 ASSOCIATES OF FLORIDA
 1705 LAURELWOOD BLVD., SUITE 200, TAMPA, FL 33606
 PH. (813) 284-1111 FAX (813) 284-1112
 PROJECT: PROVIDER OF ARCHITECTURAL SERVICES FOR THE PROJECT. THE ARCHITECT HAS REVIEWED THE PROJECT AND HAS DETERMINED THAT THE PROJECT IS IN COMPLIANCE WITH THE FLORIDA BUILDING CODE, 2018 EDITION, AS AMENDED.

NISIT SAPPARKHAO, P.E.
 FL REG. NO. 64085
 DATE _____

Project Name and Address
PINE ISLAND ROAD CPD
 SWC OF N CLEVELAND AVE & NE PINE ISLAND RD
 LEE COUNTY, FLORIDA 33903


Sheet Title
OPEN SPACE EXHIBIT

Project No.
 300-21.00

Date
 01-23-23

Scale
 AS NOTED

Sheet
MCP12



PROJECT SUMMARY

SITE LOCATION:	SWC OF N CLEVELAND AVE & NE PINE ISLAND RD LEE COUNTY, FL 33903
PROJECT AREA:	9.71 ACRE ±
STRAP NUMBER:	03442401000000008B 03442401000000008A 034424010000000080 034424060000000040 034424110000000080 034424110000000090 034424110000000100 034424110000000110 034424110000000120 034424110000000130 034424110000000140
ZONING/REZONING	C-1, C-1A & AG-2 TO CPD

OPEN SPACE SUMMARY


LAND USE	AREA
ON-SITE INDIGENOUS PRESERVE PROVIDED	1.00 ACRES
OTHER OPEN SPACE PROVIDED	1.58 ACRES
TOTAL OPEN SPACE REQUIRED	2.58 ACRES
TOTAL OPEN SPACE PROVIDED	2.58 ACRES
PUBLICLY ACCESSIBLE OPEN SPACE REQUIRED	0.35 ACRES
PUBLICLY ACCESSIBLE OPEN SPACE PROVIDED	0.35 ACRES

LEGEND

	CPD BOUNDARY		PEDESTRIAN CROSSWALK
	BUILDING		VEHICULAR FLOW INGRESS/EGRESS
	LOADING ZONE		PAVEMENT EDGE DRIVE
	SIDEWALK		DEVIATION TRIANGLE

INDIGENOUS PRESERVE SUMMARY

LAND USE	AREA
ON-SITE INDIGENOUS PRESERVE REQUIRED	1.28 ACRES
ON SITE INDIGENOUS PRESERVE PROVIDED	1.35 ACRES (1.0 ACRES PROVIDED ON SITE X 135% (CREDIT))



Revision	Date	Description
01/02/24	01/02/24	POST WRITTEN SUBMISSION
01/02/24	01/02/24	REVISED FOR HX
01/02/24	01/02/24	REVISED LAYOUT
01/02/24	01/02/24	ISSUE FOR DCI REVIEW COMMENTS
01/02/24	01/02/24	ISSUE FOR REVIEW

INFINITY
INFINITY ENGINEERING GROUP, LLC
1208 East Kennedy Boulevard
Suite 230
Tampa, Florida 33602
Tel: 813.434.4770
Fax: 813.445.4211
www.iggroup.net
FL Cert. of Auth. No. 27889

PHOENIX ASSOCIATES OF FLORIDA
1100 LYNCH ROAD | SUITE 204 | MIAMI, FLORIDA 33136
PH: 305.441.1100 | FAX: 305.441.1101
www.phoenixassociates.com
PHOENIX ASSOCIATES OF FLORIDA is a professional engineering firm providing a wide range of engineering services to its clients. The firm is a member of the American Society of Professional Engineers (ASPE) and the Florida Society of Professional Engineers (FSPE). The firm is also a member of the International Association of Engineering and Construction Firms (IAECF). The firm is committed to providing high-quality engineering services to its clients and to maintaining the highest standards of professional conduct.

NISIT SAPPARKHAO, P.E.
FL REG. NO. 64085
DATE

Project Name and Address: **PINE ISLAND ROAD CPD**
SWC OF N CLEVELAND AVE & NE PINE ISLAND RD
LEE COUNTY, FLORIDA 33903
Project No.: 300-21.00
Date: 01-23-23
Scale: AS NOTED
Sheet: **MCP2.1**

SITE LOCATION: SWYC OF N CLEVELAND AVE & NE PINE ISLAND RD
LEE COUNTY, FL 33903


PROJECT AREA: 9.71 ACRE ±

STRAP NUMBER: 0344240100000000B
0344240100000000A
0344240100000000B
0344240600000000A
0344241100000000B
0344241100000000B
0344241100000000B
03442411000000100
03442411000000110
03442411000000120
03442411000000130
03442411000000140

ZONING/REZONING C-1, C-1A & AG-2 TO CPD

	CPD BOUNDARY		PEDESTRIAN CROSSWALK
	BUILDING		VEHICULAR FLOW INGRESS/EGRESS
	PUBLICLY ACCESSIBLE OPEN SPACE = 0.35 ACRES		LOADING ZONE
	TOTAL OPEN SPACE PROVIDED = 2.55 ACRES		PAVE/MENT EDGE DRIVE
	NATIVE PRESERVE = 1.00 ACRE		SIDEWALK
			DEVIATION TRIANGLE

<u>LAND USE</u>	<u>AREA</u>	<u>LAND USE</u>	<u>AREA</u>
REQUIRED OPEN SPACE	2.56 ACRES (0.20 X 3.49 ACRES + 0.30 X 6.22 ACRES)	REQUIRED ON-SITE PRESERVE	1.29 ACRES (0.5 X 2.56 ACRES)
PROVIDED OPEN SPACE	2.56 ACRES (INCLUDES NATIVE PRESERVE)	PROVIDED ON-SITE PRESERVE (PER LDC SEC. 10-415(B)(3)(e) & (b)(4) CREDITS)	1.35 ACRES = (135% (CREDIT) X 1.0 ACRES PROVIDED ON-SITE)
REQUIRED PUBLICLY ACCESSIBLE OPEN SPACE	0.35 ACRES (0.10 X 3.49 ACRES)		
PROVIDED PUBLICLY ACCESSIBLE OPEN SPACE (IN ADDITION TO REQUIRED OPEN SPACE)	0.35 ACRES		

[illegible]

NISIT SAPPARKHAO, P.E.
FL REG. NO. 64085

DATE

PINE ISLAND ROAD CPD
S/WC OF N CLEVELAND AVE & NE PINE ISLAND RD
LEE COUNTY, FLORIDA 33503

Sheet Title

OPEN SPACE EXHIBIT

ect No. 800-21.00	Sheet
01-23-23	MCP2.2
S NOTED	

Exhibit D

HEARING PARTICIPANTS

County Staff:

1. Elizabeth Workman

Applicant Representatives:

1. Alexis Crespo
2. Brett Nevaril
3. Barrett Stejkal
4. Ted Treesh

Public Participants:

1. Sarah Decker
2. Jason Harper

Exhibit E

INFORMATION

UNAUTHORIZED COMMUNICATIONS

The LDC prohibits communications with the Hearing Examiner or her staff on the substance of pending zoning actions. There are limited exceptions for written communications requested by the Hearing Examiner, or where the Hearing Examiner seeks advice from a disinterested expert.

HEARING BEFORE LEE COUNTY BOARD OF COUNTY COMMISSIONERS

- A. The Hearing Examiner will provide a copy of this recommendation to the Board of County Commissioners.
- B. The Board will hold a final hearing to consider the Recommendation and record made before the Hearing Examiner. The Department of Community Development will notify hearing participants of the final hearing date. Only Parties and participants may address the Board at the final hearing. Presentation by participants are limited to the substance of testimony presented to the Hearing Examiner, testimony concerning the correctness of Findings of Fact or Conclusions of Law contained in the Recommendation, or allegations of relevant new evidence not known or that could not have been reasonably discovered by the speaker at the time of the Hearing Examiner hearing.
- C. Participants may not submit documents to the Board of County Commissioners unless they were marked as Exhibits by the Hearing Examiner. Documents must have the Exhibit number assigned at hearing.

COPIES OF TESTIMONY AND TRANSCRIPTS

- A. Every hearing is recorded. Recordings are public records that become part of the case file maintained by the Department of Community Development. The case file and recordings are available for public examination Monday through Friday between 8:00 a.m. and 4:30 p.m.
- B. A verbatim transcript may also be available for purchase from the court reporting service.