

M E M O R A N D U M
FROM
THE OFFICE OF THE
LEE COUNTY HEARING EXAMINER

DATE: August 4, 2025

TO: Board of County Commissioners FROM: Amanda L. Rivera
Lee County Deputy Hearing Examiner

RE: HOME FRONT HEROES MINOR CPD
Hearing Examiner Recommendation

Deputy Hearing Examiner Amanda L. Rivera has rendered a Recommendation on the following zoning request:

HOME FRONT HEROES MINOR CPD

DCI2023-00047

HEARD: March 13, 2025
Record Closed: March 28, 2025

The Zoning Section of the Department of Community Development will schedule a final hearing before the Board in the coming weeks.

cc: Michael Jacob, Esq. / County Attorney's Office
Joseph Adams, Esq. / County Attorney's Office
Anthony Rodriguez, AICP / Zoning Section
Brian Roberts / Zoning Section
Warren Baucom / Economic Development
Phil Gillogly / Natural Resources
Brienne Cherry / Community Development
Applicant(s) & Representative(s)
Other Interested Parties

Summary of Hearing Examiner Recommendation

HOME FRONT HEROES MINOR CPD

Applicant seeks to amend the Moody River RPD/CPD to rezone land east of Moody Road. The requested rezoning permits operation of a non-profit entity dedicated to community youth enrichment.

Although the request seeks CPD zoning, proposed uses are narrowly tailored to social services through community outreach programs. Conditions of approval ensure the site will not be used for high-impact commercial activities such as retail or restaurants.

Existing site approvals offset trip generation by eliminating multi-family units on the affected 15.76 acres. Proposed conditions of approval and LDC regulations mitigate off-site impacts to protect surrounding residents from site activity.


The Hearing Examiner agrees with Staff's recommendation of approval, with conditions.

Detailed recommendation follows


DCI2023-00047

Future Land Use

-  Subject Property
-  Intensive Development
-  Central Urban
-  Suburban
-  Public Facilities
-  Wetlands



0 500 1,000
Feet




EagleView, Lee County Property Appraiser, Lee County GIS



DCI2023-00047

Aerial

 Subject Property



0 500 1,000
Feet



OFFICE OF THE HEARING EXAMINER, LEE COUNTY, FLORIDA

HEARING EXAMINER RECOMMENDATION

REZONING: DCI2023-00047

Regarding: HOME FRONT HEROES MINOR CPD

Location: South of Hancock Bridge Parkway, East of Moody Road
North Fort Myers Planning Community
(District 4)

Hearing Date: March 13, 2025

Record Closed: March 28, 2025

I. Request

Amend the Moody River Estates RPD/CPD (Z-05-048) to rezone the western 15.76± acres of Tract M from Residential Planned Development (RPD) to Commercial Planned Development (CPD) to allow a maximum of 46,000 square feet of administrative offices, two caretaker's residences, recreation, social services, and accessory multi-purpose outdoor recreation areas, boat ramps, and a private multi-slip docking facility with a maximum 10 wet slips and 10 boat trailer parking/dry slips. The maximum building height is 45 feet.

The property's legal description is set forth in Exhibit A.

II. Hearing Examiner Recommendation

Approval, subject to the conditions and deviations set forth in Exhibit B.

III. Discussion

The Hearing Examiner serves in an advisory capacity to the Board of County Commissioners (Board) on applications to amend an approved planned development.¹ In satisfaction of this duty, the Hearing Examiner accepted testimony and evidence on the application to rezone 15.76± acres of the Moody River Estates RPD/CPD to CPD.²

In preparing a recommendation to the Board, the Hearing Examiner must consider the Lee County Comprehensive Plan (Lee Plan), the Land Development Code (LDC), and other applicable County regulations to the facts presented in a rezoning

¹ LDC §34-145(d)(1)a & (2)a.

² The zoning boundary includes 4.98± acres of Hanock Creek. See Legal Description & MCP.

request.³ Specifically, the Hearing Examiner must find the request is compatible with surrounding uses and complies with Lee Plan and LDC requirements relating to such items as transportation facilities, natural resources, and urban services.⁴ The Hearing Examiner may take judicial notice of previous Board decisions.⁵ The Hearing Examiner's recommendation must be based on competent and substantial evidence.⁶

The Hearing Examiner recommends approval, finding the request satisfies LDC review criteria.

Zoning Review Criteria

Before recommending approval, the Hearing Examiner must find the request:

- A. Complies with the Lee Plan;
- B. Meets the LDC and other applicable County regulations or qualifies for deviations;
- C. Is compatible with existing and planned uses in the surrounding area;
- D. Provides access sufficient to support the proposed development intensity;
- E. Addresses impacts on transportation facilities by County regulations or conditions of approval;
- F. Will not adversely affect environmentally critical/sensitive areas or natural resources; and
- G. Will be served by urban services, if located in a Future Urban Area.⁷

When the requested zoning action is a planned development, the Hearing Examiner must also find:

- H. The proposed use/mix of uses is appropriate at the proposed location;
- I. Recommended conditions (1) provide sufficient safeguards to the public interest, and (2) reasonably relate to impacts on the public interest expected from the proposed development; and

³ LDC §34-145(d)(3).

⁴ LDC §34-145(d)(4).

⁵ Lee Co. Admin. Code 2-6 §2.3.D(4)(b).

⁶ Lee Co. Admin. Code 2-6 §3.3.A(2); LDC §34-83(a)(4)a.1(a).

⁷ LDC §34-145(d)(4)a.1. Future Urban Area is a defined term in the Lee Plan Glossary.

- J. Requested deviations (1) enhance achievement of planned development objectives, and (2) protect public health, safety, and welfare.⁸

Zoning History/Request Synopsis

In 2003, the Board rezoned 221.9± acres to Moody Ranch RPD/CPD to permit 1,000 residential dwelling units and 45,000 square feet of commercial uses.⁹

In 2005, the Board amended the Moody Ranch approval to add 19.56± acres identified as “Tract M” east of Moody Road.¹⁰ The amendment approved 200 dwelling units, a private club, recreational facilities, parking, and a boat ramp with dock.¹¹ Maximum approved height on Tract M is 75 feet.¹²

Subsequent development orders followed in 2013 to construct parking, restroom facilities, landscaping, and infrastructure for a private boat launch facility and clearing for future development.¹³

Intervening civil court cases imposed development restrictions and divided Tract M into two parcels.¹⁴

The scope of review for the requested amendment is limited to the western 15.76± acres of Tract M (the “site”).¹⁵ Applicant proposes to develop the site with 46,000 square feet of non-residential uses, including administrative offices, two caretaker’s residences, recreation areas, and social services.¹⁶ Site development will support a charitable organization aimed to educate youth, veterans, and the disabled/disadvantaged in crime prevention/public safety, social outreach, recreation activities, and animal welfare services.¹⁷

⁸ LDC §34-145(d)(4)a.2.

⁹ See Staff Report (pg. 1, *citing* Z-03-022, Attachment M).

¹⁰ See Staff Report (pg. 1-2, *citing* Z-05-048, Attachment L).

¹¹ Z-05-048. The Resolution did not increase density for the overall development. The newly approved 200 units were part of the 1,000 units approved for the RPD/CPD.

¹² See *Id.*

¹³ See Staff Report (pg. 2, *referencing* LDO2013-00596 and DOS2013-00023, Attachment N).

¹⁴ See Staff Report (pg. 2, Attachment F). The western part of Tract M comprises 15.76± acres and the eastern portion occupies the remaining 3.63± acres. See MCP. The record references a Settlement Agreement directing use of the property for non-profit purposes/14 single-family units, but the Agreement is not part of the record and is outside the scope of Hearing Examiner Review. See LDC §34-145(d). Applicant testified the eastern portion is limited to 55 multi-family units and is under separate ownership. Hewitt Testimony (Transcript pg. 14 & 16).

¹⁵ Existing RPD/CPD approvals otherwise remain unchanged.

¹⁶ Hearing testimony reflects caretakers’ quarters are requested as a security measure and to accommodate deputies’ differing schedules. Akin Testimony (Transcript pg. 10).

¹⁷ See Staff Report (pg. 1, Attachment F); Applicant Ex. 1 (slides 4-5, 12).


Site design retains the existing gated entrance from Moody Road.¹⁸ Moody River Estates residents/guests will continue to access the entry gate and traverse north to the boat ramp, parking, and restroom facility.¹⁹ A second gate will provide access to Applicant's charitable organization campus to the south.²⁰

Applicant proposes to reduce permitted height from 75 to 45 feet. Staff recommended approval, with conditions.

Character of the Area

The property sits south of Hancock Bridge Parkway, east of Moody Road.

The site is bounded by the Mangrove Bay multi-family residential community to the north. Moody River Estates, comprised of multi-family and single-family residences and amenity centers, sits to the west beyond Moody Road. Vacant agricultural lands within the 20/20 Conservation program abut to the south. Hancock Creek flows through the property and around commercial properties to the east before emptying into the Caloosahatchee River.



¹⁸ See Applicant Ex. 2: MCP.

¹⁹ Hewitt Testimony (Transcript pg. 21-22).

²⁰ *Id.* at 22.

Lee Plan Consistency/Compatibility

Planned developments must be consistent with the Lee Plan.²¹

Lee Plan Maps designate the site within the Suburban and Wetlands future land use categories in the North Fort Myers Planning Community.²²

Suburban lands are predominantly residential on the fringe of urban areas.²³ Industrial uses are prohibited in the Suburban category.²⁴ The request does not propose industrial use, consistent with this classification.

Wetlands consist of low impact uses that do not adversely affect wetland ecological function.²⁵ The portions of the site designated as Wetlands are located on the island east of the developable area. Conservation easements encumber the Wetlands to ensure protection of environmentally sensitive areas in perpetuity.²⁶

The North Fort Myers Planning Community aims to improve the livability and economic vitality of the community and preserve natural resources.²⁷ The request satisfies this goal by providing recreational opportunities and educational programs through community outreach for youth. Applicant protects natural resources by maintaining indigenous preserves and conservation easements. Nature trails and boardwalks provide accessibility to natural resources without compromising environmentally sensitive lands.²⁸

Compatibility

Applications to amend planned developments must demonstrate compatibility with surrounding land uses.²⁹

The Lee Plan encourages compact and contiguous development patterns where services and infrastructure exist to serve new development.³⁰ The proposed

²¹ LDC §34-411(a), (c), and (i).

²² Lee Plan Maps 1-A, 1-B, & 2-A.

²³ Lee Plan Policy 1.1.5. Commercial uses are not prohibited in the Suburban classification.

²⁴ *Id.*

²⁵ Lee Plan Policy 1.5.1.

²⁶ The MCP reflects the island is encumbered by Conservation Easement North, recorded in the Lee Co. Public Records at Instrument #2013000240535.

²⁷ Lee Plan Goal 30, Policy 30.5.3; LDC §§33-1531 *et. seq.*

²⁸ Lee Plan Policy 30.5.3.

²⁹ LDC §34-145(d)(4)a.1(c). *Compatible* is defined as: the relation between two land uses, buildings or structures, or zoning districts, the state wherein those two things exhibit either a positive relationship based on fit, similarity or reciprocity of characteristics, or a neutral relationship based on a relative lack of conflict or on a failure to communicate negative or harmful influences to another. LDC §34-2.

³⁰ Lee Plan Objectives 2.1, 2.2, Policies 2.2.1, 2.2.2, 6.1.1, 6.1.4.

project constitutes infill development consistent with surrounding development patterns.³¹

The site has been approved for 200 multi-family units and a 53 multi-slip docking facility since 2005.³² The request to amend the RPD/CPD must therefore be evaluated for impacts generated by the delta between the proposed development and existing approvals.³³ The record reflects the proposed amendment adequately addresses potential off-site impacts through design elements, conditions of approval, and Code protections.

Applicant proposes to reduce approved building heights from 75 to 45 feet. Caretakers' units are further reduced to 35 feet due to proximity to residents. The MCP decreases the multi-slip docking facility from 53 to 10 wet slips. These reductions ameliorate impacts anticipated from the proposed development.

Site design locates the social services building in the southwest corner and the caretakers' residences in the northeast to buffer neighboring residents from site impacts.³⁴ The 42,000 square foot building will host offices, classrooms, and indoor recreational facilities such as basketball courts, gymnasiums, and fitness areas.³⁵ Building design must demonstrate compliance with architectural standards.³⁶ Lighting must adhere to LDC specifications to minimize light pollution, glare, and light trespass. Conditions of approval limit hours of operation for outdoor activities and impose buffer standards to shield site activities.

Proposed uses offer valuable community programs through educational opportunities and outreach, job counseling, manpower training, and workforce education.³⁷ Caretakers on-site provide an added measure of security for site and surrounding area.³⁸

³¹ Lee Plan 6.1.7, Glossary definition of "infill." The request does not impact preserves/conservation areas, retains the existing access to Moody Road, and is surrounded by residential development with commercial uses proximate along Hancock Bridge Parkway.

³² Z-05-048; Hewitt Testimony (Transcript pg. 25). Existing approvals allow outdoor recreation facilities such as tennis courts, which would generate noise and off-site impacts. *Id.*

³³ Existing zoning presents off-site impacts based upon the approved development program. Accordingly, review criteria measures impacts generated by the request against impacts that have already been approved. Exchanging residential units for non-residential uses offsets anticipated impacts.

³⁴ Hearing testimony reflects over 200 feet from the building to nearest residence. Transcript pg. 89.

³⁵ The remaining 4,000 square feet in the request is reserved for two caretakers' quarters. See MCP.

³⁶ LDC §§33-1531 *et. seq.*

³⁷ Lee Plan Objective 160.2.

³⁸ Public comment noted current safety concerns that may be ameliorated by Sheriff personnel on site.

Transportation/Traffic

Planned developments must have access to roads with sufficient capacity to support proposed intensity.³⁹ Existing regulations or conditions of approval must address expected impacts on transportation facilities.⁴⁰

Access

The project retains a single access to Moody Road aligned with a gated entry to Moody River Estates.⁴¹ Moody Road is a county-maintained minor collector.⁴² Moody Road intersects Hancock Bridge Parkway just north of the site. Hancock Bridge Parkway is an arterial road.⁴³

The MCP reflects site access will remain gated.⁴⁴ Hearing testimony confirmed RPD/CPD residents/guests may continue to access the gated entry before traversing north to the boat ramp, parking, and restroom facility.⁴⁵ Applicant anticipates installing a second gate to access its campus to the south.⁴⁶ Emergency service providers submitted letters of no objection for the proposed access configuration.⁴⁷

Site design retains an easement along the southern boundary to preserve access to the eastern parcel.

Transportation Impacts

Applicant's traffic engineer prepared a Traffic Impact Statement (TIS) that evaluated trip generation based on a conservative development program.⁴⁸ Expert testimony confirmed the request does not significantly affect projected traffic

³⁹ LDC §34-145(d)(4)a.1(d); §34-411(d)(1).

⁴⁰ LDC §34-145(d)(4)a.1(e); §34-411(d)(2).

⁴¹ The main entrance is located on Hancock Bridge Parkway. Secondary entrances are gate restricted to residents.

⁴² See Staff Report (Attachment H); Lee Co. Admin. Code 11-1. Moody Road is classified as a major collector north of Hancock Bridge Parkway to Pondella Road, and as a minor collector for the segment south to Skyline Drive. Lee Co. Admin. Code 11-1.

⁴³ *Id.*

⁴⁴ Hewitt and Akin Testimony (Transcript pg. 22, 32, 93-94).

⁴⁵ Hewitt Testimony (Transcript pg. 21-22).

⁴⁶ *Id.* at 22.

⁴⁷ See Staff Report (Attachment K); Hewitt Testimony (Transcript pg. 31); Condition 36, Deviation 19. The record contains Letters of No Objection from North Fort Myers Fire District, Lee County Public Safety, and Lee County Sheriff's Office.

⁴⁸ See Staff Report (Attachment F). The TIS utilized classifications for a recreational center and four single-family homes to over-estimate trip generation. The request proposes a private facility and two caretakers' units, which both generate less traffic than the uses evaluated in the TIS. Additionally, expert testimony forecasted significant ride-sharing to the site given the nature of the use, and noted most site-related traffic will occur after school/weekends/summer to accommodate youth programs.

volumes beyond current entitlements.⁴⁹ Affected roadways will continue to operate at acceptable levels of service after project build-out.⁵⁰

Site related impacts will be evaluated during development order review.⁵¹

Applicant demonstrated the request has sufficient access and will not have a detrimental impact on the surrounding roadway system.⁵²

Environmental and Natural Resources

Planned development design must protect and preserve natural site features.⁵³

Site Conditions

The site is vacant, comprised mostly of disturbed lands.⁵⁴ A portion of Hancock Creek is within the property boundary.⁵⁵ Conservation 20/20 land abuts to the south.

Mangrove fringes largely consist of exotic vegetation, qualifying as indigenous under the LDC.⁵⁶ A conservation easement encumbers 1.12± acres of indigenous wetland preserve.⁵⁷

Coastal Area Development

The property lies in a Coastal High Hazard Area.⁵⁸ Land uses in coastal areas are subject to policies in the Lee Plan Conservation & Coastal Management Element.⁵⁹ The Element directs the county to protect human life and development from the impacts of coastal flooding.⁶⁰

⁴⁹ Bykau Testimony (Transcript pg. 49); Applicant Ex. 1 (slide 38). The TIS examined traffic generation for existing approvals of 145 units to conserve the 55 units assigned to the eastern portion of Tract M.

⁵⁰ See Staff Report (Attachment F & H); Bykau Testimony (Transcript pg. 50); Applicant Ex. 1 (slide 38).

⁵¹ Site related improvements include capital improvements and right-of-way dedications for “direct access” improvements to the project. Direct access improvements include site driveways/roads, median cuts made necessary by driveways/roads, right-turn, left-turn, and deceleration/acceleration lanes serving driveways/roads, traffic control measures, and roads/intersection improvements whose primary purpose at the time of construction is to provide access to the development. See Lee Plan Glossary and LDC §2-264; Lee Plan Objective 39.1, Policy 39.1.1. LDC §2-66 *et. seq.*

⁵² See Staff Report (Attachment F and H).

⁵³ LDC §34-411(h)-(g).

⁵⁴ See Staff Report (Attachment I).

⁵⁵ Classified as Bays/Estuaries on the FLUCCS Map (540).

⁵⁶ See Staff Report (Attachment I, *citing* LDC §10-1).

⁵⁷ See Staff Report (Attachment D, I, & J); Lee Plan Policies 101.1.1, 101.1.2, 101.3.2, 101.3.5, 101.4.2, & 101.4.3.

⁵⁸ See Lee Plan Map 5-A, Staff Report (pg. 7). Coastal High Hazard Areas are below the elevation of the Category 1 storm surge line established by a Sea, Lake, and Overland Surges from Hurricanes (SLOSH) computerized storm surge model. Lee Plan Glossary, *citing* F.S. §163.3177(6)(a)10,c(VI), §163.3178(2)(h).

⁵⁹ Lee Plan Objective 2.6. See Goals 59, 72, 101, Objective 101.3, Policy 101.1.1.

⁶⁰ Lee Plan Goal 101.

The Plan restricts development in Coastal High Hazard Areas to uplands.⁶¹ The request complies with this directive and replaces residential with non-residential uses, further protecting human life from potential flooding dangers.

The mangrove fringe along the property's boundary will remain intact, and Applicant proposes no new seawalls in this amendment application.⁶² Development will be subject to regulations designed to reduce vulnerability from natural disasters such as hurricanes and flooding.⁶³

Protected Species⁶⁴

A Protected Species Survey revealed no protected species on site.⁶⁵ Staff inspection confirmed this finding.⁶⁶

A bald eagle nest occupied the RPD/CPD portion west of Moody Road prior to 2022. At that time, the eagles migrated to the parcel south of the subject site.⁶⁷ Evidence indicates the nest was destroyed during Hurricane Ian.⁶⁸ The nest was reconstructed, but fledglings were never confirmed.⁶⁹ Applicant presented the request to the Eagle Technical Advisory Committee (ETAC) and obtained approval of its Bald Eagle Management Plan. Conditions of approval ensure site development complies with the approved Plan.⁷⁰

Stormwater Management⁷¹

The RPD/CPD is subject to an existing Environmental Resource Permit (ERP) issued by South Florida Water Management District (SFWMD). Applicant must obtain a new ERP to incorporate existing outfall structures and meet current design requirements under the proposed development plan.⁷²

⁶¹ Lee Plan Goal 101, Objective 72.2, Policy 101.3.2.

⁶² LDC §26-75; Lee Plan Objective 101.1, Policies 101.1.2, 101.4.2, 101.4.3, 123.1.7, 123.2.8; Staff Report (pg. 7-8).

⁶³ Lee Plan Goals 59, 72, Objectives 72.2, 101.1, Policy 72.2.1; LDC §§2-481 *et seq.* Lee Plan Goal 101 describes Coastal Flooding as including high tide events, storm surge, and impacts of sea level rise. FEMA regulations require a minimum finished floor elevation to be one foot above base flood.

⁶⁴ Applicant's ecology expert testified as to site environmental conditions. Barrett Stejskal, BearPaws Environmental Consulting. Applicant Ex. 1 (slide 34).

⁶⁵ See Staff Report (Attachment F).

⁶⁶ See Staff Report (Attachment I).

⁶⁷ Stejskal Testimony (Transcript pg. 40); Hewitt Testimony (Transcript pg. 18); Applicant Ex. 1 (slide 11).

⁶⁸ *Id.*; Staff Report (Attachment F & I).

⁶⁹ Stejskal Testimony (Transcript pg. 40-42).

⁷⁰ Condition 28; Lee Plan Policy 123.6.1.

⁷¹ Applicant's civil engineer provided expert testimony and prepared a Surface Water Management Narrative in support of the request. See Staff Report (Attachment F). Samuel W. Marshall, P.E., Atwell. See Applicant Ex. 1 (slide 32).

⁷² Marshall Testimony (Transcript pg. 39).

Moody River RPD will continue to discharge water west of Moody Road through the property without modification.⁷³ Runoff is collected via catch basins/culverts, swales, and dry detention areas before discharging into Hancock Creek.⁷⁴

Applicant must demonstrate compliance with SFWMD and Lee County water quality and water quantity standards before development may commence.⁷⁵

Buffers/Open Space

The MCP reflects perimeter buffers that have either been approved by existing entitlements or recommended by ETAC.⁷⁶ Site design meets open space Code requirements.⁷⁷

Marine Engineering⁷⁸

Applicant's marine engineer provided expert testimony detailing marine-related elements of the request.⁷⁹ The site is currently entitled to 53 boat slips, while the request proposes 10 wet slips and 10 dry slips.⁸⁰ The 10 wet slips would be provided via a floating dock to accommodate a variety of vessels.⁸¹ Paddle craft access the water at a separate dock for canoe and kayak launching. Hearing testimony confirmed boat access is restricted to invitees of the project and will not be open to the public.⁸²

The project must obtain approval from state, federal, and local agencies with regulatory authority over proposed marine activities, including the Army Corps of Engineers and U.S. Fish and Wildlife Service.⁸³

Applicant demonstrated the request does not adversely affect environmentally critical, sensitive areas, or natural resources.⁸⁴

⁷³ Marshall and Hewitt Testimony (Transcript pg. 38-39).

⁷⁴ Roberts Testimony (Transcript pg. 63); Staff Report (Attachment F).

⁷⁵ Lee Plan Goal 60 & 61, Policy 60.4.1.

⁷⁶ Hewitt Testimony (Transcript pg. 29-30); See Condition 34 and Deviation 17.

⁷⁷ See MCP Open Space Table, reflecting 3.23± acres open space required and provided. See also Condition 35.

⁷⁸ Applicant's marine engineer is Hans Wilson, P.E.

⁷⁹ Wilson Testimony (Transcript pg. 42-48). The property is subject to a conservation easement encumbering 6.64± acres. See Staff Report (pg. 7-8, Attachment J).

⁸⁰ *Id.* Mr. Wilson detailed the restrictive nature of encumbering slip credits to ensure proposed slips remain at 10 wet and 10 dry slips.

⁸¹ Wilson Testimony (Transcript pg. 43).

⁸² Akin Testimony (Transcript pg. 84).

⁸³ *Id.*; Lee Plan Objective 128.4, Policies 128.4.5, 128.4.7, 128.4.8, 128.4.9, 128.4.10, & 128.4.11.

⁸⁴ LDC §34-145(d)(4)a.1(f).

Urban/Public Services

Public/urban services are the facilities, capital improvements, and infrastructure necessary to support development.⁸⁵ The Lee Plan requires an evaluation of available urban services during the rezoning process of lands within future urban areas.⁸⁶

Although the site is not within a future urban area, a host of urban services and infrastructure serve the property including roads, potable water, police, fire, and emergency medical services.⁸⁷ Lee County Utilities provides potable water and sanitary sewer to the site with sufficient capacity to service the project.⁸⁸

Pedestrian and transit facilities are proximate to the site. LeeTran offers seasonal trolley service with a stop across Moody Road, and year-round service via Route 70 with a stop within one mile.⁸⁹ Existing sidewalks line the west side of Moody Road to tie into the larger network of pedestrian walkways along Hancock Bridge Parkway, Pondella Road, and US 41.

Development will be subject to impact fees.⁹⁰

Deviations

“Deviations” are departures from LDC regulations.⁹¹ The request carries forward approved deviations and proposes five new deviations.⁹² Deviation numbering is retained from prior approvals to preserve continuity across development permits.⁹³ Newly requested deviations acknowledge existing site conditions and

⁸⁵ Lee Plan Glossary: Public services include public water/sewer, paved streets/roads, public transit, parks/recreation facilities, urban levels of police, fire, and emergency services, urban surface water management, schools, employment, industrial, and commercial centers, institutional, public, or administrative facilities, community facilities such as senior citizens centers, libraries, and community centers.

⁸⁶ Lee Plan Objective 2.2, Policy 2.2.1. The Lee Plan defines Future Urban and Future Suburban Areas. Lands within the Suburban land use category, such as the subject property, are not identified as a Future Urban Area. See Lee Plan Glossary.

⁸⁷ The Lee Plan defines and distinguishes Future Urban Areas, Future Non-Urban Areas, and Future Suburban Areas. Lee Plan Glossary. The property falls within Future Suburban and Future Non-Urban Areas. See also Staff Report (pg. 3, Attachment G). The site is serviced by North Fort Myers Fire Control & Rescue District. EMS – Medic 7 and a Lee County Sheriff's office are less than two miles away. See Staff Report (pg. 3).

⁸⁸ See Staff Report (Attachment G).

⁸⁹ Hewitt & Roberts Testimony (Transcript pg. 20 & 60).

⁹⁰ LDC Chapter 2, Article VI.

⁹¹ LDC §34-2.

⁹² See Applicant Ex 1 (slide 19-23).

⁹³ Several deviations were withdrawn under prior approvals, but remain numbered to ensure consistency with various agency permits. Newly requested deviations are enumerated 15-23.

accommodate flexible site design consistent with planned development directives.⁹⁴ Staff supports the requested deviations.⁹⁵

The Hearing Examiner's standard of review requires finding the deviation:

1. Enhances achievement of objectives of the planned development; and
2. Protects public health, safety, and welfare.⁹⁶

Applying LDC deviation standards of review to testimony and evidence in the record, the Hearing Examiner concludes requested deviations meet approval criteria.⁹⁷

Conditions

The county must administer the zoning process so proposed land uses acceptably minimize adverse impacts to adjacent property. Conditions must plausibly relate to anticipated impacts from the proposed development and must be pertinent to mitigation of those impacts on public health, safety, and welfare.⁹⁸

The RPD/CPD is subject to many conditions of approval.⁹⁹ Conditions relate to impacts anticipated from the project.¹⁰⁰ Existing conditions are carried forward without modification.¹⁰¹ New conditions are tied to the proposed amendment.

Public

Applicant held a public meeting consistent with LDC requirements before the North Fort Myers Planning Panel.¹⁰² In addition, Applicant testified to continuous coordination with the Moody River community throughout the application process.¹⁰³

⁹⁴ LDC §34-612(2).

⁹⁵ Emergency service providers reviewed the deviation request and issued letters of no objection. See Staff Report (Attachment J).

⁹⁶ LDC §34-145(d)(4).

⁹⁷ LDC §34-377(a)(4).

⁹⁸ LDC §34-932(b).

⁹⁹ Z-21-022.

¹⁰⁰ LDC §34-83(b)(4)a.3.

¹⁰¹ Condition 1 is modified to reflect the updated MCP and unit count reduction.

¹⁰² Applicant provided meeting minutes from the September 24, 2024 session and supporting materials consistent with LDC §33-1532. See Staff Report (Attachment F).

¹⁰³ See Applicant Ex. 1 (slide 15); Hewitt Testimony (Transcript pg. 19-20).

Several members of the public attended the hearing.¹⁰⁴ Residents voiced concerns about traffic, noise, safety, and compatibility.¹⁰⁵

Conclusion

The Hearing Examiner concurs with staff's analysis and recommendation that the requested RPD/CPD amendment meets LDC approval criteria.

IV. Findings and Conclusions

The Hearing Examiner makes the following findings and conclusions based on the testimony and evidence in the record:

As conditioned herein, the proposed RPD/CPD amendment:


- A. Complies with the Lee Plan. See Lee Plan Goals 2, 4, 5, 6, 30, 60, 101, 128, 160, Objectives 2.1, 2.2, 5.1, 6.1, 30.1, 128.4, 160.3, and Policies 1.1.5, 1.5.1, 2.1.1, 2.1.2, 2.2.1, 5.1.2, 5.1.5, 6.1.1, 6.1.4, 6.1.5, 6.1.6, 6.1.8, 60.4.1, 101.1.1, 101.1.2, 101.3.2, 101.3.5, 101.4.2, 101.4.3, 123.6.1, 128.4.5, 128.4.6, 128.4.7, 128.4.8, 128.4.9, 128.4.11, 135.9.5, 141.1.2; Lee Plan Maps 1A-B, 2A, 4-A, 4-B.
- B. Meets the LDC and other County regulations. See LDC Chapters 10, 33, and 34; §§33-1531 *et. seq.*
- C. Is compatible with existing and planned uses in the area. See, Lee Plan Policies 1.1.5, 2.1.1, 2.1.2, 2.2.1, 5.1.5, 6.1.4, 6.1.8, 135.9.5; LDC §34-411(c), (i), and (j).
- D. Provides sufficient access to support the proposed intensity. LDC §34-411(d).
- E. Addresses expected impact on transportation facilities by County regulations or conditions of approval. See Lee Plan Goal 39, Objective 39.1, Policy 6.1.5, LDC §34-411(d).
- F. Will not adversely affect environmentally critical areas and natural resources. See Lee Plan Goals 77, Objectives 1.5, 4.1, 77.1, Policy 1.5.1, 6.1.6, 60.4.1, 101.1.1, 101.1.2, 101.3.2, 101.3.5, 101.4.2, 101.4.3, 123.6.1, 128.4.5, 128.4.6, 128.4.7, 128.4.8, 128.4.9, 128.4.11, Standard 4.1.4, LDC §34-411(g)-(h).

¹⁰⁴ Most speakers were residents from the neighboring Mangrove Bay multi-family development to the north. Public Testimony (Transcript pg. 44-63).

¹⁰⁵ Some matters fell outside the scope of Hearing Examiner review. The Hearing Examiner's authority in zoning cases is set forth in LDC §34-145(d).

- G. Will be served by urban services. See, Lee Plan Glossary, Map 4A-B, Goal 2; Objectives 2.1, 2.2, 4.1, 53.1, 56.1; Policies 2.2.1, 6.1.4, 6.1.5, 6.1.7, and Standards 4.1.1 and 4.1.2; LDC §34-411(d)-(e).
- H. The proposed mix of uses is appropriate at the proposed location. See Lee Plan Policies 1.1.5, 2.1.1, 5.1.5, and 135.9.5.
- I. The recommended conditions are sufficient to protect the public interest and reasonably relate to the impacts expected from the development. See Lee Plan Policies 5.1.5, 135.9.6; See *also* LDC Chapters 10, 33, and 34.
- J. As conditioned herein, the approved deviation:
 - 1. Enhances objectives of the planned development; and
 - 2. Protects public health, safety, and welfare. §34-145(d)(4)a.2(c).

Date of Recommendation: August 4, 2025.



Amanda L. Rivera
Deputy Hearing Examiner

Lee County Hearing Examiner
1500 Monroe Street, Suite 218
Post Office Box 398
Fort Myers, FL 33902-0398

Exhibits to Hearing Examiner's Recommendation

Exhibit A Legal Description and Vicinity Map
Exhibit B Recommended Conditions and Deviations
Exhibit C Exhibits Presented at Hearing
Exhibit D Hearing Participants
Exhibit E Information

Exhibit A

LEGAL DESCRIPTION AND VICINITY MAP

Exhibit A



Professional Engineers, Planners & Land Surveyors

DESCRIPTION
OF A
PARCEL OF LAND
LYING IN
SECTION 10, TOWNSHIP 44 SOUTH, RANGE 24 EAST
LEE COUNTY, FLORIDA

A PARCEL OF LAND LYING IN SECTION 10, TOWNSHIP 44 SOUTH, RANGE 24 EAST, LEE COUNTY, FLORIDA, AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

COMMENCING AT THE SOUTHWEST CORNER OF THE SOUTHEAST QUARTER OF SAID SECTION 10, THENCE RUN ALONG THE WEST BOUNDARY OF SAID SOUTHEAST QUARTER N 01°10'32" E FOR 1343.11 FEET TO A POINT OF INTERSECTION WITH THE SOUTH BOUNDARY OF THE NORTHWEST QUARTER OF THE SOUTHEAST QUARTER OF SAID SECTION 10 SAID POINT BEING THE **POINT OF BEGINNING**; THENCE S 89°18'20" W FOR 8.63 FEET TO THE EAST LINE OF THE COUNTY MAINTAINED RIGHT-OF-WAY OF MOODY ROAD (33' EAST OF CENTERLINE); THENCE ALONG SAID EAST RIGHT-OF-WAY LINE, N 00°36'02" W FOR 670.06 FEET TO A POINT OF INTERSECTION WITH THE SOUTH BOUNDARY OF THE LANDS DESCRIBED IN OFFICIAL RECORDS BOOK 2138, PAGE 4303, (MANGROVE BAY CONDOMINIUMS) OF THE PUBLIC RECORDS OF LEE COUNTY, FLORIDA; THENCE ALONG SAID SOUTH BOUNDARY N 89°33'52" E FOR 990.00 FEET TO THE CENTERLINE OF HANCOCK CREEK EAST CHANNEL; THENCE ALONG THE APPROXIMATE CENTERLINE OF SAID HANCOCK CREEK, FOR THE FOLLOWING (3) THREE COURSES:

- 1) S 02°52'11" E FOR 201.15 FEET;
- 2) N 74°09'54" E FOR 296.35 FEET;
- 3) S 74°26'06" E FOR 79.67 FEET TO A POINT OF INTERSECTION WITH THE EAST BOUNDARY OF THE

NORTHWEST QUARTER OF THE SOUTHEAST QUARTER OF SAID SECTION 10; THENCE ALONG SAID EAST BOUNDARY S 01°30'32" W FOR 164.71 FEET TO THE NORTHEAST CORNER OF LANDS DESCRIBED IN INSTRUMENT NUMBER 2022000185447 OF SAID PUBLIC RECORDS; THENCE NORTHWESTERLY, SOUTHWESTERLY AND NORTHWESTERLY ALONG THE NORTHERLY LINE OF SAID LANDS, FOR THE FOLLOWING (17) SEVENTEEN COURSES:

- 1) N 81°07'54" W FOR 28.53 FEET;
- 2) N 89°05'42" W FOR 33.51 FEET;
- 3) N 84°36'07" W FOR 27.15 FEET;
- 4) N 81°02'31" W FOR 37.15 FEET;
- 5) N 86°39'42" W FOR 47.65 FEET;
- 6) S 76°21'19" W FOR 19.74 FEET;
- 7) S 71°36'26" W FOR 17.76 FEET;
- 8) S 65°13'50" W FOR 21.64 FEET;
- 9) S 60°18'43" W FOR 36.94 FEET;
- 10) S 47°10'00" W FOR 26.05 FEET;
- 11) S 38°29'37" W FOR 39.67 FEET;
- 12) S 48°24'32" W FOR 77.81 FEET;
- 13) S 73°49'21" W FOR 16.95 FEET;
- 14) S 63°14'23" W FOR 58.74 FEET;
- 15) S 69°08'58" W FOR 35.05 FEET;
- 16) S 83°44'12" W FOR 60.94 FEET;

17) N 87°06'59" W FOR 12.91 FEET TO THE NORTHWEST CORNER OF SAID LANDS, SAID POINT ALSO BEING AN INTERSECTION WITH THE WEST LINE OF THE EAST 533 FEET OF SAID NORTHWEST QUARTER OF THE SOUTHEAST QUARTER OF SECTION 10; THENCE S 01°30'32" W ALONG SAID WEST LINE AND THE WEST LINE OF

SHEET 1 OF 3

• SERVING THE STATE OF FLORIDA •

SAID LANDS FOR 190.12 FEET TO THE SOUTHWEST CORNER OF SAID LANDS AND AN INTERSECTION WITH THE SOUTH LINE OF SAID NORTHWEST QUARTER OF THE SOUTHEAST QUARTER; THENCE S 89°18'20" W ALONG SAID SOUTH LINE FOR 799.25 FEET TO THE **POINT OF BEGINNING**.

PARCEL CONTAINS 15.76 ACRES, MORE OR LESS.


NOTE: ACREAGE INCLUDES STATE OWNED SOVEREIGN LANDS.

SUBJECT TO EASEMENTS, RESTRICTIONS, RESERVATIONS AND RIGHTS-OF-WAY OF RECORD.

BEARINGS ARE BASED ON THE WEST LINE OF THE SOUTHEAST QUARTER OF SECTION 10, TOWNSHIP 44 SOUTH, RANGE 24 EAST, LEE COUNTY, FLORIDA AS BEARING N 01°10'32" E.

DESCRIPTION PREPARED: 02-02-2024

DESCRIPTION REVISED 02-02-2024



RICHARD M. RITZ
REGISTERED LAND SURVEYOR
FLORIDA CERTIFICATION NO. 4009
DATE SIGNED: 02-02-2024

Digitally signed by Richard M. Ritz, R.L.S.
#4009 State of Florida using an SHA-1
authentication code. Printed copies of this
document are not considered signed and
sealed and the SHA-1 authentication code
must be verified on any electronic copies.
Date: 2024.02.02 12:00:08 -05'00'

REVIEWED
DCI2023-00047
Rick Burris, Principal
Planner
Lee County DCD/Planning
9/3/2024

SHEET 2 OF 3

• SERVING THE STATE OF FLORIDA •

10511 Six Mile Cypress Parkway • Suite 101 • Fort Myers, Florida 33966
Phone 239-939-5490 • www.bankseng.com • Fax 239-939-2523
Engineering License No. EB 6469 • Surveying License No. LB 6690
S:\Jobs\25xx\2506\Surveying\Descriptions\2506-MOOD-LGL-2024.doc
S:\Jobs\25xx\2506\Surveying\Descriptions\2506-MOOD-SKT-2024.dwg

A PARCEL OF LAND LYING IN
SECTION 10, TOWNSHIP 44 SOUTH, RANGE 24 EAST,
LEE COUNTY, FLORIDA

NOTES:

- 1.) SUBJECT TO EASEMENTS, RESTRICTIONS, RESERVATIONS AND RIGHTS-OF-WAY OF RECORD.
- 2.) BEARINGS ARE BASED ON THE WEST LINE OF THE SE 1/4 OF SECTION 10, TOWNSHIP 44 SOUTH, RANGE 24 EAST, LEE COUNTY, FLORIDA AS BEARING N 01°10'32" E.

LINE TABLE

LINE	BEARING	DISTANCE
L1	N 81°07'54" W	28.53'
L2	N 89°05'42" W	33.51'
L3	N 84°36'07" W	27.15'
L4	N 81°02'31" W	37.15'
L5	N 86°39'42" W	47.65'
L6	S 76°21'19" W	19.74'
L7	S 71°36'26" W	17.76'
L8	S 65°13'50" W	21.64'
L9	S 60°18'43" W	36.94'
L10	S 47°10'00" W	26.05'
L11	S 38°29'37" W	39.67'
L12	S 48°24'32" W	77.81'
L13	S 73°49'21" W	16.95'
L14	S 63°14'23" W	58.74'
L15	S 69°08'58" W	35.05'
L16	S 83°44'12" W	60.94'
L17	N 87°06'59" W	12.91'

SEE SHEET 1 OF 2 FOR COMPLETE
METES AND BOUNDS DESCRIPTION.

THIS SKETCH OF DESCRIPTION
IS NOT A BOUNDARY SURVEY

Digitally signed by Richard M. Ritz, R.L.S. #4009 State of Florida using an SHA-1 authentication code. Printed copies of this document are not considered signed and sealed and the SHA-1 authentication code must be verified on any electronic copies.

Date: 2024.02.02 12:00:34 -0500

RICHARD M. RITZ
REGISTERED LAND SURVEYOR
FLORIDA CERTIFICATION NO. 4009

- DATE SIGNED: 2-2-2024
 - THIS SKETCH OF DESCRIPTION IS NOT VALID
 WITHOUT THE SIGNATURE AND THE ORIGINAL RAISED
 SEAL OF A FLORIDA LICENSED SURVEYOR AND MAPPER.

PREPARED 2-2-2024
REVISED 2-2-2024
SHEET 3 OF 3

BANKS
ENGINEERING
Professional Engineers, Planners, & Land Surveyors
Serving The State Of Florida

10511 SIX MILE CYPRESS PARKWAY, SUITE 101
FT. MYERS, FLORIDA 33966
PHONE (239)939-5490 FAX (239)939-2523

ENGINEERING LICENSE # EB 6469
SURVEY LICENSE # LB 6690

WWW.BANKSENG.COM


$$1'' = 160'$$

MANGROVE BAY
DETACHED CONDOMINIUM HOMES
(O.R. 2138, PG. 4303)

SOUTH BOUNDARY OF O.R. 2138, PG. 4303

(O.R. 2864, PG. 3167)
10-44-24-00-00047.0010

(O.R. 2864, PG. 3171)
10-44-24-00-00047.0000

SOUTH BOUNDARY OF O.R. 2864, PG. 3171

SUBJECT PARCEL

PARCEL CONTAINS 15.76 ACRES
 (NOTE: 1 ACREAGE INCLUDES STATE
 OWNED GOVERNMENT LAND)
 MORE OR LESS

NOTE: ACREAGE INCLUDES STATE OWNED SOVEREIGN LANDS

(O.R. 3616, PG. 227)
10-44-24-00-01046.0000

APPROXIMATE
EDGE OF WATERS —
HANCOCK CREEK

S 89°18'20" W
8.63'

P.O.B.
S.W. CORNER
N.W. 1/4 S.E. 1/4
SECTION 10

(BEARING BASIS)
01°10'32" E 1343.11'
BOUNDARY OF THE S.E. 1/4
SECTION 10

P.O.C.

— I.N. 2005000142765
S.W. CORNER OF THE
S.E. 1/4 SECTION 10

SKYLINE DRIVE

LEGEND:

C	INDICATES CENTERLINE
O.R.	INDICATES OFFICIAL RECORDS
P.O.B.	INDICATES POINT OF BEGINNING
I.N.	INDICATES INSTRUMENT NUMBER
P.I.	INDICATES POINT OF INTERSECTION
P.O.C.	INDICATES POINT OF COMMENCEMENT


REVIEWED
DCI2023-00047
Rick Burris, Principal
Planner
Lee County DCD/Planning
9/3/2024

S: \JOBS\25XX\2506\SURVEYING\DESCRIPTIONS\2506-MOOD-LGL-2024.DOC
S: \JOBS\25XX\2506\SURVEYING\DESCRIPTIONS\2506-MOOD-SKT-2024.DWG

DCI2023-00047

Zoning

 Subject Property



0 500 1,000
Feet




Exhibit B

RECOMMENDED CONDITIONS AND DEVIATIONS

References to uses are as defined in the Lee County Land Development Code (LDC).

CONDITIONS

1. Master Concept Plan (MCP) and Development Parameters

- a. MCP. Development must be consistent with the two-page MCP entitled "Moody River Estates," and "Home Front Heroes Minor CPD," stamped received February 6, 2025 (Exhibit B1).
- b. Lee Plan and LDC Compliance. Development must comply with the LDC and Lee Plan at time of development order approval, except as granted by deviation herein. Subsequent changes may require additional approvals.
- c. Development Parameters.
 - i) Overall RPD/CPD: Limited to 1,000 residential dwelling units and 91,000 square feet of commercial uses. Dwelling units may consist of single-family, zero-lot-line, townhouse, and multi-family units.
 - ii) Tracts A-L: Maximum height is 35 feet.
 - iii) Tract M:
 - 1) *Eastern 3.63± acres*: Maximum 200 dwelling units (of the total 1,000 permitted) and maximum building height of 75 feet.
 - 2) *Western 15.76± acres*: CPD allowing up to 46,000 square feet of non-residential intensity, including two caretakers' residences.
 - iv) Tract K: CPD allows up to 45,000 square feet of commercial uses.
 - v) Tracts B and M: If multiple-family dwelling units are developed within 250 feet of Moody Road, Developer must provide the following buffer with the first development order for the project.
 - 1) The buffer must be no less than 20 feet in width.
 - 2) There may be no fewer than five trees per 100 linear feet of the length of the buffer.
 - 3) Trees must be no less than four inches in diameter at 12 inches above the ground and no less than 16 feet in height at planting.
 - 4) Shrubs must be a minimum ten-gallon container size; planted in double staggered rows; at least 48 inches in height; and spaced 36 inches on center. They must be at least 60 inches in height within 12 months of the time of planting and maintained in perpetuity at a height of no less than 60 inches above the adjacent pavement that is required to be buffered,

- screened, or both, except for visibility at intersections and where pedestrian access is provided.
- 5) In Tract B, no building backs may face Moody Road, and no multi-family building backs may contain more than four dwelling units. In Tract M, no multi-family building backs may face Moody Road.
- 6) Tract B along Moody Road:
- Minimum Width: 20 feet
 - Minimum # of trees: 5 per 100 linear feet
 - Minimum tree size: Trees must be no less than four inches in diameter at 12 inches above the ground and no less than 16 feet in height at the time of planting.
- Hedges: Shrubs must be a minimum 10-gallon container size; planted in double staggered rows; at least 48 inches in height; and spaced 36 inches on-center. They must be at least 60 inches in height within 12 months of time of planting and maintained in perpetuity at a height of no less than 60 inches above the adjacent pavement required to be buffered, screened or both, except for visibility at intersections and where pedestrian access is provided.

At least 75 percent of the trees and 50 percent of the shrubs used to fulfill these requirements must be native Florida species.

No wall is required for this buffer.

- vi) Tract I: Single-family lot area must be at least 7,500 square feet.

2. **Uses and Development Regulations**

a) **Schedule of Uses**

RPD - PERMITTED LAND USES

Tract I - Residential IA (R-1A)

Accessory Uses

Administrative Offices

Agricultural Uses, continuation of bona fide use only

Dwelling Units

Single Family, detached (up to 500 units)

Entrance Gates and Gatehouses

Essential Services
Essential Service Facilities, Group I
Excavation, Water Retention
Fences and Walls
Home Occupation, as limited by the LDC
Model Homes, Model Units, and Model Display Center, including accessory parking lots, Real Estate Sales and Rental Office - limited to sales of lots, homes, or units within the development.
Real Estates Sales and Rental Office - limited to sales of lots, homes or units within the development.
Recreation Facilities, Personal and Private On-Site
Residential accessory uses, including but not limited to:
 Private garages, carports, and parking areas
Private swimming pools and enclosures
Private Boat Dock and tennis courts
Signs
Temporary Uses - limited to a sales center and a construction Office

Tracts C, D, F, H, and J - Residential 1 (R-1)

All uses permitted in the R-1A District plus Dwelling Units: Townhouses (up to 500 units) and Two-family Attached (up to 400 units)

Tracts A, B, and G - Residential 2 (R-2)

All uses permitted in the R-1A District plus Dwelling Units: Multiple Family Buildings (up to 600 units)

Eastern 3.63± Acres of Tract M - Residential 3 (R-3) (up to 200 units)

All uses in the Residential 1A- R-2 districts and the following:

 Multi-slip docking facility
 Parking Lot
 Accessory

Tract E - Recreational Facilities, Private On-Site or Off-Site

Accessory Uses
Administrative Offices
Agricultural Uses, continuation of bona fide use only
Club (up to 20,000 square feet) Private including but not limited to the following ancillary uses:
 Food and Beverage Service
 Pro Shop and Specialty Retail, Group I
 Locker Rooms
 Health Club and Spa
 Rental or Leasing Establishment, Group I (limited to bicycles, tennis rackets, and other small sports equipment for use within the development)
Entrance Gates and Gatehouses

Essential Services
Essential Service Facilities, Group I
Excavation, Water Retention
Fences and Walls
Project Maintenance Facility
Recreational Facilities, Group I, for use by residents and their guests
Signs, including the existing billboard
Temporary Uses - limited to Real Estate Sales and Rental Office limited
to sales of lots, homes, or units within the development and a
Construction Office

CPD PERMITTED USES

Tract K (up to 45,000 sq ft)

Accessory Uses
Administrative Offices
Animal Clinic - outside kennels are prohibited
ATM (automatic teller machine)
Auto Parts Store
Banks and Financial Establishments, All Groups
Business Services, Group I
Clothing Stores
Daycare Center, Child or Adult
Department Store
Drive-through facility accessory to any permitted use
Drug Store
Essential Services
Essential Service Facility, Group I
Fences and Walls
Gift and Souvenir Shop
Hardware Store
Health Care Facility, Group III
Hobby, Toy and Game Shop
Hospice
Offices, Medical
Personal Services Groups I and II - limited to Beauty Spas, Health Clubs or
Spas, Reducing or Slenderizing Salons, Group III, and Group IV -
limited to babysitting bureaus, debt counseling services, portrait
copying, shopping services, and tax return preparation services
Real Estate Sales and Rental Office
Rental and Leasing Establishments, Group II - outside storage is prohibited
Restaurants, Standard - Groups I, II, and III
Shopping Center
Signs, in compliance with the LDC
Social Services, Group I only

Specialty Retail Shops, Groups I - IV
Storage, Indoor only and only as ancillary use
Studios
Temporary Uses - limited to sales center and construction offices, in
compliance with LDC regulations regarding temporary uses
Variety Store (ADD2017-00148)

HOME FRONT HEROES MINOR CPD – Western 15.76± acres of Tract
M (up to 46,000 sq ft)

Accessory Uses and Structures*

Administrative Offices

Boats: Boat ramps and dockage (not marinas) – 2 non-motorized ramps
Limited for the use of Home Front Heroes Minor CPD and guests

Boat Ramp – private (Existing Moody River Estates Waterpark)
Limited to residents/guests/property owners within Moody
River Estates RPD and Home Front Heroes Minor CPD

Caretakers' Residences (maximum 2)

Community gardens

Entrance gate and gatehouse

EMS, fire or sheriff's station, limited to sheriff's office and ancillary uses

Essential services

Essential service facilities, Group I

Excavation, water retention

Fences, walls

Parking lot: accessory, temporary

Private multi-slip docking facility (maximum 10 wet slips and 10 boat trailer
parking/dry slips)

Recreational facilities, personal, private on-site

Signs, in accordance with Chapter 30

Social Services, Groups I and II, excluding Offender Rehabilitation
Agencies and Offender Self-Help Organizations

Storage, Indoor only

Temporary Uses

*Anticipated Accessory Uses include, but not limited to:

Outreach Education/Youth Programs

Community Outreach Programs to include Crime Prevention Education/
Presentations.

Sailing/Boating Lessons

Boxing Lessons

Various Programs with Sheriff's Youth Athletic League

Soccer

Basketball

Pickleball

Explorers Programs

Camping Tents
 Kayaking/Canoeing Fishing
 Sheriff's Summer Camp
 Arts and Crafts
 Shade Structures
 Tutoring
 Temporary events: Petting Zoo, Bounce Houses, Mobile Food Vendors
 (pursuant to LDC §34-3052), and similar uses
 Lee County Sheriff demonstration events - No tactical training or
 discharging of firearms

Conservation Areas (Wetland and Upland Conservation Areas)

Interpretative centers and signage, rain shelters, gazebos
 Nature and foot trails including boardwalks, benches, and jogging trails
 Paths, boardwalks and bridges
 Water Management Facilities
 Wildlife Management
 Mitigation and Restoration Activities

- b) Site Development Regulations for all parcels except Home Front Heroes
Minor CPD/western 15.76± acres of Tract M: As approved by Zoning
Resolution Z-05-048, except for building heights in the eastern 3.63± acres
of Tract M as limited by Condition 1(c)3.

OPEN SPACE AND INDIGENOUS VEGETATION/ WEST OF MOODY RD							
	ACRES	OPEN SPACE			INDIGENOUS VEGETATION		
		REQUIRED		MIN. PROVIDE D	REQUIRED		MIN. PROVIDED
		%OPEN SPACE	ACRES	ACRES	% INDIGENOUS	ACRES	ACRES
RESIDENTIAL PLANNED DEVELOPMENT							
RESIDEN. TRACTS W/LOTS GREATER THAN 6,500 SF.	54.0*	N/A	N/A	4.32	N/A	2.16	2.16
BALANCE OF DEVELOPMENT	163.4	40%	65.36	65.36	50%	32.68	32.68
TOTAL	217.4		65.36	69.68	50%	34.84	34.84
COMMERCIAL PLANNED DEVELOPMENT							
CPD	4.5	30%	1.35	1.35	50%	.68	.68**
TOTAL PROJECT	221.9		66.71	71.03		35.52	35.52

* If the acreage of "Residential Tracts with lots greater than 6,500 square feet" changes, this table will be adjusted accordingly.

** This acreage may be provided within the Residential Planned Development.

RESIDENTIAL PLANNED DEVELOPMENT / MOODY RANCH

LAND USES	MIN LOT AREA (SF)	MIN LOT WIDTH (FT)	MIN LOT DEPTH (FT)	MIN. SIDE SET-BACK INCL. CORNER LOTS (FT)*	MIN. REAR LOT SET-BACK (FT)	MIN. REAR WET-LAND SET-BACK (FT)	MIN. REAR ACC. SET-BACK (FT)	MIN. FRONT ENTRY GAR-AGE SET-BACK (FT)	MIN. BLDG. OR SIDE ENTRY GARAGE SET-BACK (FT)	MIN. WTR BODY SET-BACK (FT)	MAX BLDG. HGHT. (FT)	MIN. BLDG SEPARATION (FT)	MAX. LOT COV-ER-AGE (%)**
SINGLE-FAMILY DETACHED	4,000	40	100	5	20	20	5	20	12	20	35 OR 2 STORY	10	45
TWO FAMILY ATTACHED	3,500	35	100	0 OR 5	20	20	5	20	12	20	35 OR 2 STORY	10	45
TOWN HOUSE	2,000	25	80	0 OR 10	20	20	5	20	15	20	35 OR 2 STORY	10	45
MULTI-FAMILY	10,000	100	100	10	20	20	5	20	20	20	35 OR 2 STORY	10 OR 20 ***	45
CLUB HOUSE	20,000	80	100	10	20	20	5	N/A	20	20	45 OR 2 STORY	20	45

* Applies to lots of all widths and to corner lots. Each lot, including corner lots, will have only one front yard.

** As defined by LDC Chapter 34. *** 10 feet for 1-story building, 20 feet for 2-story buildings and higher.

COMMERCIAL PLANNED DEVELOPMENT TRACT K		
	PRINCIPAL USES	ACCESSORY USES
MIN. LOT OR PARCEL AREA	10,000 square feet	N/A
MIN. LOT WIDTH	75 feet	N/A
MINIMUM BUILDING SETBACKS:		
HANCOCK BRIDGE PARKWAY	35 feet or BH, whichever is greater	20 feet
INTERNAL FRONTAGE ROAD	15 feet	20 feet
WATERFRONT	25 feet	Zero (0) feet to bulkhead or rip-rap at top of bank
MINIMUM DISTANCE:		
Between Structures part of an architecturally unified group	10 feet	10 feet*
Between All Other Structures	20 feet	10 feet
MAXIMUM BUILDING HEIGHT:		
Office Buildings	80 feet	80 feet
Boat Dry Storage	35 feet	35 feet
Architectural features	N/A	100 feet
MAXIMUM LOT COVERAGE *	55 percent	55 percent

* as defined by LDC Chapter 34

c) HOME FRONT HEROES MINOR CPD (Western 15.76± acres of Tract M)

Minimum Lot Area and Dimensions:

Area: Conservation Easement Island 1.12 acres (no minimum width/depth)
Main Development Parcel: 9.66 acres
Width: 670 feet
Depth: 360 feet

Minimum Building Setbacks:

Perimeter (Principal) 15 feet or ½ building height (whichever is greater)
Street:
Moody Road: 25 feet
Private: 20 feet
Side: 15 feet or ½ building height (whichever is greater)
Rear: 20 feet
Waterbody: 20 feet
Accessory Structures: In compliance with LDC

Minimum Building Separation:	20 feet or ½ building height (whichever is greater)
Maximum Lot Coverage:	45 percent
Maximum Building Height:	45 feet (Over 35 feet subject to LDC §34-2174)
Open Space:	30 percent (see Deviation 15)

3. **Open Space.** Open space requirements must be tracked with each development order and must be substantially consistent with the Open Space and Indigenous Vegetation. A cumulative open space table listing the development tract, development order number, type of use, lot size, lot coverage, and required open space must be included with each development order. The open space table must include all development orders under review and approved. The development order plans must demonstrate how the open space requirements for common open space and indigenous/native tree preservation are being met. The residential development tracts must be labeled as to minimum lot size and maximum lot coverage. A minimum of 54 acres, including associated lakes and roadways, must be single family residential lots with a minimum lot size of 6,500 square feet and a maximum lot coverage of 45 percent.
4. **Species Survey.** Prior to issuance of a Vegetation Removal Permit: (1) the existing borrow pit area and wetlands must be surveyed specifically for the presence of wading bird and alligator nests. If any active nests are located, then buffer areas must be established to protect these areas; and (2) the area located north of Hancock Bridge Parkway must be resurveyed for gopher tortoise burrows.
5. **Gopher Tortoise Protection.** Gopher tortoises must be protected on-site. The gopher tortoise preserve must be provided in the CO tract with the bald eagle nest on the MCP stamped received February 25, 2005. Development order plans must include the location and detail of sandy earthen berms to be created within the gopher tortoise preserve to provide a high, dry area for burrowing; and a vegetative barrier or permanent fencing must be delineated along any roadway abutting the gopher tortoise preserve. The berms within the preserve must be planted with a mixture of bahia grass, other broad leaf vegetation, and scattered native shrubs prior to moving gopher tortoises to the preserve. Supplemental feeding such as alfalfa hay may be necessary until the berm plantings establish.

Prior to the issuance of a Certificate of Compliance for the infrastructure, either the vegetative barrier or permanent fencing must be installed along any roadways or development areas under construction abutting the gopher tortoise preserve, whichever is chosen at time of local development order review.
6. **Alligator Education.** Prior to local development order approval, the plans must include signs adjacent to the lake abutting the Club Tract E stating "It is unlawful to feed or harass alligators." Additional information regarding how to live with

alligators, including the danger of approaching or feeding alligators, must be available for residents or potential residents in the sales center and club house.

7. **Waterway Buffer.** Prior to local development order approval, a minimum 10-foot waterway buffer must be delineated along the canal measured from the State jurisdictional wetland line. Native vegetation within the waterway buffer must be retained during subdivision development and perpetually by future residents. Additionally, any native tree clusters which occur within 25- feet of the State jurisdictional wetland line must be preserved or relocated on-site using proper horticultural means if the trees interfere with building layout or the site drainage system. Sabal palms located landward of the 10-foot-wide waterway buffer may be preserved in place or relocated on-site. An accessway to a dock or fishing/observation pier may be installed through the waterway buffer limited to a four-foot width and placed to avoid existing native vegetation to the maximum extent possible.

Prior to plat approval, the homeowner's documents/deed restrictions must include language detailing the preservation of native trees along the canal.

8. **Sabal Palms.** Any sabal palms with a minimum eight-foot clear trunk located within the project boundaries north of Hancock Bridge Parkway must be either preserved in place or relocated on-site to buffers or common areas. Efforts must be made to coordinate the salvaging of any sabal palms with a minimum eight-foot clear trunk located within the project boundaries south of Hancock Bridge Parkway with the Division of Environmental Sciences' Staff, whether used on-site or otherwise. Any sabal palms being relocated must be moved in a horticulturally correct manner, per Lee County Extension Services brochure Lee 8/2000A (Exhibit B2). Preserved/relocated palms must be delineated on development order plans and receive protected tree credits per LDC §10-420(h).
9. **Littoral Plantings.** Bulkhead or rip-rap may be used along up to 30 percent of lake shorelines adjacent to internal roadways and Club Tract E. If bulkhead or rip-rap is proposed, it must be delineated on the landscape plan and the paving/grading plan with cross-sections. A compensatory littoral zone must be provided for each linear footage of bulkhead/rip-rap and must consist of an 8:1 slope, with two herbaceous littoral plants per linear foot of shoreline. Littoral plantings must be clustered within the compensatory littoral zone.
10. **Median Openings.** Full median openings indicated on the MCP are subject to future operational decisions by the County to install a traffic signal or to modify/remove the median opening. If installation of a traffic signal is deemed to be appropriate by the County at the project entrance, Developer will be responsible for the full cost of the traffic signal improvement.

11. **Model Homes/Units.** Model Homes and Model Units are regulated by LDC §34-1951. Model Homes, Model Units, and Model Display Centers throughout the entire project are subject to LDC §34-1954(d) time limitations.
12. **Building Separation.** Commercial buildings exceeding 35 feet in height must maintain additional building separation as regulated by LDC §34-2174(a).
13. **Mitigation of Impacts.** Approval of this zoning request does not address mitigation of the project's vehicular or pedestrian traffic impacts. Additional conditions consistent with the LDC may be required to obtain a local development order.
14. **Future Approvals.** Approval of this rezoning does not guarantee local development order approval. Future development order approvals must satisfy requirements of the Lee Plan Planning Communities Map and Acreage Allocation Table 1(b).
15. **Easements.** Drainage and access easements depicted on the Master Concept Plan must be accommodated and incorporated (at development order approval stage) into the development orders and plats for the subject property, unless proof that the easements have been released or relocated is provided.
16. **Blasting.** No development blasting activity is permitted unless approved through the public hearing process to amend the RPD/CPD.
17. **LCEC Easement.** The 12-foot-wide Lee County Electric Cooperative (LCEC) easement depicted on the MCP (recorded at O.R. Book 1054, Page 776), must be released or relocated at the time of development order approval.
18. **Agricultural Uses.** Existing bona fide agricultural uses are allowed only in strict compliance with the following:
 - a. Bona fide agricultural uses in existence at the time application for this project was filed (Exhibit B3) attached hereto, may continue until approval of a local development order for the area of the project containing those uses.
 - b. Additional clearing of trees or other vegetation in agricultural areas is prohibited. Existing areas of bona fide agricultural use may be maintained, i.e., mowed, but not cleared or expanded. This prohibition is not intended to preclude County approved requests for the removal of invasive exotic vegetation.
 - c. Prior to issuance of a local development order, the property owner must provide written proof, subject to approval by the County Attorney's Office, of the following:

- i. Termination of all agricultural use on any portion of the property included in the development order application/approval. Proof must include a sworn affidavit from the person or entity holding title to the subject property that specifically provides:
 1. the date the agricultural uses ceased;
 2. the legal description of the property subject to the development order approval;
 3. an affirmative statement that the owner acknowledges and agrees that all agricultural uses are illegal and prohibited on the property and that the owner covenants with the county that they will not allow any such uses on the property unless and until the property is re-zoned to permit such uses; and,
 4. that the affidavit constitutes a covenant between the owner and the county that is binding on the owner and their assignees and successors in interest. The covenant must be properly recorded in the public records of the county at the owner's expense.
 - ii. Termination of the agricultural tax exemption for any portion of the property included in the development order application/approval. Proof as to termination must include of a copy of the request to terminate the tax exemption provided to the Property Appraiser.
19. **Access.** Design of the right-out turn onto Hancock Bridge Parkway must include adequate sight distance for a vehicle to turn onto Hancock Bridge Parkway and obtain a safe speed without interfering with thru traffic, as described in AASHTO. The access point must also meet the intersection separation distance of 660 lineal feet, as defined in LDC §10-285.
20. DELETED
21. **Boat Ramp.** Development order plans must delineate the boat ramp, docks, and mooring pilings. Final design is subject to review through the Lee County Dock and Shoreline Permit process.
22. DELETED
23. DELETED
24. **Material Transfer.** The transfer of excavated materials south across Skyline Drive is limited to a maximum of 188,000 cubic yards. Material transfer is prohibited between 7:30 a.m. to 8:30 a.m. and 1:30 p.m. to 2:30 p.m. on days

the School District of Lee County holds classes. Otherwise, excavated material may be transferred from 6:00 a.m. to 6:00 p.m. Monday through Friday, provided the crossing section of Skyline Drive is well lit during early morning/late evening. Fill transfer is only permitted on Saturdays from 8:00 a.m. to 5:00 p.m. Fill transfer is prohibited on Sunday.

25. **Roadway Repair**. Developer is responsible for damage to Skyline Drive resulting from project construction activity. Developer must coordinate repairs with the Lee County Department of Transportation.
26. **Skyline Drive Crossing**. Developer must provide personnel to direct traffic and extra lighting at the crossing of Skyline Drive to prevent accidents.
27. **Mood Road Signage**. At the intersection of the project's internal road connection with Moody Road, Developer is responsible for the erection of signs warning Moody Road motorists of the potential crossing of vehicles with boat trailers.
28. **Bald Eagle Management – Tract M**. Prior to local development order approval on the western 15.76 acres of Tract M, Developer must adhere to the attached Bald Eagle Management Plan dated October 2024 (Exhibit B4) for proposed impacts within 660 feet of the bald eagle nest. The 660-foot buffer zone and activities/restrictions outlined in the Plan must be shown on development order plans.
29. **Conservation Easement – Tract M**. Prior to local development order approval on the western 15.76 acres of Tract M, Developer must demonstrate the recorded Conservation Easement has been modified to allow for a maximum of 20 boat slips to remain on the property.
30. **Boat Slips – Tract M**. Prior to local development order approval on the western 15.76 acres of Tract M, Developer must depict and number all proposed boat slips on development order plans.
31. **Bollards – Tract M**. Prior to local development order approval on the western 15.76 acres of Tract M, Developer must depict permanent bollards on development order plans that prevent motorized vessel access at the non-motorized boat ramp identified on the MCP.
32. **Indigenous Preserve – Tract M**. Prior to local development order approval on the western 15.76 acres of Tract M, development order plans must depict 1.12 acres of indigenous preserve area.
33. **Exotic Vegetation – Tract M**. Prior to local development order approval on the western 15.76 acres of Tract M, Developer must remove exotic vegetation by hand from the mangrove fringe as depicted on MCP.

34. **Buffers – Tract M.** Prior to development order approval for the western 15.76 acres of Tract M, Developer must provide the following buffers:
- a. North property line must depict a Type-B buffer preserving existing heritage trees.
 - b. South property line must depict a 30-foot-wide buffer between the 660-foot and 330-foot eagle nest zone consisting of a ten-foot-wide tree planting strip and ten-foot-wide planted swale consisting of the following:
 - i. Slash Pine (*Pinus elliottii*) and Live Oaks (*Quercus virginiana*) must six-foot-in-height, 25 gallon, and installed 20-foot on center; and
 - ii. *Spartina bakerii* must be one gallon and specified to be installed two feet on center within the swale.
 - c. Southwest corner must include preservation of existing indigenous vegetation, no earth work, and hand removal of exotics.
 - d. East property line must preserve existing indigenous vegetation, no earth work, hand removal of exotics within the 330-foot eagle nest zone and a Type-C or Type-F buffer outside of the 330-foot eagle nest zone.
 - e. West property line must depict a Type-D buffer preserving existing heritage trees and a decorative fence along the property line.
35. **Open Space – Tract M.** Prior to development order approval on the western 15.76 acres of Tract M, development order plans must depict 3.23 acres of open space based on 30 percent of 10.78 acres of land.
36. **Notice – Tract M.** Prior to development order approval on the western 15.76 acres of Tract M, Developer must demonstrate the required notice to future property owners has been recorded in the public record detailing the emergency access plan and where a copy of this plan may be obtained.
37. **Platted Lake Maintenance Easement:** The platted lake maintenance easement may continue to be located within single-family lots in Tracts A and G. This easement or right of way must be kept clear by the property owners and have satisfactory vehicle access, as required by LDC §10-328(a). (Approved in ADD2014-00053)
38. **Building Separation:** The minimum building separation for buildings 2-story or greater on property located 13210, 13220, 13230, and 13240 Silver Thorn Loop, and 3180, 3181, and 3191 Sea Trawler Bend shall be as depicted on Exhibit B5. (Approved in ADD2020-00019)
39. **Hours of Operation – Tract M.** Hours of operation for outdoor activities including food trucks, bounce houses, or sporting events for the western 15.76

acres of Tract M are limited to 7:00 a.m. to 9:00 p.m., Sunday through Thursday, and 7:00 a.m. to 11:00 p.m., Friday and Saturday.

40. **Development Permits** County development permits do not create rights to obtain permits from state/federal agencies. Further, County development permits do not create liability on the part of the County if Applicant fails to obtain requisite approvals or fulfill obligations imposed by federal/state agencies or undertakes actions in violation of state/federal law. Applicant must obtain applicable state/federal permits prior to commencing development.

DEVIATIONS

Deviations 1-14 are carried forward from prior approvals without substantive modification.

1. Withdrawn.
2. Withdrawn.
3. **Bank Slopes**. Deviation 3 seeks relief from the LDC §10-329(d)(4) requirement to slope excavation banks, to allow up to 40 percent of the banks to utilize either:
 - a vertical slope, with the condition that lake bottom slopes at the toe of bulkheads may be no greater than 4:1; or
 - a 2:1 (horizontal/vertical) slope to a depth of six-feet below control elevation, with the condition that the 2:1 sections be stabilized with rip-rap.

This deviation was APPROVED subject to Condition 9, and that adequate elements for the protection of wayward vehicles are provided when adjacent to any roadway, parking lot, or driveway aisle.

4. Withdrawn.
5. Withdrawn.
6. Withdrawn.
7. Withdrawn.

8. **Connection Separation**. Deviation 8 seeks relief from the LDC §10-285(a) requirement to provide connection separations on local roads a minimum of 125 feet, to allow driveways serving multi-family units with private driveways to have a minimum separation of 20 feet.

This deviation was APPROVED SUBJECT TO the following condition:

If the setback applies to internal roads/accessways with a posted maximum speed of 20 MPH, there must be a visual clear zone in accordance with LDC §34-3131, traffic calming devices (if required) as identified in the ITE Residential Street Design and Traffic Control Book, and each drive may only serve a private driveway/garage for an individual unit.

9. Withdrawn.

10. Withdrawn.

11. **Accessways**. Deviation 11 seeks relief from the LDC §10-296(l)(4) requirement that no more than 100 multi-family units be constructed without provision of a right-of-way, to allow up to 200 units.

This deviation was APPROVED SUBJECT TO the condition that Developer demonstrates the Emergency Medical Service and local Fire District review/approve the design supporting this deviation in development order plans prior to local development order approval, and that the health, safety, and welfare of the residents in the Eastern 3.63± acres of Tract M have been protected.

12. **Excess Spoil Removal**. Deviation 12 seeks relief from the LDC §10-329 (b) Table1 requirement which limits excess spoil removal plans for development order projects to 20,000 cubic yards of material, to allow up to 188,000 cubic yards.

This deviation was APPROVED SUBJECT TO the condition that soil removal is from the RPO site to the project's RM-2 parcel on the south side of Skyline Drive.

13. **Cul-de-sacs**. Deviation 13 seeks relief from the LDC §10-296(k)(1) requirement to provide a circular turnaround (cul-de-sac) for dead-end streets, to allow a hammerhead turnaround.

This deviation was APPROVED SUBJECT TO the condition that Developer demonstrates the Emergency Medical Service and local Fire District review/approve the design supporting this deviation in development order plans prior to development order approval, and that the health, safety, and welfare of residents in Tract G has been protected.

14. Withdrawn

Deviations 15-19 are newly requested in the RPD/CPD amendment application.

15. **Open Space – Western 15.76± acres of Tract M.** Deviation 15 seeks relief from LDC §10-415 to allow navigable waterways within the boundary to be excluded from the required open space calculations and to allow preservation of existing mangroves to meet indigenous requirement.

HEX Recommendation: Approve, SUBJECT TO Condition 35.

16. **Plant Installation - Western 15.76± acres of Tract M.** Deviation 16 seeks relief from LDC §10-421(a)(8) which requires buffer plantings be installed on the exterior side of the wall/fence, to allow the decorative fence to be outside the existing buffer along Moody Road.

HEX Recommendation: Approve

17. **Buffers - Western 15.76± acres of Tract M.** Deviation 17 seeks relief from LDC §10-416(d) which requires a type C/F buffer when commercial abuts residential and a 30' buffer when commercial abuts a public preserve, to allow the following buffers shown on the MCP:
- North property line - allow the existing type B buffer to remain;
 - East property line - allow existing indigenous trees within the 330-foot eagle nest zone and Type C/F buffer outside 330-foot eagle nest zone; and
 - South property line - allow existing indigenous trees within the 330-foot eagle nest zone with 10-foot tree planting area outside the 330-foot zone and proposed 30-foot buffer between 330-foot eagle nest zone and 660-foot eagle nest zone to serve as the preserve buffer.

HEX Recommendation: Approve SUBJECT TO Condition 34.

18. **Parking Spaces – Western 15.76± acres of Tract M.** Deviation 18 seeks relief from LDC §34-2020(b) which requires 1 parking space per 350 square feet of social services, Group I office uses, and 1 parking space for every 2 boat slips, to allow a 10 percent reduction in required parking pursuant to LDC §34-2020(c)(2).

HEX Recommendation: Approve

19. **Single Access - Western 15.76± acres of Tract M.** Deviation 19 seeks relief from LDC §10-291(3) which requires commercial developments more than ten acres to provide more than one means of ingress/egress, to allow the previously approved/constructed single access.

HEX Recommendation: Approve SUBJECT TO Condition 36.

20. Withdrawn

21. **Sign.** Deviation 21 (ADD2012-00058) seeks relief from LDC §30-152(2)c.1. requiring 15-foot setback from right of way and five feet from edge of pavement of entrance and exit lanes for signs, to allow the internal subdivision sign three feet from the entrance lane.


HEX Recommendation: Approve

22. **Easement.** Deviation 22 (ADD2014-00053) seeks relief from LDC §10-328(a) restricting any portion of required maintenance easement area within the limits of a platted single-family residential lot, to allow the existing platted lake maintenance easement to remain within the single family lots in Tracts A and G, Moody River Estate, Unit Four.

HEX Recommendation: Approve SUBJECT TO Condition 37.

Exhibits to Conditions:

- B1 MCP "Home Front Heroes Minor CPD" dated 2/06/2025
- B2 Lee County Extension Services brochure Lee 8/2000A
- B3 Bona Fide Agricultural Uses
- B4 Bald Eagle Management Plan dated October 2024
- B5 Minimum Building Separation Drawing



SITE AREA:	
MAIN LAND PARCEL:	8.77± AC
ISLAND CONSERVATION EASEMENT:	1.12± AC
MAN-MADE BASIN:	0.89± AC
TOTAL SITE AREA FOR OPEN SPACE:	10.78± AC
ZONING BOUNDARY INCLUDES 4.98± AC OF HANCOCK CREEK FOR A TOTAL ZONING BOUNDARY OF 15.76± AC	
OPEN SPACE TABLE:	
10.78± AC X 30% =	3.23± AC OPEN SPACE REQUIRED
50% INDIGENOUS:	1.62± AC INDIGENOUS OPEN SPACE REQUIRED
INDIGENOUS OPEN SPACE PROVIDED:	1.12± AC TOTAL EXISTING INDIGENOUS WETLAND ON SITE WILL BE PRESERVED*
OTHER OPEN SPACE PROVIDED:	2.41± AC (MINIMUM 2.11 AC)
EXISTING MAN MADE BASIN 0.89± AC - 0.26 AC VEGETATION (MAXIMUM 25% OF OPEN SPACE AREA):	= 0.63± AC
EXISTING BOAT RAMP OPEN SPACE:	= 0.45± AC
BUFFER AREAS:	= 0.54± AC
DRY DETENTION AREAS:	= 0.78± AC
NON-INDIGENOUS WETLANDS PRESERVED ON SITE:	= 0.26± AC (0.29± AC)**
** 0.03± AC DOES NOT MEET OPEN SPACE DIMENSIONS & 0.41± AC ADDITIONAL NON-INDIGENOUS WETLAND WITHIN CREEK NOT INCLUDED	
TOTAL OPEN SPACE PROVIDED:	3.78± AC (MINIMUM 3.23 AC)

PREPARED FOR:
HOME FRONT HEROES INC.

14750 SIX MILE CYPRESS PARKWAY
FORT MYERS, FL 33912

ALL ELEVATIONS ON CIVIL ENGINEERING PLANS REFERENCE: NAVD 1988			
03	2-04-2025	POST SUFFICIENCY SUBMITTAL	R/V
02	9-16-2024	INSUFFICIENCY RESPONSE	R/V
01	08-01-24	INSUFFICIENCY RESPONSE	XG
NO.	DATE	REVISION DESCRIPTION	BY

BANKS
ENGINEERING
Professional Engineers, Planners, & Land Surveyors
Serving The State Of Florida

10511 SIX MILE CYPRESS PKWY, STE. 101
FORT MYERS, FLORIDA 33906
PHONE: (239) 939-5490 FAX: (239) 939-2523
ENGINEERING LICENSE # EB 6469
SURVEY LICENSE # LB 6690
WWW.BANKSENG.COM

CONCEPTUAL OPEN SPACE EXHIBIT
HOME FRONT HEROES MINOR CPD
LEE COUNTY, FLORIDA

COMPLETION DATE:	PROJECT:	DRAFTED BY:	DESIGNED BY:	REVIEWED BY:	SCALE:	SHEET:
05-08-2024	2506HFI	KG	KG	SWM	AS NOTED	01



UNIVERSITY OF
FLORIDALEE COUNTY
EXTENSION
SERVICE

Horticulture

TRANSPLANTING SABAL PALMS Step-by-Step Instructions

Lee 8/2000A

Stephen H. Brown
Lee County Horticulture Agent

Rick Joyce
Deputy Director, Lee County Planning Division

Introduction

The native cabbage or sabal palm (*Sabal palmetto*) is the official state tree of Florida and is a prominent feature in Florida's landscape. The palm is highly adaptive, tough, tolerant of a wide range of soils, and is hurricane resistant. When planted six to ten feet on center, sabal palms provide desirable shade. Sabal palms, including large-sized palms, can be transplanted with high success if a few simple precautions are taken. This fact sheet provides specific proven techniques to increase the success of sabal palm transplanting.

Step-by-Step Transplant Instructions

1. Use gasoline powered tree spade or heavy steel shanked digging spade with a clean well-honed cutting edge to dig the largest possible root ball. Usually to 18 inches from the edge of the trunk.
2. Remove the palm from ground. Take care not to damage the hidden bud located within the center of the canopy.
3. Using clean sharp hand spades, trim the root ball into circular shape 13 to 16 inches from the outer edge of the trunk.
4. Two methods of pruning fronds for landscape transplant (select one):
 - a. Remove oldest (brown) fronds. Tie the remaining fronds tightly together with a biodegradable twine. Do not disturb the bud.
 - b. Remove all fronds otherwise known as "hurricane" or "cigar cut." This recommended pruning technique gives the highest rate of establishment but must be carefully done.
5. Secure the palm on a flat bed truck and transport it to the planting site. Make sure the center of the bud is well protected.
6. Keep the root ball moist between removal and installation.
7. Prepare planting hole 1-2 times the diameter of the trunk but at the same depth as the root ball.
8. Back-fill the planting hole with the same soil that had been removed. There is no need to amend the planting hole, but if it is amended, use a fill similar to that of the planting hole. The amendment should not exceed 25 percent by volume of the soil removed from the hole.
9. Carefully set the palm into the planting hole. Make sure it is planted the same depth as it was in the field. Planting too deeply will cause root suffocation and lead to nutritional deficiencies, root rot, and frequently the death of the palm...
10. Secure and stake the palm as illustrated in the diagram. DO NOT DRIVE NAILS DIRECTLY INTO THE PALM.

(Continued on the back.)


The Extension Service is part of a publicly funded statewide educational network that provides information and scientific knowledge to area residents, businesses and government leaders. The University of Florida, Extension Service offers the latest research and technology in more than 200 subjects related to horticulture, energy/conservation, agriculture, youth development and family and consumer sciences. Last year, the Lee County Extension Service provided assistance to more than 70,000 people and provided 463 classes and workshops on everything from family financial planning to pesticide training.

The Lee County Extension Service is an Equal Employment Opportunity - Affirmative Action Employer that provides research, educational information and other services without regard to race, color, sex, age, handicap or national origin.

11. Establish a water-retaining ring around the palm three feet from the trunk. The ring should slope gently toward the trunk.
12. Fill the ring with mulch to a depth of three inches. Keep the mulch at least three inches away from the trunk.
13. Irrigation:
 - a. Palms with fronds remaining: Fill the ring with 50 gallons of water three times weekly.
 - b. Palms with hurricane cut: Fill the ring with 20 to 25 gallons of water three times weekly.
14. In both cases, after four weeks, reduce irrigation to twice weekly. Water twice weekly for four weeks, and then reduce irrigation to once weekly for an additional four weeks. Twelve weeks after planting, cease irrigation if the palm appears

healthy. However, during drought, water once a week for up to two years. For each inch of rain, skip one scheduled irrigation treatment.

15. As soon as new growth begins to appear, loosen tied fronds. This will happen between 3-6 months after transplanting, depending on the time of year and the health of the palm.
16. Begin fertilization after new growth begins. Fertilize three to four times per year with a 2-1-3-ratio fertilizer at a rate of one to two pounds per 100 square feet. For best results use a slow release formulation.
17. Remove staking and burlap or asphalt paper rap after successful palm establishment. Removal usually occurs approximately one year after palm installation.



PLANTING AND STAKING SABAL PALM

NOT TO SCALE

AFFIDAVIT

RECEIVED

MAY 21 2003

STATE OF FLORIDA)
COUNTY OF LEE)COMMUNITY DEVELOPMENT
DCI 2002-00037

BEFORE ME, the undersigned authority, on this 20th day of May, 2003, personally appeared Anthony Persichilli who is personally known to me and who did take an oath, who deposes and says as follows:

1. That I am the owner of the following described property, to wit:
See attached Exhibit "A"
Parcel No. 09-44-24-00-01002.1010
2. That the above described property was used for bona fide agricultural purposes, to with cattle grazing at the time of the Lee County Board of County Commissioners review and consideration of the rezoning of the property described on the attached Exhibit "A" scheduled to be heard on May 22, 2003.
3. The agricultural use of the property is an existing bona fide agricultural use.
4. The agricultural use is being conducted on 23.84 acres. The 23.84 acres of the total 45.84 acres as described on the attached Exhibit "A" is being used for cattle grazing.
5. Affiant further states that he is familiar with the nature of an oath; and with the penalties as provided by the laws of the State of aforesaid for falsely swearing to statements made in an instrument of this nature. Affiant further certifies that he has read, or has heard read to him, the full facts of this affidavit and understands its meaning and context.


FURTHER AFFIANT SAYETH NAUGHT.


Colonial Homes
By Anthony Persichilli
Its Division President

SWORN TO and subscribed before me on the date and year first above written.

(Notary Seal)





Signature of Notary

Commission No.

(Print, type or stamp commissioned name
of Notary Public)

Exhibit "G"

Page 1 of 4



Ag: 23.84



MKT: 22.80

RECEIVED

MAY 21 2003

COMMUNITY DEVELOPMENT

DU 2002-00037

<http://gis.lecpa.org/service/com.esri.esrimap.Esrimap?ServiceName=msLeePAInternet&Cl...> 5/25/2003

Exhibit "C"

Page 2 of 4

AFFIDAVIT

RECEIVED

MAY 21 2003

DCI 2002-00037
COMMUNITY DEVELOPMENT

STATE OF FLORIDA)
COUNTY OF LEE)

BEFORE ME, the undersigned authority, on this 20th day of May, 2003 personally appeared Anthony Persichilli who is personally known to me and who did take an oath, who deposes and says as follows:


1. That I am the owner of the following described property, to wit:
See attached Exhibit "A"
Parcel No. 10-44-24-00-01054.0000
2. That the above described property was used for bona fide agricultural purposes, to with cattle grazing at the time of the Lee County Board of County Commissioners review and consideration of the rezoning of the property described on the attached Exhibit "A" scheduled to be heard on May 22, 2003.
3. The agricultural use of the property is an existing bona fide agricultural use.
4. The agricultural use is being conducted on 119.56 acres. The 119.56 acres of the total 177.49 acres as described on the attached Exhibit "A" is being used for cattle grazing.
5. Affiant further states that he is familiar with the nature of an oath; and with the penalties as provided by the laws of the State of aforesaid for falsely swearing to statements made in an instrument of this nature. Affiant further certifies that he has read, or has heard read to him, the full facts of this affidavit and understands its meaning and context.


FURTHER AFFIANT SAYETH NAUGHT.


Colonial Homes
By Anthony Persichilli
Its Division President

SWORN TO and subscribed before me on the date and year first above written.

(Notary Seal)





Signature of Notary

Commission No.

(Print, type or stamp commissioned name
of Notary Public)

Exhibit "G"



AG: 119.56 Ac.

MKT: 57.93 Ac.

RECEIVED

MAY 21 2003

COMMUNITY DEVELOPMENT

DCI 2002-00037

<http://gis.lecpa.org/service/com.esri.csr/map.Esr/map?ServiceName=msLeePAInternet&Cl...> 5/25/2003

HOME FRONT HEROES

**BALD EAGLE (*HALIAEETUS LEUCOCEPHALUS*)
MANAGEMENT PLAN**

Lee County STRAP #'s: 10-44-24-00-00047.0000, 10-44-24-00-01046.0000, 10-44-24-00-00047.0010, 10-44-24-00-00047.0020, 10-44-24-00-00047.0030, & 10-44-24-00-00046.0010

October 2024

Prepared For:

Banks Engineering
Stacy Hewitt – Director of Planning
10511 Six Mile Cypress Parkway
Fort Myers, Florida 33966
Phone: 239-939-5490
E-Mail: shewitt@bankseng.com

Prepared By:



BearPaws Environmental Consulting
1599 Covington Circle East
Phone: (239) 340-0678
Email: BearPaws.Env.Consulting@GMail.com

Introduction

The 15.76± Home Front Heroes property is located at 884 Moody Road, in a portion of Section 10, Township 44S, and Range 24E, of Lee County, Florida. More specifically, the site is located south of Hancock Bridge Parkway, east of Moody Road, and north of Skyline Drive, in North Fort Myers, Florida. Please see the attached Project Location Map (Exhibit A).

There is a bald eagle (*Haliaeetus leucocephalus*) nest located at 26.65551 N, 81.897032 W. The nest is located southeast of the property, just within 330 feet of the proposed site development. This bald eagle management plan is being proposed to be approved for the LE-43D nest by Lee County, as a portion of the proposed project will be within the 330-foot and 660-foot eagle buffer zone. This management plan has been created to outline the project's proposed protection measures for Nest LE-43D. The MCP showing the 330-foot and 660-foot buffer zones is included as Exhibit B.

Site Conditions

The Home Front Heroes property consists of a marina, open and developed land, which has been used by the Fort Myers Sailing Club in the past. This disturbed upland herbaceous area is vegetated primarily by uplands, which encompasses a majority of the property. The canopy is mostly open with scattered slash pine (*Pinus elliottii*), melaleuca (*Melaleuca quinquenervia*), live oak (*Quercus virginiana*), and earleaf acacia (*Acacia auriculiformis*). The sub-canopy is also mostly open with widely scattered cabbage palm (*Sabal palmetto*), Brazilian pepper (*Schinus terebinthifolius*), and wax myrtle (*Myrica cerifera*). The groundcover contained mostly disturbed opportunistic weedy species. There are some scattered red mangroves (*Rhizophora mangle*), located along the edges of the herbaceous community; however, they were beyond the mean high-water line, within the FLUCFCS 540 - Bays & Estuaries. There is a large mangrove swamp (FLUCFCS 612) located off the "mainland property" on an island, but it's being proposed to be preserve, which is dominated by red mangroves (*Rhizophora mangle*), with widely scattered slash pine (*Pinus elliottii*), melaleuca (*Melaleuca quinquenervia*), Brazilian pepper (*Schinus terebinthifolius*), and cabbage palm (*Sabal palmetto*). The property on which Nest LE-43D is located consists of undeveloped vacant land and forested land.

Site Observations

A bald eagle (*Haliaeetus leucocephalus*) constructed a nest (LE-43D) in a slash pine (*Pinus elliottii*) tree located approximately 320 feet southeast of the southern property line and approximately 970 feet east of Moody Road. The nest was active during the 2023-2024; however, it was declared unsuccessful for the 2023 nesting season and is believed to be unsuccessful for the 2024 nesting season. Nest LE-43D was a new nest, which was initially reported in July 2022; the nest was destroyed during Hurricane Ian, but reconstructed afterward, but the fledglings were never confirmed.

There have been four vegetation associations that were identified using the Florida Land Use, Cover and Forms Classification System (FLUCFCS). Figure 2 depicts the approximate location and configuration of these vegetation associations and Table 1 summarizes the acreages by FLUCFCS Code. A brief description of each FLUCFCS Community is also provided below.

FLUCFCS Codes & Community Descriptions

Uplands

The following community areas have been designated as upland habitats. Uplands are any area that does not qualify as a wetland because the associated hydrologic regime is not sufficiently wet enough to elicit development of vegetation, soils, and/or hydrologic characteristics associated with wetlands.

FLUCFCS 140 Commercial – 1.41± Acres

This commercial property has been previously cleared and developed and is comprised of a paved parking lot, concrete pads, portable trailers, and a boat ramp. This community occupies approximately 1.41± acres of the site. This community would be considered uplands by regulatory agencies.

FLUCFCS 400 E2 Planted Landscape Buffers (Exotics 25-49%) – 0.36± Acres

This upland community type occupies approximately 0.36± acres of the property and is located along the right-of-way. This community was planted as part of the previously approved development order's issues for this property. Exotic species such as earleaf acacia (*Acacia auriculiformis*), melaleuca (*Melaleuca quinquenervia*), mimosa (*Albizia julibrissin*), and Brazilian pepper (*Schinus terebinthifolius*) occupy approximately 25-49% of this community. The canopy contains melaleuca (*Melaleuca quinquenervia*) with scattered earleaf acacia (*Acacia auriculiformis*), mimosa (*Albizia julibrissin*), slash pine (*Pinus elliotii*), and live oak (*Quercus virginiana*). The sub-canopy contains scattered cabbage palm (*Sabal palmetto*) and Brazilian pepper (*Schinus terebinthifolius*). The ground cover is mostly open, but contains scattered various opportunistic weedy species. Commonly observed vines include greenbriar (*Smilax sp.*), and grapevine (*Vitis rotundifolia*). This community would be considered uplands by the regulatory agencies.

FLUCFCS 420 E4 Mixed Forest Mixed (Exotics > 75%) – 0.13± Acres

This upland community type occupies approximately 0.13± acres of the property. Exotic species such as earleaf acacia (*Acacia auriculiformis*), mimosa (*Albizia julibrissin*), and Brazilian pepper (*Schinus terebinthifolius*) occupy approximately 75-99% of this community. The canopy is dominated by melaleuca (*Melaleuca quinquenervia*) with scattered earleaf acacia (*Acacia auriculiformis*), mimosa (*Albizia julibrissin*), slash pine (*Pinus elliotii*), and live oak (*Quercus virginiana*). The sub-canopy contains scattered cabbage palm (*Sabal palmetto*) and Brazilian pepper (*Schinus terebinthifolius*). The ground cover is mostly open, due to the dense exotic coverage, but contains scattered various opportunistic weedy species. Commonly observed vines include greenbriar (*Smilax sp.*), and grapevine (*Vitis rotundifolia*). This community would be considered uplands by the regulatory agencies.

FLUCFCS 740 Disturbed Lands – 6.80± Acres

This upland habitat type occupies a majority of the property and encompasses approximately 6.80± acres of the property. Exotic species such as earleaf acacia (*Acacia auriculiformis*), melaleuca (*Melaleuca quinquenervia*), mimosa (*Albizia julibrissin*), and Brazilian pepper (*Schinus terebinthifolius*) occupy approximately 50-74% of this community. The canopy is mostly open with scattered slash pine (*Pinus elliotii*), melaleuca (*Melaleuca quinquenervia*), live oak (*Quercus virginiana*), and earleaf acacia (*Acacia auriculiformis*). The sub-canopy is also mostly open with widely scattered cabbage palm (*Sabal palmetto*), Brazilian pepper (*Schinus terebinthifolius*), and wax myrtle (*Myrica cerifera*). The groundcover contained Spanish needle (*Bidens alba*), false buttonweed (*Spermacoce floridan*), caesar weed (*Urena lobata*), dog fennel (*Eupatorium capillifolium*), ragweed (*Ambrosia artemisiifolia*), finger grass (*Eustachys floridana*), muhly grass (*Muhlenbergia capillaris*), broomsedge (*Andropogon virginicus*), and bahia grass (*Paspalum notatum*), with various other opportunistic weedy species. Commonly observed vines include air potato (*Dioscorea bulbifera*), greenbriar (*Smilax sp.*), grapevine (*Vitis rotundifolia*), Virginia creeper (*Parthenocissus quinquefolia*), creeping oxeye (*Sphagneticola trilobata*), peppervine (*Ampelopsis arborea*), and poison ivy (*Toxicodendron radicans*). This community would be considered uplands by regulatory agencies.

Other Surface Waters (OSW)

The following community area has been designated as other surface waters. Surface waters are waters on the surface of the earth, contained in bounds created naturally or artificially.

FLUCFCS 500 Man-Made Basin – 0.63± Acres

This man-made “other surface water” (OSW) community occupies approximately 0.63± acres of the property. This community was dug-out and created during the original permitting process and leads out to Hancock Creek, which runs out to the Caloosahatchee River. There are red mangroves (*Rhizophora mangle*), along the edges of this community. The depth varies from approximately a few inches along the edge to several feet deep in the middle. This community would be considered “other surface waters” by the regulatory agencies.

FLUCFCS 540 Bays & Estuaries – 4.13± Acres

This “other surface water” (OSW) community occupies approximately 4.13± acres of the property. This community includes a boat ramp and Hancock Creek that runs out to the Caloosahatchee River. There are red mangroves (*Rhizophora mangle*), along the sides of the canal. The depth varies from approximately a few inches along the edge to several feet deep in the middle. This community would be considered “other surface waters” by the regulatory agencies.

Wetlands

The following community areas have been designated as wetland habitats. Wetlands are any areas that under normal circumstances have hydrophytic vegetation, hydric soils, and wetland hydrology.

FLUCFCS 612 E3 Mangrove Wetlands (Exotics 50-74%) – 1.60± Acres

This wetland community type occupies approximately 1.60± acres of the property. Exotic species such as (*Melaleuca quinquenervia*) and Brazilian pepper (*Schinus terebinthifolius*) occupy approximately 50-74% of this community. The canopy contains red mangrove (*Rhizophora mangle*), and buttonwood (*Conocarpus erectus*) with scattered slash pine (*Pinus elliotii*), and melaleuca (*Melaleuca quinquenervia*). The sub-canopy contains cabbage palm (*Sabal palmetto*), Brazilian pepper (*Schinus terebinthifolius*), seaside mahoe (*Thespesia populnea*), sea grape (*Coccoloba uvifera*), and pond apple (*Annona glabra*). The ground cover is mostly open with giant leather fern (*Acrostichum daneifolium*), and coin vine (*Dalbergia ecastaphyllum*). This community does contain wetland vegetation, advantageous rooting, water line staining, and algal matting, as well as other signs in this community that would be classified as wetlands. This community would be considered wetlands by the regulatory agencies.

FLUCFCS 612 E4 Mangrove Wetlands (Exotics > 75%) – 0.70± Acres

This wetland community type occupies approximately 0.70± acres of the property. Exotic species such as (*Melaleuca quinquenervia*) and Brazilian pepper (*Schinus terebinthifolius*) occupy approximately greater than 75% of this community. The canopy contains red mangrove (*Rhizophora mangle*), and buttonwood (*Conocarpus erectus*) with scattered slash pine (*Pinus elliotii*), and melaleuca (*Melaleuca quinquenervia*). The sub-canopy contains cabbage palm (*Sabal palmetto*), Brazilian pepper (*Schinus terebinthifolius*), seaside mahoe (*Thespesia populnea*), sea grape (*Coccoloba uvifera*), and pond apple (*Annona glabra*). The ground cover is mostly open with giant leather fern (*Acrostichum daneifolium*), and coin vine (*Dalbergia ecastaphyllum*). This community does contain wetland vegetation, advantageous rooting, water line staining, and algal matting, as well as other signs in this community that would be classified as wetlands. This community was located along the edge of the disturbed lands with a majority located beyond the mean high-water line but were still included as part of this community. This community would be considered wetlands by the regulatory agencies.

Table 1. FLUCFCS Community Table

FLUCFCS Code	Community Description	Habitat Type	Acreage
140	Commercial, Parking, & Boat Ramp	Upland	1.41± Ac.
400 E2	Planted Landscape Buffers (Exotics 25-49%)	Upland	0.36± Ac.
420 E4	Upland Forest Mixed (Exotics > 75%)	Upland	0.13± Ac.
500	Man-Made Basin	OSW	0.63± Ac.
540	Bays & Estuaries	OSW	4.13± Ac.
612 E3	Mangrove Wetlands (Exotics 50-74%)	Wetland	1.60± Ac.
612 E4	Mangrove Wetlands (Exotics > 75%)	Wetland	0.70± Ac.
740	Disturbed Lands	Upland	6.80± Ac.
Total			15.76± Ac.

General Development Guidelines

The protection measures outlined below have been designed utilizing the FWS's *National Bald Eagle Management Guidelines* (FWS 2007a) and Section 14-111 through 14-120 of the Lee County Land Development Code. These proposed restrictions and requirements apply only to the Homefront Heroes project and are not binding on any other property in the vicinity of Bald Eagle Nest LE-43D.

If Nest LE-43D is vacated before the end of the nesting season (May 15th) or if Lee County Division of Environmental Sciences (DES) determines that Nest LE-43D has been abandoned, construction activities may commence upon confirmation of those conditions by DES. If the nest is not active by March 15th or as confirmed by DES, then the nesting season for Nest LE-43D shall be considered over and the construction restrictions shall not apply. A determination that the nest is not active shall be consistent with the *Bald Eagle Monitoring Guidelines* (FWS 2007b).

330 Feet Zone Activities and Restrictions

A very small portion of the project parcel is located just inside of the 330' LE-43D nesting buffer. There is no work proposed within the 330' buffer zone. All work, including the installation of the type "C" or "F" buffer and creation of the dry detention has been relocated to outside of the buffer zone. There will be no buildings or roadways proposed within this buffer zone.

330 - 660 Feet Zone Activities and Restrictions

A portion of the property is located within the 660' buffer of Nest LE-43D. The project will include the installation of the dry detention area and the installation of the type "C" or "F" buffer along the 330' zone. Additionally, other construction proposed within the 660' buffer will include driveways, multi-purpose outdoor recreation area, and private multi-slip docking, within the 660' zone.

The restrictions described below are only applicable to the portion of the property within 660' of Nest LE-43D. All construction activities within the 660' buffer zone shall only be conducted during the non-nesting season (i.e., May 6th - September 30th) without a monitor, and when the nest is not actively being used for nesting; otherwise, a monitor will be required to be present.

- Major exterior construction activities, such as initial site clearing, major earthwork, grading, drive isles construction, and access road construction may occur during the nesting season, provided that the activities do not disturb the nesting bald eagles, as defined by the Bald Eagle Monitoring Guidelines.

- The use of any chemicals that are known to be toxic to wildlife shall be prohibited within 660± feet of the bald eagle nest. The use of all chemicals will be in accordance with labeling instructions.
- Outdoor lighting installed within 660± feet of the bald eagle nest shall be subdued, shielded, and directed away from the nest tree.
- Native slash pine and live oak trees will be installed along the southern property boundary, outside of the 330' buffer zone, to provide a visual buffer between development and eagle nest. Trees planted will be a minimum of 6-foot in height and 25-gallon container size at time of insulation and planted on 20-foot center. The trees will be included on the landscape plans and with the development order that's required for the site development. The visual vegetation buffer installation will occur outside of nesting season, since a portion of the property lies within 330-foot zone of the bald eagle nest.

Greater Than 660 Feet Zone Activities and Restrictions

The proposed uses of the property more than 660-feet of Bald Eagle Nest LE-43D consist of the construction of a future commercial building, caretakers' residences, parking, infrastructure, and outdoor recreation area. Construction activities and normal activities will be allowed outside of 660± feet of the bald eagle nest throughout the year.

Implementation

The landowner and/or developer will be responsible for following this Bald Eagle Management Plan. There is no work proposed within the 330' buffer zone of the bald eagle nest. Coordination has been made with Ms. Ulgonda Kirkpatrick of USFWS via email on September 24, 2024. The FWS stated that the project appears to be fairly low risk to the eagles, particularly given the proposed buffer. The monitoring guidelines and disturbance avoidance should not be necessary for this site; therefore, the applicant will not be obtaining a take permit from USFWS as a majority of the property is located outside of the 330-foot buffer zone and any proposed work has been relocated to outside of the 330' buffer zone. There will be limited work proposed within the 660' buffer zone during nesting season, provided that the activities do not disturb the nesting bald eagles as defined by the Bald Eagle Monitoring Guidelines.

A qualified ecologist will monitor Nest LE-43D consistent with the *Bald Eagle Monitoring Guidelines* and will submit the reports to DES on a monthly basis during nesting season. DE staff will review these reports and may also inspect the site to verify compliance with the conditions of this Bald Eagle Management Plan. Any violation of these conditions may result in a "Stop Work Order" being issued to halt all construction activity during the bald eagle nesting season, including building inspections, until the violation is resolved.

All of the management practices will remain in effect until the nest is deemed abandoned or lost by DES pursuant to Section 14-112 of the Land Development Code. None of these management practices will be required after the nest is deemed abandoned or lost. The nest will be defined as abandoned if the nest is intact or partially intact but has been inactive through five or more consecutive nesting seasons. The nest will be defined as lost if the nest or nest tree is destroyed by natural causes (e.g. nest that fell apart or was blown out of a tree, or the tree itself was lost) and is not rebuilt in the same tree within three nesting seasons.

Bald Eagle Management Plan Modifications



Any changes to this Bald Eagle Management Plan must be reviewed and approved by Lee County Division of Environmental Sciences staff through the planned development administrative amendment process.

References

- Florida Fish and Wildlife Conservation Commission. 2008. Bald Eagle Management Plan. 60p.
- Florida Fish and Wildlife Conservation Commission. 2017. Historical Bald Eagle Nesting Areas.
- U.S. Fish and Wildlife Service. 2007a. National Bald Eagle Management Guidelines. 23p.
- U.S. Fish and Wildlife Service. 2007b. Bald Eagle Monitoring Guidelines. 20p.

EXHIBIT A

Project Location Map



DRAWN BY:	DATE:	CATEGORY:
BWS	3/12/24	LOCATION
JOB NUMBER		SCALE:
S/T/R		NTS
10/44S/24E		COUNTY
		LEE

Home Front Heroes (Moody Road)

Location Map



PAGE

EXHIBIT

EXHIBIT B

Aerial FLUCFCS Map




EXHIBIT C

Protected Species Survey Map with Bald Eagle Buffer Zones





EXHIBIT D

Master Concept Plan



LEGEND:

- LIMITS OF CONSTRUCTION
- APPROXIMATE LOCATION OF DRY DETENTION AREAS
- WETLAND PRESERVE (INDIGENOUS 1.124 AC, ADDITIONAL 0.846 AC INDIGENOUS WETLAND WITHIN CREEK)
- WETLAND PRESERVE (NON-INDIGENOUS 0.291 AC, ADDITIONAL 0.841 AC NON-INDIGENOUS WETLAND WITHIN CREEK)
- Δ DEVIATION



SITE AREA:

MAIN LAND PARCEL	8.774 AC
ISLAND CONCENTRATION (AS SHOWN)	1.124 AC
MAN-MADE BASIN	0.894 AC
TOTAL SITE AREA FOR OPEN SPACE:	10.792 AC

ZONING BOUNDARY INCLUDES 4.894 AC OF HANCOCK CREEK FOR A TOTAL ZONING BOUNDARY OF 15.786 AC

OPEN SPACE TABLE:

15.786 AC AT 2.5% = 3.946 AC OPEN SPACE REQUIRED	Δ
1.824 AC INDIGENOUS OPEN SPACE REQUIRED	
1.124 AC TOTAL EXISTING INDIGENOUS WETLAND ON SITE WILL BE PRESERVED	
ADDITIONAL 0.846 AC INDIGENOUS WETLAND WITHIN CREEK NOT INCLUDED	
OTHER OPEN SPACE PROVIDED	
TOTAL OPEN SPACE PROVIDED:	MINIMUM 2.111 AC

- NOTES:**
- EXISTING ZONING: MOODY RIVER CITIES RPD (205-048) TRACT M. MAXIMUM 200 DWELLING UNITS WITH MAXIMUM HEIGHT OF 75 FEET, BOAT RAMP AND MULTI-SLIP DOCKING FACILITY
 - SUBJECT PROPERTY IS A WESTERN 15.786 AC OF TRACT M (10.786 AC WITHOUT HANCOCK CREEK)
 - PARCEL 10-44-24-004-004-0000 EASTERN 3.024 AC OF TRACT M NOT INCLUDED IN REQUEST
 - REQUEST TO AMEND EXISTING RPD/CPD TO REZONE WESTERN 15.786 AC OF TRACT M FROM RPD TO REPLACE PREVIOUSLY APPROVED RESIDENTIAL WITH HOME FRONT HEROES MINOR COMMERCIAL PLANNED DEVELOPMENT TO ALLOW A MAXIMUM 50,000 SF OF COMMERCIAL USE INCLUDING UP TO 4 CARETAKER'S RESIDENCES WITH ACCESSORY MULTI-PURPOSE OUTDOOR RECREATION AREA, EXISTING BOAT RAMPS AND PRIVATE MULTI-SLIP DOCKING FACILITY WITH MAXIMUM 20 SLIPS (10 WET AND 10 BOAT TRAILER PARKING), WITH A MAXIMUM HEIGHT OF 45'
 - SEE PHASING PLAN
 - SHARED FACILITIES WITH OTHER HOME FRONT HEROES

PROVIDED FOR: **HOME FRONT HEROES INC.**

14790 338 CYPRESS PARKWAY
FORT MYERS, FL 33912

ALL ELEVATIONS IN CIVIL ENGINEERING PLANS REFERENCED TO NAVD 83

NO.	DATE	DESCRIPTION	BY	CHK
1	10/24/2023	PROPOSED	JB	JB
2	10/24/2023	PROPOSED	JB	JB
3	10/24/2023	PROPOSED	JB	JB
4	10/24/2023	PROPOSED	JB	JB
5	10/24/2023	PROPOSED	JB	JB
6	10/24/2023	PROPOSED	JB	JB
7	10/24/2023	PROPOSED	JB	JB
8	10/24/2023	PROPOSED	JB	JB
9	10/24/2023	PROPOSED	JB	JB
10	10/24/2023	PROPOSED	JB	JB
11	10/24/2023	PROPOSED	JB	JB
12	10/24/2023	PROPOSED	JB	JB
13	10/24/2023	PROPOSED	JB	JB
14	10/24/2023	PROPOSED	JB	JB
15	10/24/2023	PROPOSED	JB	JB
16	10/24/2023	PROPOSED	JB	JB
17	10/24/2023	PROPOSED	JB	JB
18	10/24/2023	PROPOSED	JB	JB
19	10/24/2023	PROPOSED	JB	JB
20	10/24/2023	PROPOSED	JB	JB
21	10/24/2023	PROPOSED	JB	JB
22	10/24/2023	PROPOSED	JB	JB
23	10/24/2023	PROPOSED	JB	JB
24	10/24/2023	PROPOSED	JB	JB
25	10/24/2023	PROPOSED	JB	JB
26	10/24/2023	PROPOSED	JB	JB
27	10/24/2023	PROPOSED	JB	JB
28	10/24/2023	PROPOSED	JB	JB
29	10/24/2023	PROPOSED	JB	JB
30	10/24/2023	PROPOSED	JB	JB
31	10/24/2023	PROPOSED	JB	JB
32	10/24/2023	PROPOSED	JB	JB
33	10/24/2023	PROPOSED	JB	JB
34	10/24/2023	PROPOSED	JB	JB
35	10/24/2023	PROPOSED	JB	JB
36	10/24/2023	PROPOSED	JB	JB
37	10/24/2023	PROPOSED	JB	JB
38	10/24/2023	PROPOSED	JB	JB
39	10/24/2023	PROPOSED	JB	JB
40	10/24/2023	PROPOSED	JB	JB
41	10/24/2023	PROPOSED	JB	JB
42	10/24/2023	PROPOSED	JB	JB
43	10/24/2023	PROPOSED	JB	JB
44	10/24/2023	PROPOSED	JB	JB
45	10/24/2023	PROPOSED	JB	JB
46	10/24/2023	PROPOSED	JB	JB
47	10/24/2023	PROPOSED	JB	JB
48	10/24/2023	PROPOSED	JB	JB
49	10/24/2023	PROPOSED	JB	JB
50	10/24/2023	PROPOSED	JB	JB
51	10/24/2023	PROPOSED	JB	JB
52	10/24/2023	PROPOSED	JB	JB
53	10/24/2023	PROPOSED	JB	JB
54	10/24/2023	PROPOSED	JB	JB
55	10/24/2023	PROPOSED	JB	JB
56	10/24/2023	PROPOSED	JB	JB
57	10/24/2023	PROPOSED	JB	JB
58	10/24/2023	PROPOSED	JB	JB
59	10/24/2023	PROPOSED	JB	JB
60	10/24/2023	PROPOSED	JB	JB
61	10/24/2023	PROPOSED	JB	JB
62	10/24/2023	PROPOSED	JB	JB
63	10/24/2023	PROPOSED	JB	JB
64	10/24/2023	PROPOSED	JB	JB
65	10/24/2023	PROPOSED	JB	JB
66	10/24/2023	PROPOSED	JB	JB
67	10/24/2023	PROPOSED	JB	JB
68	10/24/2023	PROPOSED	JB	JB
69	10/24/2023	PROPOSED	JB	JB
70	10/24/2023	PROPOSED	JB	JB
71	10/24/2023	PROPOSED	JB	JB
72	10/24/2023	PROPOSED	JB	JB
73	10/24/2023	PROPOSED	JB	JB
74	10/24/2023	PROPOSED	JB	JB
75	10/24/2023	PROPOSED	JB	JB
76	10/24/2023	PROPOSED	JB	JB
77	10/24/2023	PROPOSED	JB	JB
78	10/24/2023	PROPOSED	JB	JB
79	10/24/2023	PROPOSED	JB	JB
80	10/24/2023	PROPOSED	JB	JB
81	10/24/2023	PROPOSED	JB	JB
82	10/24/2023	PROPOSED	JB	JB
83	10/24/2023	PROPOSED	JB	JB
84	10/24/2023	PROPOSED	JB	JB
85	10/24/2023	PROPOSED	JB	JB
86	10/24/2023	PROPOSED	JB	JB
87	10/24/2023	PROPOSED	JB	JB
88	10/24/2023	PROPOSED	JB	JB
89	10/24/2023	PROPOSED	JB	JB
90	10/24/2023	PROPOSED	JB	JB
91	10/24/2023	PROPOSED	JB	JB
92	10/24/2023	PROPOSED	JB	JB
93	10/24/2023	PROPOSED	JB	JB
94	10/24/2023	PROPOSED	JB	JB
95	10/24/2023	PROPOSED	JB	JB
96	10/24/2023	PROPOSED	JB	JB
97	10/24/2023	PROPOSED	JB	JB
98	10/24/2023	PROPOSED	JB	JB
99	10/24/2023	PROPOSED	JB	JB
100	10/24/2023	PROPOSED	JB	JB

BANKS ENGINEERING

Professional Engineer, Planner, & Land Surveyor
Surveying The State Of Florida

10311 326 MILE CYPRESS PARK, STE. 101
FORT MYERS, FLORIDA 33905
PHONE: (239) 338-1100 FAX: (239) 338-2223
ENGINEERING LICENSE # 03 8468
SURVEY LICENSE # LP 8890
WWW.BANKSENG.COM

MASTER CONCEPT PLAN

HOME FRONT HEROES MINOR CPD

LEE COUNTY, FLORIDA

COMPLETION DATE	PROJECT	DRAWN BY	DESIGNED BY	REVIEWED BY	SCALE	SHEET
10/24/2023	23060PH	JB	JB	JPM	AS NOTED	02 OF 02

5245 RAMSEY WAY, SUITE #2
FORT MYERS, FLORIDA 33907
PHONE: (239) 275-8575
FAX: (239) 275-8457



A TRACT OR PARCEL OF LAND SITUATED IN THE STATE OF FLORIDA, COUNTY OF LEE, BEING PART OF TRACT "E", MOODY RIVER ESTATES AS RECORDED IN PLAT BOOK 78, PAGES 80-87, PUBLIC RECORDS OF LEE COUNTY, FLORIDA, LYING IN SECTION 10, TOWNSHIP 44 SOUTH, RANGE 24 EAST, BEING FURTHER DESCRIBED AS FOLLOWS:

[illegible]

CONTAINING 124,132 SQUARE FEET OR 2.85 ACRES, MORE OR LESS

**SUBJECT TO EASEMENTS, RESTRICTIONS, RESERVATIONS AND RIGHTS-OF-WAY
(RECORDED AND UNRECORDED, WRITTEN AND UNWRITTEN)**

BEARINGS ARE BASED ON THE SOUTHERLY RIGHT-OF-WAY LINE OF HANCOCK BRIDGE PARKWAY BEING N.89°22'42"W.

1. SEAGARD ARE, BASED ON THE WEST LINE OF THE SOUTHWEST QUARTER SECTION LINE OF SECTION 13, TOWNSHIP 43 SOUTH, RANGE 25 EAST AS BEING NORTH 07°00'40" WEST. THE SEAGARD ARE IS MADE, INCLUDING BEARINGS AND DISTANCES ARE IDENTICAL WITH PLAT WALLS.

2. CONSIDERING ARE IN FEET AND DECIMALS THEREOF.

3. ABBREVIATIONS

R = RADIUS R = DELTA ANGLE A = ARC LENGTH

W = WATERSHED C = CHORD C = CHORD BEARING

P.L.C. = PERMANENT CONTROL POINT, P.L.C. = POINT OF BEGINNING

P.M.A. = PERMANENT ADJUSTMENT POINT, P.M.A. = POINT OF COMMENCEMENT

S/W = RIGHT-OF-WAY, P.U.L. = PUBLIC UTILITY EASEMENT, L.M. = LAKE MAINTENANCE EASEMENT

L.U. = UTILITY EASEMENT, D.C. = DRAINAGE DRAINAGE, C.A. = COMMON AREA

F.C. = FLOOD, H. = HIGHWAY, C.A. = COMMON AREA

U.C. = UNITED TELEPHONE COMPANY, C.A. = COMMON ELEMENT

P. = PLUG, H. = HIGHWAY

D.P.L. = DRAINAGE & PUBLIC UTILITY EASEMENT, S.F. = SQUARE FEET

F.M. = FLOOD, C.A. = COMMON AREA, D.C. = DRAINAGE

P.C. = POINT OF COMMENCEMENT

S.L. = SET 8/16" IRON ROD & CIP LHM 707

P.L.C. = PERMANENT CONTROL POINT

4. ALL IMPROVEMENTS SHOWN ARE PROPOSED EXCEPT TO THE EXTENT SUCH IMPROVEMENTS HAVE BEEN OFFERED AS BEING SUBSTANTIALLY COMPLETE, AND ARE BASED ON THE ABOVE

A CONDOMINIUM LYING IN
SECTION 10, TOWNSHIP 44 SOUTH, RANGE 24 EAST,
LEE COUNTY, FLORIDA
SITE PLAN /SURVEY

Line	Bearing	Distance
L1	S.89°22'43"E	81.2
L2	N.14°14'37"W	24.7
L3	S.14°14'37"E	54.7
L4	S.03°41'41"W	18.8

NO.	RADLE	DELTA	ARC	TANGENT	CHORD	CHORD BEARING
1	248.00	33.30 17	287.14	147.82	282.98	N.18°11'22"W.
2	415.00	49°03'38"	188.11	88.30	184.78	N.12°37'01"W.
3	60.00	24°08'38"	287.82	130.83	285.84	N.02°08'58"W.
4	110.00	8°04'25"	288.11	143.81	283.81	N.43°21'31"E.
5	460.00	34°04'38"	208.77	165.86	207.33	S.03°08'58"W.
6	305.00	49°03'38"	278.33	147.29	272.08	S.12°37'01"E.
7	348.00	38°00'41"	233.90	121.63	228.40	S.10°43'40"E.

MAP OF BOUNDARY SURVEY OF CARRIAGE HOMES BE AT MOODY RIVER ESTATES, BEING PART OF TRACT "E", MOODY RIVER ESTATES, AS RECORDED IN PLAT BOOK 79, PAGES 80-82 DEED 67, PUBLIC RECORDS OF LEE COUNTY, FLORIDA.

THIS BOUNDARY SURVEY MEETS THE MINIMUM TECHNICAL STANDARDS SET FORTH BY THE FLORIDA BOARD OF LAND SURVEYORS, PURSUANT TO SECTION 473.007, FLORIDA STATUTES AND CHAPTER 61017-8, FLORIDA ADMINISTRATIVE CODE. NO OTHER RECORD OR INSTRUMENT RELY UPON THIS SURVEY.

Aut. H. No. 50-22-0

CERTIFICATE OF AUTHORIZATION - JUNE 1997

NOT VALID WITHOUT THE SIGNATURE AND THE ORIGINAL PAPERED SIGNATURE OF A LICENSED SURVEYOR AND MAPPER

THIS BOUNDARY SURVEY IS ONLY FOR THE LANDS AS DESCRIBED. IT IS NOT A GUARANTEE OF TITLE, ZONING, EASEMENTS OR FREEDOM OF ENCUMBRANCES.

ABSTRACT NOT RECORDED.

ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED DATE 05-11-2010 BY 60322 UCBAW/ANM

REPRODUCTION OF THE


I HEREBY CERTIFY THAT THE PLAN OF CARIBBEA HOMES IS A SMOOBY HINDS LOCATED IN CONDOMINIUM CONSISTING OF THE FIVE PAGES TOGETHER WITH THE DECLARATION OF CONDOMINIUM FOR CARIBBEA HOMES. A SMOOBY HINDS ESTATE, ARE SUFFICIENT DETAILS TO IDENTIFY THE COMMON ELEMENTS AND SHOW LISTING THEIR RESPECTIVE LOCATIONS AND APPROXIMATE DIMENSIONS.

THE CONSTRUCTION OF THIS CONDOMINIUM IS NOT SUBSTANTIALLY COMPLETE.

100

Att. Th. H. 12-23-2005

SCOTT M. SHORE
PROFESSIONAL SURVEYOR AND MAPPER
FLORIDA CERTIFICATE No. 5743




THIS INSTRUMENT PREPARED BY:
METRON
SURVEYING & MAPPING, LLC
LAND SURVEYORS-PLANNERS
LBA 7071
5245 RAMSEY WAY, SUITE #2
FORT MYERS, FLORIDA 33907
PHONE: (239) 275-8575
FAX: (239) 275-8457

COACH HOMES V AT MOODY RIVER ESTATES

A CONDOMINIUM LYING IN
SECTION 10, TOWNSHIP 44 SOUTH, RANGE 24 EAST,
LEE COUNTY, FLORIDA
SITE PLAN / SURVEY

CURVE TABLE					
NO.	RADIUS	DELTA	ARC	TANGENT	CHORD
1	175.00'	36.534°	112.79'	38.43'	110.83'
2	350.00'	02:27:30"	02:27:30"	7.20'	13.00'
3	450.00'	02:27:48"	18.33'	9.87'	18.83'
4	320.00'	06:07:04"	45.34'	22.71'	45.30'
5	20.00'	06:37:48"	13.33'	22.04'	5.5844:20'
6	143.00'	87:18:00"	176.30'	160.72'	5.5844:20'
7	90.00'	23:27:54"	37.84'	18.10'	37.37'
8	55.00'	24:20:52"	24.62'	16.18'	31.5703:24'
9	90.00'	32:32:58"	83.07'	44.78'	80.15'
10	105.00'	40:30:02"	186.93'	106.11'	148.27'

LINE TABLE		
Line	Bearing	Distance
L1	NORTH	6.31'
L2	S.72°47'31"E.	83.46'



DESCRIPTION:
COACH HOMES V AT MOODY RIVER ESTATES

A TRACT OR PARCEL OF LAND SITUATED IN THE STATE OF FLORIDA, COUNTY OF LEE, LYING IN SECTION 10, TOWNSHIP 44 SOUTH, RANGE 24 EAST, BEING PART OF TRACT "MF-2" AND "MF-3", MOODY RIVER ESTATES UNIT TWO AS RECORDED IN PLAT BOOK 63, PAGES 14-16, BEING FURTHER DESCRIBED AS FOLLOWS:

BEGINNING AT THE SOUTHWEST CORNER OF SAID TRACT "MF-2"; THENCE S.89°23'58"W. FOR 101.70 FEET; THENCE N.83°57'48"W. FOR 100.00 FEET; THENCE S.89°23'58"W. FOR 284.02 FEET TO THE BEGINNING OF A CURVE TO THE RIGHT HAVING A RADIUS OF 175.00 FEET; THENCE ALONG THE ARC OF SAID CURVE THROUGH A CENTRAL ANGLE OF 36°53'42" FOR 112.79 FEET; THENCE N.83°40'20"W. FOR 136.47 FEET; THENCE N.82°03'40"W. FOR 124.13 FEET TO THE BEGINNING OF A CURVE TO THE LEFT HAVING A RADIUS OF 350.00 FEET; THENCE ALONG THE ARC OF SAID CURVE THROUGH A CENTRAL ANGLE OF 02°27'30" FOR 13.00 FEET; THENCE N.05°29'00"E. FOR 133.03 FEET TO THE POINT OF CURVE OF A NON-TANGENT CURVE TO THE RIGHT; OF WHICH THE RADIUS POINT LIES S.05°33'33"W. A RADIAL DISTANCE OF 480.00 FEET; THENCE EXISTING ALONG THE ARC THROUGH A CENTRAL ANGLE OF 02°27'48" FOR 18.33 FEET; THENCE S.82°03'40"E. FOR 163.83 FEET TO THE BEGINNING OF A CURVE TO THE LEFT HAVING A RADIUS OF 320.00 FEET; THENCE ALONG THE ARC OF SAID CURVE THROUGH A CENTRAL ANGLE OF 06°07'04" FOR 45.34 FEET TO A POINT OF REVERSE CURVE TO THE RIGHT HAVING A RADIUS OF 30.00 FEET AND A CENTRAL ANGLE OF 6°52'48"; THENCE SOUTHEASTERLY ALONG THE ARC FOR 23.33 FEET TO A POINT OF REVERSE CURVE TO THE LEFT HAVING A RADIUS OF 145.00 FEET AND A CENTRAL ANGLE OF 67°18'04"; THENCE SOUTHEASTERLY ALONG THE ARC FOR 170.32 FEET; THENCE N.89°23'58"E. FOR 270.80 FEET TO THE BEGINNING OF A CURVE TO THE RIGHT HAVING A RADIUS OF 30.00 FEET; THENCE ALONG THE ARC OF SAID CURVE THROUGH A CENTRAL ANGLE OF 23°27'54" FOR 37.84 FEET TO A POINT OF REVERSE CURVE TO THE LEFT HAVING A RADIUS OF 30.00 FEET AND A CENTRAL ANGLE OF 23°27'54"; THENCE NORTHEAST ALONG THE ARC FOR 246.58 FEET TO A POINT OF REVERSE CURVE TO THE RIGHT HAVING A RADIUS OF 60.00 FEET AND A CENTRAL ANGLE OF 32°32'58"; THENCE SOUTHWESTERLY ALONG THE ARC FOR 83.07 FEET; THENCE S.89°23'58"E. FOR 214.17 FEET TO THE BEGINNING OF A CURVE TO THE RIGHT HAVING A RADIUS OF 100.00 FEET; THENCE ALONG THE ARC OF SAID CURVE THROUGH A CENTRAL ANGLE OF 80°34'02" FOR 186.03 FEET; THENCE NORTH FOR 4.31 FEET; THENCE N.89°23'58"E. FOR 111.51 FEET; THENCE N.82°45'48"E. FOR 30.32 FEET; THENCE S.72°47'31"E. FOR 83.46 FEET; THENCE N.74°03'22"E. FOR 203.81 FEET; THENCE N.89°23'58"E. FOR 124.73 FEET; THENCE S.07°30'02"E. FOR 385.24 FEET TO THE POINT OF BEGINNING.

PARCEL CONTAINS 202,440 SQUARE FEET OR 4.65 ACRES, MORE OR LESS.

SUBJECT TO EASEMENTS, RESTRICTIONS, RESERVATIONS AND RIGHTS-OF-WAY (RECORDED AND UNRECORDED, WRITTEN AND UNWRITTEN).

MAP OF BOUNDARY SURVEY OF COACH HOMES V AT MOODY RIVER ESTATES, BEING PART OF MOODY RIVER ESTATES UNIT TWO, TRACT "MF-2" AND "MF-3", AS RECORDED IN PLAT BOOK 63, PAGES 14 THROUGH 16, PUBLIC RECORDS OF LEE COUNTY, FLORIDA.

THIS BOUNDARY SURVEY MEETS THE MINIMUM TECHNICAL STANDARDS SET FORTH BY THE FLORIDA BOARD OF LAND SURVEYORS, PURSUANT TO SECTION 472.02(2), FLORIDA STATUTES, AND CHAPTER 81017-6, FLORIDA ADMINISTRATIVE CODE. NO OTHER PERSON OR ENTITY MAY RELY UPON THIS SURVEY.

Scott M. Shore 12-13-2005
SCOTT M. SHORE, PROFESSIONAL SURVEYOR AND MAPPER LSE 5743 DATE OF SURVEY

CERTIFICATE OF AUTHORIZATION # LB-7071
NOT VALID WITHOUT THE SIGNATURE AND THE ORIGINAL RAISED SEAL OF A FLORIDA LICENSED SURVEYOR AND MAPPER.
THIS BOUNDARY SURVEY IS ONLY FOR THE LANDS AS DESCRIBED. IT IS NOT A CERTIFICATE OF TITLE, ZONING, EASEMENTS OR FREEDOM OF ENCUMBRANCES.
ABSTRACT NOT REVIEWED.
ALL IMPROVEMENTS SHOWN ARE PROPOSED UNLESS OTHERWISE NOTED.

SURVEYOR'S CERTIFICATE
I HEREBY CERTIFY THAT THIS PLAT OF COACH HOMES V AT MOODY RIVER ESTATES CONDOMINIUM CONSISTING OF SIX (6) PAGES TOGETHER WITH THE DECLARATION OF CONDOMINIUM FOR COACH HOMES V AT MOODY RIVER ESTATES ARE IN SUFFICIENT DETAIL TO IDENTIFY THE COMMON ELEMENTS AND EACH UNIT AND THEIR RELATIVE LOCATIONS AND APPROPRIATE DIMENSIONS.
THE CONSTRUCTION OF THIS CONDOMINIUM IS NOT SUBSTANTIALLY COMPLETE.

Scott M. Shore 12-16-2005
SCOTT M. SHORE, PROFESSIONAL SURVEYOR AND MAPPER
FLORIDA CERTIFICATE NO. 5743 DATE SIGNED

Exhibit C

EXHIBITS PRESENTED AT HEARING

STAFF EXHIBITS

1. *DCD Staff Report with attachments for DCI:* Prepared by Brian Roberts, Manager, Development Services, date received February 26, 2025 (multiple pages – 8.5"x11" & 11"x14") [black & white, color]
2. Affidavit of Publication: For Zoning Case DCI2023-00047, Home Front Heroes Minor CPD (1 page – 8.5"x11")
3. *PowerPoint Presentation:* Prepared by Lee County Staff for DCI2023-00047, Home Front Heroes Minor CPD, dated March 13, 2025 (multiple pages – 8.5"x11")[color]

APPLICANT EXHIBITS

- a. *48-Hour Notice:* Email from Stacy Hewitt to Hearing Examiner, with copies to Brian Robers, Lauren Schaefer, Sandra Kokotilo, Joseph Adams, Esq., Amanda Swindle, Esq., Michael Jacob, Esq., Richard Akin, Esq., and Maria Perez, dated Monday, March 10, 2025, 2:23 PM (multiple pages – 8.5"x11" and 11"x17")
1. *PowerPoint Presentation:* Prepared by Home Front Heroes, Inc., for DCI2023-00047, Home Front Heroes Minor CPD, dated March 13, 2025 (multiple pages – 8.5"x11")[color]
2. *Master Concept Plan:* Prepared by Wilson Miller for Colonial Homes and Home Front Heroes (2 pages – 11"x17" and 24"x36")
3. *Written Submissions:* Email from Stacy Hewitt to Hearing Examiner, with copies to Brian Roberts, Richard Akin, Esq., and Maria Perez, dated Wednesday, March 26, 2025, 1:04 PM (multiple pages – 8.5"x11"){post hearing submittal}

Exhibit D

HEARING PARTICIPANTS

County Staff:

1. Brian Roberts

Applicant Representatives:

1. Richard Akin, Esq.
2. Yury Bykau
3. Stacy Ellis Hewitt
4. Sam Marshall
5. Barrett Stejskal

Public Participants:

1. Joyce Campana
2. Dawn M. Krutz
3. Beth Russo
4. Tom Ward
5. Kirk Woodbury

Exhibit E
INFORMATION

UNAUTHORIZED COMMUNICATIONS

The LDC prohibits communications with the Hearing Examiner or her staff on the substance of pending zoning actions. There are limited exceptions for written communications requested by the Hearing Examiner, or where the Hearing Examiner seeks advice from a disinterested expert.

HEARING BEFORE LEE COUNTY BOARD OF COUNTY COMMISSIONERS

- A. The Hearing Examiner will provide a copy of this recommendation to the Board of County Commissioners.
- B. The Board will hold a final hearing to consider the Recommendation and record made before the Hearing Examiner. The Department of Community Development will notify hearing participants of the final hearing date. Only Parties and participants may address the Board at the final hearing. Presentation by participants are limited to the substance of testimony presented to the Hearing Examiner, testimony concerning the correctness of Findings of Fact or Conclusions of Law contained in the Recommendation, or allegations of relevant new evidence not known or that could not have been reasonably discovered by the speaker at the time of the Hearing Examiner hearing.
- C. Participants may not submit documents to the Board of County Commissioners unless they were marked as Exhibits by the Hearing Examiner. Documents must have the Exhibit number assigned at hearing.

COPIES OF TESTIMONY AND TRANSCRIPTS

- A. Every hearing is recorded. Recordings are public records that become part of the case file maintained by the Department of Community Development. The case file and recordings are available for public examination Monday through Friday between 8:00 a.m. and 4:30 p.m.
- B. A verbatim transcript may also be available for purchase from the court reporting service.